

GENERAL NOTES

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF SIXTEEN SANDBAGS.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITIONS AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS INCLUDED IN THESE PLANS

THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENT PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION, BUT SHALL BE CONSIDERED AS INCLUDED IN THE COST OF THE ASSOCIATED PAY ITEMS.

ELEVATIONS, DIMENSIONS, AND DETAILS INCLUDED IN THE PLANS ARE SUBJECT TO CONSTRUCTION VARIATIONS.

ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. FOR NON-MEMBERS, CONTACT THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

- AmerenIP (ELECTRIC TRANSMISSION)
- AT&T Illinois (COMMUNICATIONS)
- Buckeye Partners, L.P. (PIPELINE)
- Illinois American Water Company (WATER)
- Laclede Pipeline Company (PIPELINE)

MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

THE CONTRACTOR SHALL NOTIFY THE ENGINEER FOURTEEN (14) DAYS PRIOR TO LANE CLOSURES. IN ADDITION, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE LOCAL MoDOT MAINTENANCE TEAM AT LEAST SEVEN (7) DAYS PRIOR TO BEGINNING AND SETTING UP TRAFFIC CONTROL DEVICES.

FILE NAME =	USER NAME = #USER#	DESIGNED - TMB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES I-270 OVER MISSISSIPPI RIVER	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		CHECKED - TSB	REVISED -			270	60B-I-8	MADISON	49	2	
	PLOT SCALE = #SCALE#	DRAWN - TMB	REVISED -			SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.					
	PLOT DATE = 3/23/2011	CHECKED - RAM	REVISED -			ILLINOIS FED. AID PROJECT CONTRACT NO. 76A92					