

F. A. I. ROUTE 270

50% ILLINOIS
50% MISSOURI

SUMMARY OF QUANTITIES

URBAN

CONSTRUCTION
TYPE CODE

CODE NO.	ITEM	UNIT	TOTAL	0014
28100811	STONE DUMPED RIPRAP, CLASS A6	TON	11,200	11,200
50102400	CONCRETE REMOVAL	CU YD	3	3
50104000	BRIDGE RAIL REMOVAL	FOOT	5,409	5,409
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3	3
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	366,400	366,400
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	245	245
50900200	STEEL RAILING, TYPE 2399	FOOT	10,818	10,818
58700300	CONCRETE SEALER	SQ YD	33,634	33,634
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1	1
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	276	276
X0322559	BOLT REPLACEMENT	EACH	72	72
X0324061*	LOG JAM REMOVAL	L SUM	1	1
X6310218*	TRAFFIC BARRIER TERMINAL, TYPE 6, SPECIAL	EACH	2	2
X6331007*	REMOVAL AND REPLACEMENT OF STEEL PLATE BEAM GUARDRAIL, RAIL ELEMENT	FOOT	50	50
Z0001901	JACK AND REPOSITION BEARINGS	EACH	1	1
Z0001905	STRUCTURAL STEEL REPAIR	POUND	515	515
Z0007101*	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES, No. 1	L SUM	1	1
Z0010501*	CLEANING AND PAINTING STEEL BRIDGE, No. 1	L SUM	1	1
Z0010605	CLEANING DRAINAGE SYSTEM	L SUM	1	1
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 IN.)	SQ FT	2,230	2,230
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	11	11
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	97	97
Z0021900	EXPANSION JOINT REPAIR	FOOT	66	66
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1
Z0050400	REMOVE AND REPLACE ANCHOR BOLTS	EACH	4	4
X0327286	SUBSTRUCTURE REPAIR (GROUT BAGS)	L SUM	1	1
X0327285	DOWNSPOUT ADJUSTMENT	EACH	38	38

* SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER#	DESIGNED - TMB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES I-270 OVER MISSISSIPPI RIVER				F.A.I. RTE. 270	SECTION 60B-I-8	COUNTY MADISON	TOTAL SHEETS 49	SHEET NO. 3
#FILE#	PLOT SCALE = #SCALE#	CHECKED - TSB	REVISED -		SCALE: N.T.S.	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 76A92		
	PLOT DATE = 3/23/2011	DRAWN - TMB	REVISED -		ILLINOIS FED. AID PROJECT								
		CHECKED - RAM	REVISED -										