

PAVEMENT PATCHING SCHEDULE										
LOCATION	NORTHBOUND LANE					SOUTHBOUND LANE				
	SIZE		PAVEMENT PATCHING 15"			SIZE		PAVEMENT PATCHING 15"		
	LENGTH	WIDTH	TYPE II	TYPE III	TYPE IV	LENGTH	WIDTH	TYPE II	TYPE III	TYPE IV
MILE STATION	FOOT	FOOT	SQ YD	SQ YD	SQ YD	FOOT	FOOT	SQ YD	SQ YD	SQ YD
0.5	20	12			26.67					
0.7						25	4	11.11		
0.8	6	12	8.00							
1.5						200	3			66.67
2.1	8	12	10.67			15	12		20.00	
2.2						12	12		16.00	
2.32	10	12	13.33							
2.4	10	12	13.33							
2.6						15	4	6.67		
3						15	12		20.00	
3.4	15	5	8.33							
3.5	6	12	8.00			50	4		22.22	
3.7	6	12	8.00			6	12	8.00		
3.9	15	12		20.00						
4.13						10	12	13.33		
4.18	6	12	8.00			6	12	8.00		
4.3	6	12	8.00							
4.4						6	12	8.00		
4.55	80	4			35.56					
4.6	10	12	13.33							
4.61						10	12	13.33		
4.9	30	12			40.00					
5.5	12	12		16.00		12	12		16.00	
5.6	16	12		21.33						
5.8						6	12	8.00		
6.0	10	12	13.33							
SUBTOTAL			112.33	57.33	102.22			76.44	94.22	66.67
ANTICIPATED FAILURE (20%)			22.71	11.54	20.62			15.52	18.91	13.49
TOTAL			135.04	68.87	122.84			91.96	113.13	80.16

TOTAL QTY TYPE II	227.00
-------------------	--------

TOTAL QTY TYPE III	182.00
--------------------	--------

TOTAL QTY TYPE IV	203.00
-------------------	--------

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET NO.	
#FILE#	PLOT SCALE = #SCALE#	DRAWN - ---	REVISED - ---			600	(51,132)RS-4	*	23	8
	PLOT DATE = #DATE#	CHECKED - ---	REVISED - ---			SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT		
		DATE - -----	REVISED - ---			* MONROE, RANDOLPH CONTRACT NO. 76879				