SUMMARY OF QUANTITIES

					ST. CLAIR COUNTY											
				100% STATE URBAN	ROADWAY I-70	CULVERT I-70										
CODE NO.	ITEM	UNIT	TOTAL QUANTITY		CONSTRUCTION TYPE CODE											
					0001	0040										
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	196		196											
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	48		48											
20100500	TREE REMOVAL, ACRES	ACRE	0.7		0.7											
20101000	TEMPORARY FENCE	FOOT	740		740											
20200100	EARTH EXCAVATION	CU YD	27,390		27,390											
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	16,590		16,590											
20400800	FURNISHED EXCAVATION	CU YD	71,240		71,240											
20800150	TRENCH BACKFILL	CU YD	1,303		1,303											
* 25000210	SEEDING, CLASS 2A	ACRE	0.75		0.75											
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68		68											
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68		68											
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68		68											
* 25100115	MULCH, METHOD 2	ACRE	70.75		70.75											
25100630	EROSION CONTROL BLANKET	SQ YD	91,076		91,076											
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20,039		20,039											
28000305	TEMPORARY DITCH CHECKS	FOOT	140		140											
28000400	PERIMETER EROSION BARRIER	FOOT	12,570		12,570											
28000510	INLET FILTERS	EACH	4		4											
28100107	STONE RIPRAP, CLASS A4	SQ YD	311		311											
28200200	FILTER FABRIC	SQ YD	251		251											
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	647		647											
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	13		13											
40701811	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6 1/2"	SQ YD	489		489											
44000100	PAVEMENT REMOVAL	SQ YD	9,340		9,340											
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	13		13											
44004250	PAVED SHOULDER REMOVAL	SQ YD	6		6											
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	91		91											
44201299	DOWEL BARS 1 1/2"	EACH	122		122											
44213200	SAW CUTS	FOOT	297		297											
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	89		89											
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	6		6											

* DENOTES SPECIALTY ITEMS

..\DBCONN-06-BORDER.DGN,..\DBCONN-06-SCO1.DGN,..\DBCONN-99-NOTIF1.DGN,..\DBCONN-06-LEGEND.DGN
2-04-2011, 15:52:02 BONDHUJO \\FS-0044\AMYVAULT\D-TRANS.07\228\228688-006\CIVIL\C4C\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 06\DBCONN-06-SHT-SUMMARY1.DGN

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES 1	F.A.P. RTE. 998 / SECTION 82-1A / COUNTY ST. CLAIR / TOTAL SHEETS 190 / SHEET NO. 4
		DRAWN - JB	REVISED -	I-70 CONNECTION		CONTRACT NO. 76C41
TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -		SCALE: N.T.S. / SHEET NO. OF SHEETS / STA. TO STA.	FED. ROAD DIST. NO. / ILLINOIS / FED. AID PROJECT
	PLOT DATE = $DATE$	DATE - 02/04/11	REVISED -			