TREE REMOVAL (6 TO 15 UNITS DIAMETER) — TOTAL 196 UNIT

LOCATION	STA.	OFF.	SUBTOTALS
I-70	171+59	234' LT	6
I-70	172+46	237' LT	10
I-70	172+49	256' LT	8
I-70	181+86	182' RT	14
I-70	181+89	175' RT	6
I-70	181+92	174' RT	10
I-70	181+94	174' RT	8
I-70	181+94	171' RT	8
I-70	181+95	170' RT	8
I-70	182+51	176' RT	8
I-70	182+53	171' RT	10
I-70	183+01	172' RT	12
I-70	183+38	163' RT	8
I-70	183+43	161' RT	8
I-70	184+02	154' RT	10
I-70	184+10	162' RT	6
I-70	184+34	161' RT	12
I-70	184+53	159' RT	10
I-70	184+93	159' RT	12
I-70	184+97	160' RT	8
I-70	185+03	155' RT	14

TREE REMOVAL (OVER 15 UNITS DIAMETER) — TOTAL 48 UNIT

LOCATION	STATION	OFFSEST	LT/RT	SUBTOTALS
I-70	168+70	342	LT	16
I-70	168+69	317	LT	16
I-70	168+65	277	LT	16

TREE REMOVAL, ACRES — TOTAL 0.7 ACRE

LOCATION	VERTEX I.D.	STATION	OFFSET	RT/LT	AREA SQ FT	SUBTOTALS
I-70	D1	169+80	235	LT		
	D2	171+43	236	LT		
	D3	171+15	414	LT		
	D4	171+10	413	LT		
	D5	170+00	248	LT		
	D6	169+91	253	LT	14,163	0.33
I-70	E1	168+81	380	LT		
	E2	169+09	336	LT		
	E3	169+27	352	LT		
	E4	169+10	385	LT	1,136	0.03
PACKERS	F1	16+02	28	LT		
	F2	16+02	18	LT		
	F3	16+87	19	LT		
	F4	16+87	29	LT	837	0.02
INDUSTRIAL DR	G1	26+76	427	RT		
	G2	26+68	749	RT		
	G3	28+48	364	RT		
	G4	28+97	306	RT		
	G5	28+97	214	RT		
	G6	28+57	226	RT		
	G7	28+56	292	RT		
	G8	28+21	334	RT	13,494	0.31

TEMPORARY FENCE — TOTAL 740 FOOT

LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET	SUBTOTALS
I-70	182+17.85	224	185+07.71	227	407
I-70	171+02.16	-235	174+35.47	-235	333

SEEDING, CLASS 2A — TOTAL 0.75 ACRE

LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET	AREA (SF)	SUBTOTALS
INDUSTRIAL	28+11.90	9.1	28+97.09	264.5	23,896	0.5
EX ST CLAIR	121+68.00	-18.9	120+46.37	-130.5	8,742	0.2

NITROGEN FERTILIZER NUTRIENT — TOTAL 68 POUND
PHOSPHORUS FERTILIZER NUTRIENT — TOTAL 68 POUND
POTASSIUM FERTILIZER NUTRIENT — TOTAL 68 POUND

	ACRES	90 LBS/ACRE	SUBTOTALS
FROM SEEDING CL 2A	0.75	68	68
FROM SEEDING CL 2A	0.75	68	68
FROM SEEDING CL 2A	0.75	68	68

MULCH, METHOD 2 — TOTAL 70.75 ACRE

		SUBTOTALS
EROSION CONTROL BLANKET AREA NOT INCLUDED	TEMPORARY EROSION CONTROL	35.36
	PERMANENT SEEDING	35.35

EROSION CONTROL BLANKET — TOTAL 91,076 SQ YD

LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET		SUBTOTALS
I-70	181+16.23	-140.2	192+55.40	249.5	TEMPORARY	43,066
I-70	181+16.23	-140.2	192+55.40	249.5	PERMANENT	43,066
EX ST CLAIR	121+68.00	-18.9	120+46.37	-130.5	TEMPORARY	710
EX ST CLAIR	121+68.00	-18.9	120+46.37	-130.5	PERMANENT	971
INDUSTRIAL	28+11.90	9.1	28+72.05	272.7	TEMPORARY	427
INDUSTRIAL	28+87.09	265.7	28+97.54	24.9	TEMPORARY	180
INDUSTRIAL	26+97.33	429.3	28+97.54	24.9	PERMANENT	2,655

TEMPORARY EROSION CONTROL SEEDING — TOTAL 20,039 POUND

LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET	AREA (SF)	AREA (AC)	LBS./AC	SUBTOTALS
I-70	148+21.71	-172.5	149+88.77	-224.9	8,678	0.20	450	90
I-70	148+40.92	-150.5	162+00.00	179.5	421,252	9.67	450	4,352
I-70	162+00.00	-232.0	176+00.00	228.6	708,339	16.26	450	7,318
I-70	176+00.00	-232.0	190+00.00	302.3	645,331	14.81	450	6,667
I-70	190+00.00	-232.0	192+55.40	249.5	133,622	3.07	450	1,380
PACKERS	16+85.00	-24.5	15+00.00	23.0	6,349	0.15	450	66
PACKERS	5+30.00	45.0	7+00.00	-12.0	4,320	0.10	450	45
EX ST CLAIR	121+68.00	-18.9	120+46.37	-130.5	6,388	0.15	450	66
INDUSTRIAL	28+11.90	9.1	28+72.05	272.7	3,840	0.09	450	40
INDUSTRIAL	28+87.09	265.7	28+97.54	24.9	1,619	0.04	450	17

RATE OF 450 LBS/AC ASSUMES AN AVERAGE OF 4.5 APPLICATIONS AT 100 LBS PER APPL.

TEMPORARY DITCH CHECKS — TOTAL 140 FOOT

LOCATION	STATION	OFFSET	DIRECTION	SUBTOTALS
I-70	159+10.32	104.9	LT	10
I-70	160+83.37	106.4	RT	10
I-70	162+72.98	216.5	LT	10
I-70	164+32.82	125.4	RT	10
I-70	167+17.09	145.6	LT	10
I-70	171+15.99	137.3	LT	10
I-70	174+53.44	118.8	LT	10
I-70	177+00.18	183.3	RT	10
I-70	177+38.07	107.4	LT	10
I-70	177+39.27	178.4	RT	10
I-70	182+26.49	140.2	RT	10
I-70	182+39.02	106.2	LT	10
I-70	187+47.04	127.5	LT	10
I-70	187+59.10	150.0	RT	10

PERIMETER EROSION BARRIER — TOTAL 12,570 FOOT

LOCATION	FROM STA.	OFFSET	TO STA.	OFFSET	SUBTOTALS
I-70	148+21.7	-172.5	149+88.8	-224.8	233
I-70	148+40.9	-150.5	148+70.7	-117.6	46
I-70	150+08.9	-204.7	150+70.6	-142.8	87
I-70	149+00.0	-87.3	149+66.9	69.1	180
I-70	150+91.4	-122.0	162+00.0	-372.5	1,319
I-70	149+66.9	129.1	153+92.5	168.9	802
I-70	154+20.4	109.3	162+00.0	179.5	889
I-70	162+00.0	-372.5	176+00.0	-232.0	1,895
I-70	162+00.0	179.5	176+00.0	228.6	1,588
I-70	176+00.0	-232.0	190+00.0	-232.0	1,369
I-70	176+00.0	228.6	190+00.0	302.3	1,601
I-70	190+00.0	-232.0	192+50.7	-209.2	273
I-70	190+00.0	302.3	192+51.0	-179.2	702
PACKERS	15+50.0		16+85.0		317
PACKERS	5+29.8		7+00.0		414
INDUSTRIAL DR	28+11.9	9.1	28+72.1	272.7	316
INDUSTRIAL DR	28+87.1	265.7	28+97.6	24.9	249
EX ST CLAIR	121+68.0	-18.9	121+23.9	-84.9	91
EX ST CLAIR	120+90.83	-60.5	120+42.26	-19.0	199

INLET FILTERS — TOTAL 4 EACH

LOCATION	STATION	OFFSET	DIRECTION	SUBTOTALS
I-70	177+13	5	LT	1
I-70	177+13	4.5	RT	1
I-70	177+14	53.1	RT	1
I-70	160+64	106.7	RT	1