

## SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE	
					ROADWAY	I-70 BRIDGE STR NO 082-0312 & 082-0313
					URBAN	
					0001	0008
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	76	76	
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	121	121	
	20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25	
	20200100	EARTH EXCAVATION	CU YD	2,580	2,580	
	20400800	FURNISHED EXCAVATION	CU YD	128,660	128,660	
	20800150	TRENCH BACKFILL	CU YD	1,041	1,041	
	25000210	SEEDING, CLASS 2A	ACRE	7.00	7.00	
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	617	617	
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	617	617	
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	617	617	
	25100115	MULCH, METHOD 2	ACRE	7.00	7.00	
	25100630	EROSION CONTROL BLANKET	SQ YD	14,284	14,284	
	25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	18,401	18,401	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,368	1,368	
	28000305	TEMPORARY DITCH CHECKS	FOOT	67	67	
	28000400	PERIMETER EROSION BARRIER	FOOT	2,870	2,870	
	28100107	STONE RIPRAP, CLASS A4	SQ YD	453	453	
	28200200	FILTER FABRIC	SQ YD	453	453	
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	292	292	
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	255	255	
	44000100	PAVEMENT REMOVAL	SQ YD	1,526	1,526	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	41	41	
	44000300	CURB REMOVAL	FOOT	72	72	
	44000600	SIDEWALK REMOVAL	SQ FT	1,729	1,729	
	44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	46	46	
	50102400	CONCRETE REMOVAL	CU YD	60	60	
	50300225	CONCRETE STRUCTURES	CU YD	170.7		170.7
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,040.8		1,040.8
	50300260	BRIDGE DECK GROOVING	SQ YD	2,607		2,607

• DENOTES SPECIALTY ITEM

FILE NAME = DBTRI-76C50-ah-500-01.dgn	USER NAME = pms@rno	DESIGNED OP	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 998	SECTION 82-1-2HB	COUNTY ST. CLAIR	TOTAL SHEETS 72	SHEET NO. 5
PLOT SCALE = 2.0000' / in.	CHECKED DBM	DATE 03-18-11	REVISED -	SCALE: NONE	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	CONTRACT NO. 76C50		
PLOT DATE = #DATE#	DATE 03-18-11	REVISED -		FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT			