SUMMARY OF QUANTITIES

					100% STATE		
					ROADWAY	I-70 BRIDGE STR NO 082-0312 & 082-0313	
SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0001	0008	
	50300300	PROTECTIVE COAT	SQ YD	2,997		2,997	
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
	50500505	STUD SHEAR CONNECTORS	EACH	6,426		6,426	
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	249,580		249,580	
	50800515	BAR SPLICERS	EACH	212		212	
	51100100	SLOPE WALL 4 INCH	SQ YD	1,090		1,090	
	51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	3,804		3,804	
	51202305	DRIVING PILES	FOOT	3,804		3,804	
	51203200	TEST PILE METAL SHELLS	EACH	4		4	
	51500100	NAME PLATES	EACH	2		2	
	52000030	PREFORMED JOINT SEAL 2½"	FOOT	158		158	
	52100520	ANCHOR BOLTS, 1"	EACH	56		56	
	542A4651	PIPE CULVERTS, CLASS A, TYPE 7 36"	FOOT	280	280		
	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2		
	54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1		
	550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	96	96		
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	288		288	
	60600605	CONCRETE CURB, TYPE B	FOOT	72.0	72.0		
	66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	4	4		
	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1,779	1,779		
	66900450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1	1		
	66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4		
	67100100	MOBILIZATION	L SUM	1	1		
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2		
	72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2		
	81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1,860	1,860		
	81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	1,195		1,195	
	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	600	600		
	X0326385	COMBINED SEWER REMOVAL 21"	FOOT	647	647		

• DENOTES SPECIALTY ITEM