

## SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	TOTAL	100% STATE 0021
	83003600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM	EACH	11	11
	83505400	LIGHT TOWER, 130 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 6	EACH	19	19
	83507800	LIGHT TOWER, 150 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 6	EACH	10	10
	83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	72	72
	83700350	LIGHT TOWER FOUNDATION, 54" DIAMETER	FOOT	475	475
	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	7	7
	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	16	16
	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	24	24
	84200804	REMOVAL OF POLE FOUNDATION	EACH	24	24
	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1	1
	84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1
	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1	1
	X0321631	REMOVAL OF LUMINAIRE	EACH	11	11
	X0322141	REMOVE TEMPORARY WOOD POLE	EACH	34	34
	X0324181	DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	11	11
	X0326492	REMOVAL OF EXISTING SIGN LIGHTING UNIT AND SALVAGE	EACH	7	7
	X0326899	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	3	3
	X8040100	ELECTRIC CONNECTION TO SIGN STRUCTURE	EACH	2	2
	X8130125	REMOVE EXISTING JUNCTION BOX	EACH	13	13
	X8420502	REMOVAL OF LIGHT TOWER, NO SALVAGE	EACH	12	12
	X8430100	REMOVE EXISTING CONDUIT ATTACHED TO STRUCTURE	FOOT	1270	1270
	Z0004002	BOLLARDS	EACH	7	7
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
	+ Z0076602	TRAINEES (SPECIAL)	HOURL	1,500	1,500
	87000240	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (XLP-TYPE TC) 2/C NO. 2 AND NO. 4	FOOT	2690	2690
	87000405	ELECTRIC CABLE ASSEMBLY IN TRENCH, 600V (XLP-TYPE TC) 2/C NO. 2 AND NO. 4	FOOT	22605	22605
	83700400	LIGHT TOWER FOUNDATION, 60" DIAMETER	FOOT	260	260
	X8350010	LIGHT TOWER, 130 FT. MOUNTING HEIGHT, LUMINAIRE MT.-6, SPECIAL	EACH	1	1
	X0327234	LIGHTING UNIT IDENTIFICATION DECAL	EACH	5	5
	X0327235	LOCATING UNDERGROUND UTILITIES	FOOT	1060	1060
	X0327236	TEMPORARY WOOD POLE, 50 FT., CLASS 4	EACH	19	19

• DENOTE SPECIALTY ITEM  
+ 0042

FILE NAME =	USER NAME = lantz	DESIGNED - WDS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
*FILE#		DRAWN - TL	REVISED -			55/64	82-1L	ST. CLAIR	60	6	
	PLOT SCALE = 1:8000 / IN.	CHECKED - JPC	REVISED -			SCALE: NONE		SHEET NO. 2 OF 2 SHEETS		STA. TO STA.	
	PLOT DATE = 1/13/2011	DATE - JANUARY 4, 2011	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					
						CONTRACT NO. 76C54					