

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		100% STATE 0005		CODE NO	ITEM	UNIT		100% STATE 0005	
20400800	FURNISHED EXCAVATION	CU YD	120	120		* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25		63200310	GUARDRAIL REMOVAL	FOOT	1423	1423	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23		67100100	MOBILIZATION	L SUM	1	1	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23		70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
25100115	MULCH, METHOD 2	ACRE	0.25	0.25		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
28100109	STONE RIPRAP, CLASS A5	SQ YD	6	6		70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
28200200	FILTER FABRIC	SO YD	6	6		70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9.7	9.7		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
40600300	AGGREGATE (PRIME COAT)	TON	47	47		70300100	SHORT TERM PAVEMENT MARKING	FOOT	2266	2266	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	773	773		70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	78	78	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	781	781		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15618	15618	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	740	740		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	572	572	
40600990	TEMPORARY RAMP	SO YD	317	317		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	78	78	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1293	1293		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	756	756	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	25	25		* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	78	78	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	10817	10817		* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15618	15618	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	3641	3641		* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	572	572	
44003100	MEDIAN REMOVAL	SO FT	24	24		* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	78	78	
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	668	668		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	116	116	
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SO YD	365	365		* 78200300	PRISMATIC CURB REFLECTOR	EACH	63	63	
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SO YD	19	19		* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	22	22	
44201299	DOWEL BARS 1 1/2"	EACH	920	920		* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
44213100	PAVEMENT FABRIC	SO YD	19	19		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	138	138	
44213200	SAW CUTS	FOOT	1679	1679		80300100	LOCATING UNDERGROUND CABLE	FOOT	50	50	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	338	338		88600600	DETECTOR LOOP REPLACEMENT	FOOT	840	840	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	378	378		Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SO YD	990	990	
58100200	WATERPROOFING MEMBRANE SYSTEM	SO YD	990	990		Z0010615	CLEANING EXISTING INLETS	EACH	2	2	
60403500	GRATES, TYPE B	EACH	4	4		Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	200	200	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3	3		Z0036200	PAINT CURB	FOOT	286	286	
* 63000001	STEEL PLATE BEAM GUARDRAIL TYPE A, 6 FOOT POSTS	FOOT	862.5	862.5							
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4							
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6							

\*SPECIALTY ITEM

FILE NAME #	USER NAME # *USER#	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 9185	SECTION 10-IRS-1	COUNTY ST. CLAIR	TOTAL SHEETS 25	SHEET NO. 3	
#FILEL#		DRAWN - ---	REVISED - ---								
	PLOT SCALE # *SCALE#	CHECKED - ---	REVISED - ---								
	PLOT DATE # *DATE#	DATE - ---	REVISED - ---								
						SCALE: _____		SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____	
						FED. ROAD DIST. NO. _ [ILLINOIS] FED. AID PROJECT					