

P.C.C PAVEMENT CONCRETE SCHEDULE					
LOCATION			AGG. BASE COURSE, TYPE A 12"	P.C.C. PAVEMENT 9"	PROTECTIVE COAT
STA.	to	STA.	(TON)	(SQ YD)	(SQ YD)
58+38.20	to	58+55.73	2.68	3.82	3.82
58+55.73	to	58+62.08	1.23	1.76	1.76
58+62.08	to	255+69.59	35.63	50.90	50.90
255+69.59	to	255+53.90	8.98	12.83	12.83
255+53.90	to	255+09.08	18.35	26.22	26.22
255+09.08	to	254+61.12	7.46	10.66	10.66
TOTALS			75	107	107

SHOULDER/CURB SCHEDULE								
LOCATION			PAVED SHOULDER REMOVAL	P.C.C SHOULDERS 9"	AGG. BASE COURSE, TYPE A	PROTECTIVE COAT	AGG. SHOULDERS TYPE B	CONCRETE CURB, TYPE B
STA.	to	STA.	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(TON)	(FOOT)
57+37.08	to	58+38.20					9.83	
58+38.20	to	58+62.08	9.76	34.17	23.92	34.17		17.20
58+62.08	to	255+69.59	68.47	118.13	82.68	118.13		85.00
255+69.59	to	255+53.90	17.30	18.89	13.22	18.89		17.00
255+53.90	to	255+09.08	49.33	46.90	32.83	46.90		43.74
255+09.08	to	254+61.12	51.42	44.18	30.92	44.18		47.96
TOTALS			196	263	184	263	10	211

LOCATION			PAVEMENT MARKING REMOVAL	PREFORMED PLASTIC						POLYUREA			RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS	COMMENTS
				4"		8"		GROOVING FOR RECESSED PAV. MARKING 5"	GROOVING FOR RECESSED PAV. MARKING 9"	12"	24"	LETTERS & SYMBOLS			
				SOLID YELLOW	SKIP-DASH WHITE	SOLID WHITE	SOLID WHITE			SOLID WHITE	STOP BARS				
STATION	TO	STATION	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	
55+18.50	TO	57+18.50			67			67							
57+18.50	TO	58+74.00	145			156		156				31.2	2	4	
58+74.00	TO	60+33.00	115		36			36							
60+33.00	TO	62+03.00				171		171				31.2	2	5	
62+03.00	TO	63+68.00			55			55							
US 67 (L.T.)															
254+61.20	TO	256+45.00	220	143		414	343	557	343	213	26		12	19	
US 67 (RT.)															
254+61.20	TO	256+45.00	120	143		605	225	748	225	144	42	46.8	12	19	
SUB-TOTALS			600	286	158	1346	568	1790.00	568.00	357	68	109.20	28.00	47.00	
TOTAL			600		1790		568	1790	568	357	68	110	28	47	

FILE NAME *	USER NAME * #USER#	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>	F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - ---	REVISED - ---			304/2	4061-2	MADISON	19	6	
		CHECKED - ---	REVISED - ---			SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 76E60			
		DATE - -----	REVISED - ---			FED. ROAD DIST. NO. _____ [ILLINOIS] FED. AID PROJECT					