

SUMMARY OF QUANTITIES

90% FEDERAL
10% STATE

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021 ST. CLAIR CO.	0021 CLINTON CO.	0021 MARION CO.	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	-----	-----	-----
20200100	EARTH EXCAVATION	CU YD	71	16	55								
20400800	FURNISHED EXCAVATION	CU YD	4605	40.5	4559	5.5							
25000210	SEEDING, CLASS 2A	ACRE	3.75	0.13	3.5	0.12							
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	338	12	315	11							
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	338	12	315	11							
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	338	12	315	11							
25000700	AGRICULTURAL GROUND LIMESTONE	TON	7.5	0.1	7.3	0.1							
25100630	EROSION CONTROL BLANKET	SQ YD	17669	240.5	17299	129.5							
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4315	60	4218.5	36.5							
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	9037.5	225	8112.5	700							
63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	325	50	275								
63000350	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FT 6 IN SPAN	FOOT	2925		2925								
63000370	LONG-SPAN GUARDRAIL OVER CULVERT, 25 FT SPAN	FOOT	525		525								
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	10		8	2							
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4								
63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	12		12								
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	86	3	81	2							
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	10		7	3							
63200310	GUARDRAIL REMOVAL	FOOT	15235	472	13719	984							
63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	228	33	195								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	0.2	4.4	0.4							
67100100	MOBILIZATION	L SUM	1	0.1	0.8	0.1							
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.1	0.8	0.1							
78200410	GUARDRAIL MARKERS, TYPE A	EACH	202	5	185	12							
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	96	3	88	5							

▲ REVISÉD 6-3-11

FILE NAME =	USER NAME = jconoverpj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\p\work\p\dot\conoverpj\d8249112\sh...	ts_engadvgn	DRAWN -	REVISED -			*	DB GUARDRAIL UPDATE 2011	VARIOUS	37	4	
	PLOT SCALE = 50.0000" / IN.	CHECKED -	REVISED -								
	PLOT DATE = 3/24/2011	DATE -	REVISED -								
						SCALE: _____		SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____	
						CONTRACT NO. 76E78					