

SCHEDULE OF PAVEMENT QUANTITIES												
LOCATION		HOT-MIX ASPHALT SURFACE REMOVAL, 2-1/4"	PORTLAND CEMENT CONCRETE SURFACE REMOVAL, 2-1/4"	BITUMINOUS MATERIALS (PRIME COAT)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90, 2-1/4"	MATERIAL TRANSFER DEVICE	JOINT OR CRACK FILLING	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	NOTES			
APPLICATION RATE:		SQ YD		TON	TON	TON	POUND	EACH				
DIRECTION	STA.	TO STA.										
ST. CLAIR COUNTY												
NB	1232+48	TO 1233+73	489.3		0.20	71.7	71.7	100	1.0	3 THROUGH LANES; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
NB	1236+37	TO 1237+92	608.7		0.25	86.7	86.7	124		3 THROUGH LANES; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
NB	1237+92	TO 1239+59		650.4	0.27	82.0	82.0	134		3 THROUGH LANES		
SB	1232+26	TO 1233+60	524.7		0.22	76.1	76.1	107		3 THROUGH LANES; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
SB	1236+24	TO 1237+55	513.3		0.21	74.7	74.7	105		3 THROUGH LANES; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
SB	1237+55	TO 1239+37		698.0	0.29	87.9	87.9	146		3 THROUGH LANES		
			SUBTOTAL:	2136	1348	1.4	479	720	1			
MADISON COUNTY												
NB	1239+59	TO 1242+36		1125.6	0.47	141.8	141.8	222		3 THROUGH LANES		
NB	1242+36	TO 1243+76	537.8		0.22	77.8	77.8	112		3 THROUGH LANES; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
NB	1245+72	TO 1246+31	213.4		0.09	36.9	36.9	47		3 THROUGH LANES; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
NB	1246+31	TO 1247+07		202.7	0.08	25.5	25.5	61		2 OUTER LANES		
NB	1247+07	TO 1257+60	2808.0		1.17	353.8	353.8	842		2 OUTER LANES		
NB	1257+60	TO 1261+24	1587.1		0.66	200.0	200.0	291	1.0	2 OUTER LANES AND 1 AUX. LANE		
NB	1261+24	TO 1262+30		144.8	0.06	18.2	18.2	85		1 AUX. LANE		
NB	1261+24	TO 1284+25	6178.9		2.58	778.5	778.5	1941	1.0	2 OUTER LANES		
NB	1284+25	TO 1285+80		413.3	0.17	52.1	52.1	124		2 OUTER LANES		
NB	1285+80	TO 1287+55		233.3	0.10	29.4	29.4	140		1 MIDDLE LANE		
NB	1295+91	TO 1301+48		1485.3	0.62	187.2	187.2	446	1.0	2 OUTER LANES		
NB	1301+48	TO 1302+83	452.2		0.19	67.0	67.0	108		3 THROUGH LANES; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
NB	1308+67	TO 1328+97		8120.0	3.39	1023.1	1023.1	1624	1.0	3 THROUGH LANES		
NB	1353+10	TO 1354+50		695.5	0.29	97.6	97.6	112		3 THROUGH LANES; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
SB	1239+37	TO 1242+08		1112.8	0.46	140.2	140.2	217		3 THROUGH LANES		
SB	1242+08	TO 1243+45	901.9		0.38	123.6	123.6	110	1.0	3 THROUGH LANES AND 1 AUX. LANE; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
SB	1245+38	TO 1246+52	570.8		0.24	81.9	81.9	91		3 THROUGH LANES AND 1 AUX. LANE; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
SB	1246+52	TO 1275+25	7618.3		3.18	959.9	959.9	2298		2 OUTER LANES		
SB	1272+75	TO 1275+25		333.4	0.14	42.0	42.0	200	1.0	1 INSIDE LANE		
SB	1275+25	TO 1278+50		866.7	0.36	109.2	109.2	260		2 INSIDE LANES		
SB	1278+50	TO 1280+00		600.0	0.25	75.6	75.6	120		3 THROUGH LANES		
SB	1280+00	TO 1282+25		300.0	0.13	37.8	37.8	180		1 MIDDLE LANE		
SB	1298+70	TO 1301+22		692.6	0.29	87.3	87.3	202	1.0	2 OUTER LANES		
SB	1310+10	TO 1331+86		8714.0	3.64	1098.0	1098.0	1741	1.0	3 THROUGH LANES		
SB	1353+58	TO 1354+99		695.5	0.29	97.6	97.6	113		3 THROUGH LANES; 10 TONS P HMA SC "E" N90 ADDED FOR STRUCT APPCH		
			SUBTOTAL:	20868	25736	19.5	5941	11590	8			
PROJECT TOTAL												
			TOTAL:	23004	27084	20.9	6420	12310	9			

SCHEDULE OF PAVEMENT MARKING														
LOCATION		THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	NOTES
LOCATION:		INSIDE PAVEMENT EDGE MARKING, SOLID YELLOW LINE	WHITE SKIPPED DASH LINE DIVIDING INSIDE AND MIDDLE LANE	WHITE SKIPPED DASH LINE DIVIDING MIDDLE AND OUTSIDE LANE	OUTSIDE PAVEMENT EDGE MARKING, SOLID WHITE LINE	SOLID WHITE LINE DIVIDING OUTSIDE AND AUX. LANE	WHITE DOTTED LINE DIVIDING OUTSIDE AND AUX. LANE	MARKERS DIVIDING INSIDE AND MIDDLE LANE	MARKERS DIVIDING MIDDLE AND OUTSIDE LANE	MARKERS DIVIDING OUTSIDE AND AUX. LANE	ALL LANES	ALL LANES	ALL LANES	
DIRECTION	STA.	TO STA.	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	FOOT	SQ. FT.	
ST. CLAIR COUNTY														
NB	1232+48	TO 1233+73	120	31	31	125		4	4		8	35	12	3 THROUGH LANES
NB	1236+37	TO 1239+59	313	77	77	316		8	8		16	87	29	3 THROUGH LANES
SB	1232+26	TO 1233+60	134	33	33	129		4	4		8	37	12	3 THROUGH LANES
SB	1236+24	TO 1239+37	313	76	76	305		8	8		16	86	29	3 THROUGH LANES
			SUBTOTAL:	880	217	217	875	0	0	0	24	245	82	
MADISON COUNTY														
NB	1239+59	TO 1243+76	414	104	104	415		10	10		20	116	39	3 THROUGH LANES
NB	1245+72	TO 1246+31	59	14	13	48		2	2		4	15	5	3 THROUGH LANES
NB	1246+31	TO 1247+07			19	76			2		2	11	4	2 OUTER LANES
NB	1247+07	TO 1257+60			263	1053			26		26	147	49	2 OUTER LANES
NB	1257+60	TO 1261+24			91	434	70	19	8	6	14	131	44	2 OUTER LANES AND 1 AUX. LANE
NB	1261+24	TO 1262+30				106						4	1	1 AUX. LANE
NB	1261+24	TO 1284+25			575	246	830	345	56	34	90	1208	403	2 OUTER LANES
NB	1284+25	TO 1285+80			155	155			4		4	68	23	2 OUTER LANES
NB	1285+80	TO 1287+55			44				4		4	18	6	1 MIDDLE LANE
NB	1295+91	TO 1301+48		139		323	234		14		14	358	119	2 OUTER LANES
NB	1301+48	TO 1302+83	113	30	32	135			4		8	35	12	3 THROUGH LANES
NB	1308+67	TO 1328+97	2030	508	508	2030			50	50	100	569	190	3 THROUGH LANES
NB	1353+10	TO 1354+50	141	34	33	120			4		8	162	54	3 THROUGH LANES
SB	1239+37	TO 1243+45	411	103	102	409			10	10	20	239	80	3 THROUGH LANES AND 1 AUX. LANE
SB	1245+38	TO 1246+52	100	26	28	114			2	4	2	100	33	3 THROUGH LANES AND 1 AUX. LANE
SB	1246+52	TO 1275+25			19	892			2	24	26	139	46	2 OUTER LANES
SB	1272+75	TO 1275+25	250	718					18		18	297	99	1 INSIDE LANE
SB	1275+25	TO 1278+50	325	81	21				8	8	16	54	18	2 INSIDE LANES
SB	1278+50	TO 1280+00	150	38	38	150			4	4	8	42	14	3 THROUGH LANES
SB	1280+00	TO 1282+25				57					6	23	8	1 MIDDLE LANE
SB	1298+70	TO 1301+22			63	252					6	35	12	2 OUTER LANES
SB	1310+10	TO 1331+86	635	544	544	2176	1200	341	54	54	116	1884	628	3 THROUGH LANES
SB	1353+58	TO 1354+99	4628	2339	2848	9134	2648	956	180	278	74	532	1885	3 THROUGH LANES
			SUBTOTAL:	9256	4679	5696	18268	5296	1912	380	556	148	11311	3772
PROJECT TOTAL														
			TOTAL:	10136	4895	5913	19143	5296	1912	384	580	148	11112	3854