

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	STP FUNDING 80% FEDERAL 20% STATE	CONSTRUCTION TYPE CODE	CODE NUMBER	ITEM DESCRIPTION	UNIT	STP FUNDING 80% FEDERAL 20% STATE	CONSTRUCTION TYPE CODE
				0040 SN073-7073					0040 SN073-7073
20200100	EARTH EXCAVATION	CU YD		389	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO.		3
20700220	POROUS GRANULAR EMBANKMENT	CU YD		122	67100100	MOBILIZATION	L SUM		1
* 25000200	SEEDING, CLASS 2	ACRE		0.16	70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH		1
* 25000350	SEEDING, CLASS 7	ACRE		0.16	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM		1
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND		15	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM		1
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND		15	70103815	TRAFFIC CONTROL AND SURVEILLANCE	CAL DA		2
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND		15	70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH		1
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON		0.32	70106800	CHANGEABLE MESSAGE SIGN	CAL MO		1
* 25100115	MULCH, METHOD 2	ACRE		0.16	70300100	SHORT TERM PAVEMENT MARKING	FOOT		45
* 25100630	EROSION CONTROL BLANKET	SQ YD		763	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT		547
28000250	TEMPORARY EROSION CONTOL SEEDING	POUND		16	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT		198
28000305	TEMPORARY DITCH CHECKS	FOOT		16	70400100	TEMPORARY CONCRETE BARRIER	FOOT		312.5
28000400	PERIMETER EROSION BARRIER	FOOT		409	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT		212.5
28100105	STONE RIPRAP, CLASS A3	SQ YD		55	* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT		547
28200200	FILTER FABRIC	SQ YD		55	78300100	PAVEMENT MARKING REMOVAL	SQ FT		183
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD		116	86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH		1
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD		235	XZ137300	TEMPORARY SHORING	L SUM		397
42001300	PROTECTIVE COAT	SQ YD		235	Z0026407	TEMPORARY SHEET PILING	SQ FT		
44000100	PAVEMENT REMOVAL	SQ YD		189	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH		2
48101600	AGGREGATE SHOULDERS, TYPE B 8''	SQ YD		16	Z0030260	IMPACT ATTENUATORS TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH		1
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH		1	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH		2
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND		25,800					
50800515	BAR SPLICERS	EACH		80					
51500100	NAME PLATES	EACH		1					
54003000	CONCRETE BOX CULVERTS	CU YD		87.6					

* SPECIALTY ITEM

⚠ REVISSED 6-6-11