

INDEX OF SHEETS

| SHEET NO. | DESCRIPTION |
|-----------|--------------------------------------------------------------|
| 1 | COVER SHEET |
| 2 | SIGNATURE SHEET |
| 3 | INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES |
| 4 | MIXTURE REQUIREMENTS / STRUCTURE INFORMATION SCHEDULE |
| 5 | SUMMARY OF QUANTITIES |
| 6-7 | TYPICAL SECTIONS |
| 8-9 | RESURFACING SCHEDULE |
| 10 | PAVEMENT MARKING SCHEDULE |
| 11-20 | PLAN LAYOUT FOR FAS 2826 (IL 37) STA 559+00 TO STA 864+27.79 |
| 21 | DETAIL: TEMPORARY RAMP, SAFETY EDGE |
| 22 | DETAIL: SIDE ROADS |
| 23 | DETAIL: PAVEMENT TRANSITION |
| 24 | STANDARD DETAILS: TEMP HOT-MIX ASPHALT TRANSITIONS |
| 25 | STANDARD DETAILS: ROUGH GROOVED SURFACE SIGN; UNEVEN LANES |

HIGHWAY STANDARDS

| | |
|-----------|-----------|
| 442201-03 | 701311-03 |
| 701011-02 | 701336-06 |
| 701201-04 | 701901-01 |
| 701301-04 | 780001-02 |
| 701306-03 | 781001-03 |

GENERAL NOTES

THE THICKNESS OF BITUMINOUS MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATION OCCURS DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.

FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS AND SHALL NOT BE USED FOR THE BASIS OF FINAL QUANTITIES EXCEPT FOR QC/QA OF BITUMINOUS MIXTURES:

ALL HOT-MIX ASPHALT.....2.016 TONS/CU. YD.

ALL AGGREGATE.....2.05 TONS/CU. YD.

BITUMINOUS MATERIALS (PRIME COAT)

ON PAVEMENT....0.09 GALS/SQ. YD.

ON AGG. SURFACE....0.32 GALS/SQ. YD.

AGGREGATE (PRIME COAT).....0.0015 TONS/SQ. YD.

THE QUANTITY OF SHORT TERM PAVEMENT MARKING SHOWN IN THE PLANS WAS BASED ON ONE APPLICATION EACH FOR THE PRIME COAT, SURFACE COURSE AND LEVELING BINDER.

PRIOR TO PLACEMENT OF THE FINAL PAVEMENT MARKINGS, THE RESIDENT ENGINEER SHOULD CONTACT THE BUREAU OF OPERATIONS AND ARRANGE FOR INSPECTION AND APPROVAL OF THE PAVEMENT MARKING LAYOUT.

THE CONTRACTOR SHALL STAMP STATIONING IN THE PROPOSED BITUMINOUS MATS AT 300 FT. INTERVALS ON ALTERNATING SIDES OF THE PAVEMENT AND AS DIRECTED BY THE ENGINEER. THE STATION SYMBOL STAMPS USED SHALL BE FURNISHED BY THE CONTRACTOR. THEY SHALL BE 5 1/2 "TALL OF A DESIGN APPROVED BY THE ENGINEER AND SHALL REMAIN THE PROPERTY OF THE CONTRACTOR.

UNLESS OTHERWISE DIRECTED BY THE ENGINEER, BITUMINOUS RESURFACING SHALL BE PLACED IN A SEQUENCE THAT WILL MINIMIZE THE TIME THE CENTER -LINE EDGE IS EXPOSED TO TRAFFIC.

QUANTITIES SHOWN IN THE PLANS FOR PATCHING ARE ESTIMATES. THE ACTUAL AMOUNT OF PATCHING REQUIRED SHALL BE DETERMINED BY THE ENGINEER IN THE FIELD.

THE CONTRACTOR SHALL COMPLETE ALL PATCHING PRIOR TO THE BITUMINOUS SURFACE REMOVAL.

RECLAIMED ASPHALT PAVEMENT (RAP) WILL NOT BE ALLOWED FOR USE AS AGGREGATE IN AGGREGATE SHOULDERS, TYPE B.

* FAS 2826

** (109RS-2, 110RS-2, 110-2RS)

| | | | | | | | | | | |
|---------------------------------------------|------------------------------|------------|-----------|-----------------------------------------------------------|--------------------------------------------------|--------------|---------|---------------------------------|-----------------|--------------------------|
| FILE NAME = | USER NAME = ejobr.js | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | INDEX OF SHEETS, STANDARDS, GEN NOTES | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| ca:\pvt\work\pvt\dot\eybor.js\d0256359\bl78 | 85-shr-plandgn | DRAWN - | REVISED - | | | | | JEFFERSON | 25 | 3 |
| | PLOT SCALE = 1/8" = 1' / IN. | CHECKED - | REVISED - | | | | | | | |
| | PLOT DATE = 3/17/2011 | DATE - | REVISED - | | | | | | | CONTRACT NO. 78185 |
| | | | | | | SCALE: _____ | | SHEET NO. _____ OF _____ SHEETS | | STA. _____ TO STA. _____ |
| ILLINOIS FED. AID PROJECT | | | | | | | | | | |