

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SIGNATURE SHEET
3	GENERAL NOTES, COMMITMENTS, INDEX, STANDARDS
4	SUMMARY OF QUANTITIES
5 - 13	SCHEDULES OF QUANTITIES
15 - 24	PIER PROTECTION PLAN SHEETS
25-38	GUARDRAIL PLAN SHEETS
39-40	PROJECT DETAILS HIGHWAY STANDARDS

HIGHWAY STANDARDS

000001-06	701101-02
001001-02	701406-06
	701901-01
280001-05	701400-05
542301-03	
542311-02	
630001-09	
631011-07	
631026-05	
631031-09	
635001-01	
635006-03	
635011-02	

GENERAL NOTES

EXISTING PIPE UNDERDRAIN OUTLETS AND DRAINAGE STRUCTURES IN THE MEDIAN SLOPES SHALL BE PRESERVED AND PROTECTED DURING CONSTRUCTION. ANY DAMAGE TO AN UNDERDRAIN OUTLET RESULTING FROM CONSTRUCTION ACTIVITY SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

TWO APPLICATIONS OF TEMPORARY EROSION CONTROL SEEDING HAVE BEEN INCLUDED. THE ACTUAL QUANTITY, LOCATIONS, AND APPLICATIONS SHALL BE AS DIRECTED BY THE ENGINEER. THE APPLICATION RATE SHALL BE AS PER ARTICLE 280.04(f).

REVISE THE FIRST SENTENCE OF ARTICLE 107.09 PUBLIC CONVENIENCE AND SAFETY TO THE FOLLOWING "THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST 14 DAYS IN ADVANCE OF STARTING ANY CONSTRUCTION WORK. THIS ADDITIONAL INFORMATION IS REQUIRED SO THAT THE PUBLIC CAN BE NOTIFIED OF THE PENDING CONSTRUCTION."

CONNECTING OF NEW OR EXISTING PIPE CULVERTS TO NEW OR EXISTING INLETS OR MANHOLES SHALL BE MADE IN A MANNER WHICH RESULTS IN A NEAT AND WATERTIGHT JOINT. WHEN PLACED THROUGH THE WALL OF AN INLET OR MANHOLE, THE PIPE CULVERT SHALL BE PLACED OR CUT FLUSH WITH THE FACE OF THE WALL AND DRESSED WITH MORTAR TO PROVIDE A SMOOTH ROUNDED OR BEVELED EDGE. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT UNIT PRICES OF THE PIPE CULVERTS OR STRUCTURES INVOLVED.

THE 1/4" PLATE STEEL SHOWN IN THE ATTENUATOR BASE DRAIN DETAIL SHALL BE INCLUDED IN THE UNIT PRICE FOR ATTENUATOR BASE.

COMMITMENTS

NONE

FILE NAME =	USER NAME = shepardgd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, COMMITMENTS, INDEX, STANDARDS	F.A.I. RTE.	SECTION	COUNT /	TOTAL SHEETS	SHEET NO.
ca:\pwork\pwork\shepardgd\239675\78228-ahf-misc.dgn		DRAWN -	REVISED -			VAR	D9 SAFETY 2011-1	VARIOUS	165	3
PLOT SCALE = 1/32" = 1" IN.		CHECKED -	REVISED -			CONTRACT NO. 78228				
PLOT DATE = 3/4/2011		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				
SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____										