

# SUMMARY OF QUANTITIES

## VARIOUS

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HSIP 90% FEDERAL / 10% STATE										
				JEFFERSON COUNTY	JEFFERSON COUNTY	JOHNSON COUNTY	JOHNSON COUNTY	MASSAC COUNTY	WHITE COUNTY	PULASKI COUNTY	UNION COUNTY	WILLIAMSON COUNTY	WILLIAMSON COUNTY	FRANKLIN COUNTY
				I-57 0021	I-64 0021	I-24 0021	I-57 0021	I-24 0021	I-64 0021	I-57 0021	I-57 0021	I-57 0021	I-24 0021	I-57 0021
Z0002005	ATTENUATOR BASE	SO YD	1435.5			148.5		99		297	297	594		
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	29			3		2		6	6	12		
20200100	EARTH EXCAVATION	CU YD	3626.3			228.3		9.8		253.6	1450.4	1439.8		244.4
20400800	FURNISHED EXCAVATION	CU YD	3890.2			554.4		418.0		293.8	745.2	1590.6		288.2
25000200	SEEDING, CLASS 2	ACRE	11.3			1.0		0.6		2.1	3.1	3.8		0.7
25000350	SEEDING, CLASS 7	ACRE	11.3			1.0		0.6		2.1	3.1	3.8		0.7
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1817			160		94		330	502	612		119
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1364			120		71		248	377	459		89
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1364			120		71		248	377	459		89
25000700	AGRICULTURAL GROUND LIMESTONE	TON	22.7			2.0		1.2		4.1	6.3	7.6		1.5
25100115	MULCH, METHOD 2	ACRE	22.7			2.0		1.2		4.1	6.3	7.6		1.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2476			200		118		616	628	765		149
28000305	TEMPORARY DITCH CHECKS	FOOT	480			60		48		48	84	228		12
28000500	INLET AND PIPE PROTECTION	EACH	7								1	4		2
50102400	CONCRETE REMOVAL	CU YD	15.5							15.5				
50104400	CONCRETE HEADWALL REMOVAL	EACH	1											1
50105220	PIPE CULVERT REMOVAL	FOOT	4											4
50300225	CONCRETE STRUCTURES	CU YD	46.4			5.2		18		7.7		15.5		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4260			440		1510		830		1480		
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	425								405			20
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3								2			1
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	3								2			1
54248510	CONCRETE COLLAR	CU YD	0.5								0.5			
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	24136.5	4,838	4,263	1087.5	950	950	587.5		4987.5	4812.5	950	712.5
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	72	17	15	3	3	3	2		10	15	3	1
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2								2			
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1								1			
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	70	17	13	3	3	3	2		9	15	3	2
63200310	GUARDRAIL REMOVAL	FOOT	250								200			50
63500105	DELINEATORS	EACH	3								2			1
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	6	0.5	0.5	0.5	0.5	1	0.5	0.5	0.5	0.5	0.5	0.5
67100100	MOBILIZATION	L SUM	1	0.10	0.10	0.10	0.10	0.10	0.10		0.1	0.1	0.1	0.1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.10	0.10	0.10	0.10	0.10	0.10		0.1	0.1	0.1	0.1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	1.50	1.50	1.00	1.00	1.00	1.00	1	1	1	1	1
78200410	GUARDRAIL MARKERS, TYPE A	EACH	413	82.00	71.00	18.00	17.00	17.00	15.00		77	86	17	13
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	70	17.00	13.00	3.00	3.00	3.00	2.00		9	15	3	2