

# ROADWAY SCHEDULES

TRAFFIC BARRIER TERMINAL, TYPE 6A		
STATION	EACH	REMARKS
BETHEL ROAD		
RT 18+74.31	1	
LT 18+79.60	1	
RT 20+99.92	1	
LT 21+04.21	1	
PROJECT TOTAL	4	

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		
STATION	EACH	REMARKS
BETHEL ROAD		
RT 19+25.79	1	
LT 19+31.08	1	
RT 20+55.77	1	
LT 20+61.06	1	
PROJECT TOTAL	4	

FURNISHING AND ERECTING RIGHT OF WAY MARKERS		
STATION	EACH	REMARKS
BETHEL ROAD		
45.00' LT STA. 18+00.00	1	
45.00' RT STA. 18+00.00	1	
110.00' LT STA. 19+00.00	1	
85.00' RT STA. 19+68.00	1	
85.00' RT STA. 22+37.00	1	
110.00' LT STA. 23+00.00	1	
PROJECT TOTAL	6	

PERMANENT SURVEY MARKERS, TYPE I		
STATION	EACH	REMARKS
BETHEL ROAD		
STA. 20+15	1	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	1	

MOBILIZATION		
STATION	L SUM	REMARKS
BETHEL ROAD		
ENTIRE PROJECT	1	
PROJECT TOTAL	1	

GUARDRAIL MARKERS, TYPE A		
STATION	EACH	REMARKS
BETHEL ROAD		
RT 18+74.31	4	
LT 18+79.60	4	
RT 20+99.92	4	
LT 21+04.21	4	
PROJECT TOTAL	16	

TERMINAL MARKER - DIRECT APPLIED		
STATION	EACH	REMARKS
BETHEL ROAD		
RT 18+74.31	1	
LT 18+79.60	1	
RT 20+99.92	1	
LT 21+04.21	1	
PROJECT TOTAL	4	

SEEDING, CLASS 2 (SPECIAL)		
STATION	ACRE	REMARKS
BETHEL ROAD		
LT 18+00 - 20+17	0.27	
RT 18+00 - 19+77	0.24	
RT 19+40	0.07	TEMPORARY DRAIN. EASEMENT
RT 20+07	0.06	TEMPORARY DRAIN. EASEMENT
RT 20+06 - 22+37	0.28	
LT 20+35 - 23+29	0.15	
LT 20+71 - 23+93	0.40	
PROJECT TOTAL	1.47	

SEEDING, CLASS 7 (SPECIAL)		
STATION	ACRE	REMARKS
BETHEL ROAD		
LT 18+00 - 20+17	0.27	
RT 18+00 - 19+77	0.24	
RT 19+40	0.07	TEMPORARY DRAIN. EASEMENT
RT 20+07	0.06	TEMPORARY DRAIN. EASEMENT
RT 20+06 - 22+37	0.28	
LT 20+35 - 23+29	0.15	
LT 20+71 - 23+93	0.40	
PROJECT TOTAL	1.47	

WOVEN WIRE FENCE (SPECIAL)		
STATION	FOOT	REMARKS
BETHEL ROAD		
LT 18+00 - 18+40	48	
RT 18+00 - 22+37	442	
LT 18+60 - 20+10	159	
LT 20+33 - 21+85	152	
PROJECT TOTAL	800	

TRAFFIC CONTROL AND PROTECTION, (SPECIAL)		
STATION	L SUM	REMARKS
BETHEL ROAD		
ENTIRE PROJECT	1	
PROJECT TOTAL	1	

BREAKER-RUN CRUSHED STONE		
STATION	TON	REMARKS
BETHEL ROAD		
CONTINGENCY ITEM	205	AS DIRECTED BY ENGINEER
PROJECT TOTAL	205	

CONSTRUCTION LAYOUT		
STATION	L SUM	REMARKS
BETHEL ROAD		
ENTIRE PROJECT	1	
PROJECT TOTAL	1	

FENCE REMOVAL		
STATION	FOOT	REMARKS
BETHEL ROAD		
RT 18+00 - 19+69	180	
LT 18+00 - 19+63	166	
RT 20+31 - 22+36	217	
LT 20+42 - 22+01	109	
LT 21+88 - 21+96	33	
PROJECT TOTAL	705	

FILE = S:\PROJECTS\2010\1183\_JoDavless\_County\_Bethel\_Road\_DESIGN\1183TYP\cds.dgn

REV.	DATE	BY	REMARKS	DRAWN
				M.P.O.
				CHECKED
				D.L.B.
				APPROVED
				X.X.X.

**JO DAVIESS COUNTY  
BRIDGE REPLACEMENT  
EAST BETHEL ROAD OVER LITTLE RUSH CREEK  
2011**

**WILLET, HOFMANN & ASSOCIATES, INC.**  
CONSULTING ENGINEERS  
Land Surveying - Transportation - Structural  
Environmental - Architecture  
800 East Second Street Dixon, Illinois 61021  
Phone 815.284.3381 Fax 815.284.3385  
Design Firm #194-000918  
www.willett-hofmann.com

ROADWAY SCHEDULES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
10-00134-00-BR	JO DAVIESS	34	5
STA. - STA.			
WHA PROJECT: 1183D10	DATE: 1/2011		