

SCHEDULE OF QUANTITIES

TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TEMPORARY DITCH CHECKS	PIPE UNDERDRAINS 6"						
LOCATION	UNIT	REMARKS	LOCATION	FOOT	REMARKS	LOCATION	FOOT	REMARKS
STA. 12+11 LT. 27'	8		RT. STA. 12+25	8		LT. STA. 12+00 - 14+53	269	
STA. 12+11 LT. 15'	15		RT. STA. 12+50	8		RT. STA. 12+00 - 14+60	272	
STA. 12+25 LT. 25'	24	2 STUMPS @ 12	RT. STA. 12+75	8		LT. STA. 15+40 - 18+00	264	
STA. 12+40 LT. 27'	19	1@12 & 1@7	RT. STA. 13+00	8		RT. STA. 15+49 - 18+00	254	
STA. 12+48 LT. 25'	12		RT. STA. 13+25	9		TOTAL 1,059 FOOT		
STA. 12+81 LT. 18'	15	1@12 & 1@8	RT. STA. 13+50	10		60107700*		
STA. 12+83 LT. 31'	20	1@12, 1@10, & 1@8	RT. STA. 13+75	9		STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS		
STA. 12+86 LT. 24'	30		RT. STA. 14+00	8		LOCATION	FOOT	REMARKS
STA. 12+94 LT. 24'	10		RT. STA. 14+25	8		LT. STA. 14+28.0 - 14+40.3	12.5	1: 11.2 FLARE RATE
STA. 13+09 LT. 24'	14	1 STUMP @ 14	LT. STA. 18+00	11		RT. STA. 14+34.9 - 14+47.5	12.5	1: 19.6 FLARE RATE
STA. 13+18 LT. 24'	14		TOTAL 87 FOOT			LT. STA. 15+51.5 - 15+63.8	12.5	1: 15.0 FLARE RATE
STA. 13+28 LT. 36'	10		28000305*			RT. STA. 15+61.6 - 15+74.3	12.5	1: 9.4 FLARE RATE
STA. 13+34 LT. 20'	12		PERIMETER EROSION BARRIER			TOTAL 50.0 FOOT		
STA. 13+42 LT. 23'	8		LOCATION	FOOT	REMARKS	63000001		
STA. 13+64 LT. 42'	12		LT. STA. 12+00 - 14+69	285		TRAFFIC BARRIER TERMINAL, TYPE 5A		
STA. 14+01 LT. 37'	7		RT. STA. 14+94 - 14+96	6		LOCATION	EACH	REMARKS
STA. 14+12 LT. 43'	6		LT. STA. 15+04 - 15+08	14		LT. STA. 14+40.3 - 14+53.3	1	1: 11.2 FLARE RATE
STA. 14+17 LT. 42'	6	2@8	RT. STA. 15+34 - 16+65	135		RT. STA. 14+47.5 - 14+60.9	1	1: 19.6 FLARE RATE
STA. 14+26 LT. 28'	8		RT. STA. 16+81 - 18+00	119		LT. STA. 15+38.4 - 15+51.5	1	1: 15.0 FLARE RATE
STA. 14+34 LT. 28'	12		TOTAL 559 FOOT			RT. STA. 15+48.3 - 15+61.6	1	1: 9.4 FLARE RATE
STA. 14+41 LT. 43'	16		28000400			TOTAL 4 EACH		
STA. 14+57 LT. 33'	8		SUBBASE GRANULAR MATERIAL, TYPE A			63100075		
STA. 14+85 RT. 29'	6		LOCATION	TON	REMARKS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		
STA. 15+15 LT. 33'	8		STA. 12+00.00 - 12+10.11	17	12" (TAPER)	LOCATION	EACH	REMARKS
STA. 15+20 LT. 45'	6		STA. 12+10.11 - 14+60.37	413	12"	LT. STA. 13+77.3 - 14+28.0	1	
STA. 15+30 LT. 41'	8		STA. 15+39.38 - 17+72.55	383	12"	RT. STA. 13+82.6 - 14+34.9	1	
STA. 15+77 RT. 28'	6		STA. 17+72.55 - 18+00.00	44	12" (TAPER)	LT. STA. 15+63.8 - 15+14.5	1	
STA. 15+88 RT. 25'	6		TOTAL 857 TON			RT. STA. 15+74.3 - 15+26.6	1	
TOTAL 326 UNIT			31100100*			TOTAL 4 EACH		
20100110			AGGREGATE SURFACE COURSE, TYPE B			63100167*		
TREE REMOVAL (OVER 15 UNITS DIAMETER)			LOCATION	TON	REMARKS	GUARDRAIL MARKERS, TYPE A		
LOCATION	UNIT	REMARKS	F.E.R. 16+73	25		LOCATION	EACH	REMARKS
STA. 12+41 LT. 24'	24		TOTAL 25 TON			LT. STA. 13+77.3 - 14+53.3	3	
STA. 12+51 LT. 16'	18		40200800*			RT. STA. 13+82.6 - 14+60.9	3	
STA. 12+63 LT. 24'	20		BITUMINOUS MATERIALS (PRIME COAT)			LT. STA. 15+38.4 - 16+14.5	3	
STA. 12+95 LT. 22'	24		LOCATION	GALLON	REMARKS	RT. STA. 15+48.3 - 16+26.6	3	
STA. 13+04 LT. 17'	24		STA. 12+00.00 - 12+10.11	2	0.1 GAL/SY (OVER BIT)	TOTAL 12 EACH		
STA. 13+40 LT. 18'	18		STA. 12+10.11 - 14+60.37	55	0.1 GAL/SY (OVER BIT)	78200410		
STA. 13+62 LT. 15'	26		STA. 15+39.38 - 17+72.55	51	0.1 GAL/SY (OVER BIT)	SEEDING CLASS 3 (SPECIAL)		
STA. 13+92 LT. 20'	18		STA. 17+72.55 - 18+00.00	6	0.1 GAL/SY (OVER BIT)	LOCATION	ACRE	REMARKS
STA. 14+04 LT. 21'	18		STA. 12+00.00 - 12+10.11	10	0.4 GAL/SY (OVER AGG)	LT. STA. 12+00 - 18+00	0.31	
STA. 14+15 LT. 20'	18		STA. 12+10.11 - 14+60.37	242	0.4 GAL/SY (OVER AGG)	RT. STA. 12+00 - 18+00	0.28	
STA. 14+50 LT. 44'	28	1 STUMP @ 28	STA. 15+39.38 - 17+72.55	224	0.4 GAL/SY (OVER AGG)	TOTAL 0.59 ACRE		
STA. 15+09 LT. 44'	20		STA. 17+72.55 - 18+00.00	26	0.4 GAL/SY (OVER AGG)	X2501100*		
STA. 15+46 RT. 33'	24	1 STUMP @ 24	TOTAL 616 GALLON			40600100*		
STA. 16+89 LT. 20'	18		HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30					
STA. 17+74 LT. 26'	22		LOCATION	TON	REMARKS			
STA. 17+85 LT. 26'	22		STA. 12+00.00 - 12+10.11	4	2 - 1 1/2" LIFTS, TAPER			
TOTAL 342 UNIT			STA. 12+10.11 - 14+60.37	98	2 - 1 1/2" LIFTS			
20100210			STA. 15+39.38 - 17+72.55	92	2 - 1 1/2" LIFTS			
EARTH EXCAVATION			STA. 17+72.55 - 18+00.00	10	2 - 1 1/2" LIFTS, TAPER			
LOCATION	CU YD	REMARKS	TOTAL 204 TON			40603305		
STA. 12+00 - 18+00	389		AGGREGATE SHOULDERS, TYPE B					
TOTAL 389 CU YD			LOCATION	TON	REMARKS			
20200100*			LT. STA. 12+00.00 - 14+54.15	28				
FURNISHED EXCAVATION			RT. STA. 12+00.00 - 14+61.24	28				
LOCATION	CU YD	REMARKS	LT. STA. 15+37.92 - 18+00.00	29				
STA. 12+00 - 18+00	233		RT. STA. 15+47.78 - 16+59.33	20				
TOTAL 233 CU YD			RT. STA. 16+89.00 - 18+00.00	6				
20400800			TOTAL 111 TON			48101200		
EROSION CONTROL BLANKET			PIPE CULVERT REMOVAL					
LOCATION	SQ YD	REMARKS	LOCATION	FOOT	REMARKS			
LT. STA. 12+00 - 18+00	1,479		RT. STA. 16+63 - 16+84	21	UNDER EXISTING ENTRANCE			
RT. STA. 12+00 - 18+00	1,335		TOTAL 21 FOOT			50105220		
TOTAL 2,814 SQ YD			25100630					

FILE NAME = S:\PROJECTS\2010\1285D10\Bureau\Co-TR240\DESIGN\STRUCT\1285D10_ScheduleOfQuantities.dgn

USER NAME =	DESIGNED - B.S.K.	REVISED -	BUREAU COUNTY TR 240 OVER PLOW HOLLOW CREEK STATION 15+00	SCHEDULE OF QUANTITIES STRUCTURE NO. 006-4012	TWP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE =	CHECKED - B.K.C.	REVISED -			240	10-01121-00-BR	BUREAU	23	3	
PLOT DATE =	DRAWN - R.D.A.	REVISED -			WHA* 1285D10		CONTRACT NO. 87483			
	CHECKED - B.S.K.	REVISED -			ILLINOIS FED. AID PROJECT		BROS-0011(075)			

STA. 12+00 TO STA. 18+00