

PAVEMENT MARKING SCHEDULE					
LOCATION	THERMOPLASTIC PAVEMENT MARKING - LINE 4" (FOOT)	THERMOPLASTIC PAVEMENT MARKING - LINE 8" (FOOT)	THERMOPLASTIC PAVEMENT MARKING - LINE 12" (FOOT)	EPOXY PAVEMENT MARKING - LINE 4" (FOOT)	EPOXY PAVEMENT MARKING - LINE 12" (FOOT)
PEACE ROAD					
STA 114+50, 19' LT TO STA 120+15, 18' LT	566	-	-	-	-
STA 114+50, 12' LT TO STA 114+89, 12' LT	-	10	-	-	-
STA 114+50, CL TO STA 123+00, CL	1,700	-	-	-	-
STA 114+50, 6' RT TO STA 115+95, CL	290	-	-	-	-
STA 114+50, 12' RT TO STA 114+74, 12' RT	-	24	-	-	-
STA 114+50, 24' RT TO STA 151+00, 50' RT	58	-	-	-	-
STA 114+50, 17' LT TO STA 120+15, 18' LT	-	-	117	-	-
STA 114+50, CL TO STA 115+95, CL	-	-	10	-	-
STA 115+44, 50' RT TO STA 124+45, 18' RT	-	-	921	-	-
STA 122+40, CL TO STA 124+54, 2' LT	856	-	-	-	-
STA 123+00, CL TO STA 124+54, 2' RT	308	-	-	-	-
STA 123+00, 12' RT TO STA 124+45, 18' RT	-	-	84	-	-
STA 123+00, CL TO STA 124+54, CL	-	-	16	-	-
STA 123+30, 12' LT TO STA 124+59, 12' LT	40	-	-	-	-
STA 124+59, 12' LT TO STA 126+61, 12' LT	-	-	-	40	-
STA 124+64, 25' RT TO STA 126+66, 25' LT	-	-	-	203	-
STA 124+54, 2' LT TO STA 126+55, 2' LT	-	-	-	406	-
STA 124+54, CL TO STA 126+55, CL	-	-	-	-	28
STA 124+54, 2' RT TO STA 126+55, 2' RT	-	-	-	406	-
STA 124+45, 18' RT TO STA 126+45, 25' RT	-	-	-	201	-
STA 124+45, 18' RT TO STA 126+45, 25' RT	-	-	-	-	37
STA 126+00, 12' RT TO STA 126+50, 12' RT	-	-	-	20	-
TOTAL	3,818	34	1,148	1,276	65

EARTH EXCAVATION										
LOCATION STA TO STA	UNDERCUT AND PGE REPLACEMENT (CY)	UNSUITABLE EXCAVATION (TOPSOIL) (CY)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CY)	EARTH EXCAVATION (CY)	UTILITY EXCAVATION (CY)	EXCESS STRUCTURE EXCAVATION (CY)	TOTAL SUITABLE EXCAVATION (CY)	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (CY)	EMBANKMENT (CY)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CY)
PEACE ROAD										
STA 114+50 TO STA 115+35	9	14	23	35	-	-	35	30	23	7
STA 115+35 TO STA 116+00	12	13	25	26	-	-	26	23	34	(11)
STA 116+00 TO STA 117+50	27	47	74	79	2	-	81	69	147	(78)
STA 117+50 TO STA 123+00	118	295	413	310	100	-	410	349	1,113	(764)
STA 123+00 TO STA 124+52	87	142	229	237	-	-	237	202	670	(468)
TOTAL	253	511	764	687	102	-	789	673	1,987	(1,314)

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC. PROJECT: ILLINOIS DEKALB COUNTY PEACE ROAD IMPROVEMENTS. DRAWING: SCHEDULE-01. DATE: 3/20/2011. 4:02 PM.



DESIGNED - DJS	REVISED -
DRAWN - UKB	REVISED -
CHECKED - RWL	REVISED -
DATE - 04-01-2011	FILE NAME - 081068-41-SCHEDULE-01.dgn

CITY OF DeKALB, ILLINOIS
PEACE ROAD
IMPROVEMENTS

SCHEDULE OF MATERIALS	
SCALE:	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-01-WR	DeKALB	33	12
CONTRACT NO. 87488				
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT M-5017045				