	CODE NO.	ITEM	UNIT	STU	ITEP		NON-PARTICIPATING	TOTAL QUANTITY
				0004	0028	0031	LOCAL 0043	
△	56106300	ADJUSTING WATER MAIN 6"	FOOT	100				100
△	56106400	ADJUSTING WATER MAIN 8"	FOOT	100				100
△	56106500	ADJUSTING WATER MAIN 10"	FOOT	100				100
△ •	56200500	WATER SERVICE LINE 1 1/2"	FOOT				100	100
△ •	56201120	WATER SERVICE LINE 4"	FOOT				10	10
△	56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	200				200
△ •	56300300	ADJUSTING WATER SERVICE LINES	FOOT	100				100
△ •	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	3				3
△ •	X60228D	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1				1
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1				1
	60236700	INLETS, TYPE A, TYPE 10 FRAME AND GRATE	EACH	2				2
	60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	3				3
	60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	2				2
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	2				2
	60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1				1
	60255500	MANHOLES TO BE ADJUSTED	EACH	9				9
	60260100	INLETS TO BE ADJUSTED	EACH	3				3
	60261200	INLETS TO BE ADJUSTED WITH NEW TYPE 10 FRAME AND GRATE	EACH	1				1
*	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	5				5
•	60266600	VALVE BOXES TO BE ADJUSTED	EACH	8				8
	60500050	REMOVING CATCH BASINS	EACH	4				4
•	60500060	REMOVING INLETS	EACH	3				3
•	60500405	FILLING VALVE VAULTS	EACH				4	4
	60600605	CONCRETE CURB, TYPE B	FOOT		471			471
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT		2,761			2,761
•	61139800	STORM SEWERS(SPECIAL)4"	FOOT	200				200
•	61139900	STORM SEWERS(SPECIAL)6"	FOOT	200				200
	67100100	MOBILIZATION	L SUM	1				1
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	432				432
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	332				332
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,866				3,866
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	168				168
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	224				224
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	244				244

• SEE SPECIAL PROVISIONS

△ SPECIALTY ITEMS

FILE NAME = v:\transportation\2893\28930001.dgn	USER NAME = jolson	DESIGNED - JRB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CITY OF JACKSONVILLE DOWNTOWN STREETS RECONSTRUCTION SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JMO	REVISED -			N/A	10-00121-01-PV	MORGAN	77	4
	PLOT SCALE = 1.0000 ' / IN.	CHECKED - JRB	REVISED -					CONTRACT NO. 93547		
	PLOT DATE = 2/24/2011	DATE - 2/22/11	REVISED -		SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		