


T.R.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
52	06-04114-00-BR	WABASH	13	3
FED. ROAD DIST. NO. 7		ILLINOIS	DRAINAGE DITCH	
PROJECT # BR05-1051032		CONTRACT # 35653		
LEC JOB # HD01004#B				

323 W. 3RD ST.
P.O. BOX 160
MT. CARMEL, IL
62863
PHONE: (618)-262-8651
FAX: (618)-263-3327

405 W. STATE ST.
SUITE 1
PRINCETON, IN
47670
PHONE: (812)-386-7611
FAX: (812)-385-2812

PROFESSIONAL DESIGN FIRM
LAND SURVEY &
ENGINEERING
CORPORATION
184-00987
(62-032435)(35-002769)



AARON M. MEFFORD
NAME
SIGNATURE
DATE 4-13-11
EXPIRES 11-30-11

DRAINAGE DITCH
TOWNSHIP ROUTE 52
WABASH COUNTY, ILLINOIS

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION		CHANNEL EXCAVATION		ESTIMATED UNSUITABLE MATERIAL		SUITABLE MATERIAL ADJUSTED FOR SHRINKAGE		EMBANKMENT		EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
STA 0+00 TO 4+71.8	1517.8	0.0	0.0	0.0	0.0	1138.4	886.4	152.0				
STA 4+71.8 TO 5+28.2	0.0	146.7	73.4	0.0	55.0	0.0	0.0	55.0				
STA 5+28.2 TO 10+00	563.6	0.0	0.0	0.0	422.7	651.0	-228.3	6.4				
1 FIELD ENTRANCE	0.0	0.0	0.0	0.0	0.0	6.4	-6.4					
TOTAL	2081.4	146.7	73.3	1616.1	1643.8	-21.7						

SHEET TITLE:
CROSS-SECTIONS
SCALE: 1" = 5'
BY: AMM
DATE: 4/9/11
REV:
3 OF 13 SHEETS
SHEET NO. 3