

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9266	06-00062-06-PV	ST. CLAIR	80	3
FHWA REG. NO. 7	ILLINOIS	PROJECT NO.	RS-0163(035)	
FEDERAL AID PROJECT	CONTRACT NO.		97457	

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	TRAFFIC SIGNAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	515	515	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	346	346	
20100500	TREE REMOVAL, ACRES	ACRE	1	1	
20200100	EARTH EXCAVATION	CU YD	12,945	12,945	
20800150	TRENCH BACKFILL	CU YD	2,283	2,283	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	18,819	18,819	
25000200	SEEDING, CLASS 2	ACRE	5.0	5.0	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	405.0	405.0	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	405.0	405.0	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	405.0	405.0	
25100115	MULCH, METHOD 2	ACRE	5.00	5.00	
25100630	EROSION CONTROL BLANKET	SQ YD	6,656	6,656	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	450	450	
28000305	TEMPORARY DITCH CHECKS	FOOT	128	128	
28000400	PERIMETER EROSION BARRIER	FOOT	8,631	8,631	
28000500	INLET AND PIPE PROTECTION	EACH	17	17	
28100101	STONE RIPRAP, CLASS A1	SQ YD	101	101	
28100127	STONE RIPRAP, CLASS B4	SQ YD	101	101	
28200200	FILTER FABRIC	SQ YD	101	101	
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	1,079	1,079	
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	18,788	18,788	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	28	28	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,358	6,358	
40600300	AGGREGATE (PRIME COAT)	TON	183	183	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,271	1,271	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	308	308	
40701901	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11"	SQ YD	15,401	15,401	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	38	38	
40800030	AGGREGATE (PRIME COAT)	TON	9	9	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	42	42	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	347	347	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	912.0	912.0	
42400800	DETECTABLE WARNINGS	SQ FT	70	70	
44000100	PAVEMENT REMOVAL	SQ YD	14,051	14,051	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,188	1,188	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	64	64	

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	TRAFFIC SIGNAL
44000600	SIDEWALK REMOVAL	SQ FT	720	720	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,372	1,372	
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	511	511	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	466	466	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	5,736	5,736	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50104400	CONCRETE HEADWALL REMOVAL	EACH	6	6	
50105220	PIPE CULVERT REMOVAL	FOOT	1,304	1,304	
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	87	87	
542C0211	PIPE CULVERTS, CLASS C, TYPE 1 6"	FOOT	12	12	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	86	86	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	5	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	5	5	
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1	1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4	4	
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,915	1,915	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	634	634	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1,052	1,052	
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	123	123	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	435	435	
550A0420	STORM SEWERS, CLASS A, TYPE 2 27"	FOOT	240	240	
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	408	408	
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	288	288	
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	23	23	
550A1050	STORM SEWERS, CLASS A, TYPE 4 36"	FOOT	33	33	
56300300	ADJUSTING WATER SERVICE LINES	FOOT	60	60	
56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	60	60	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	3	3	
60219100	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 9 FRAME AND GRATE	EACH	2	2	
60219500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 15 FRAME AND LID	EACH	1	1	
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	40	40	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	2	2	
60221800	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 9 FRAME AND GRATE	EACH	1	1	

CHAD D. FAIRBANKS
062-063136
4-20-11
copying 11-30-11

* DENOTES SPECIALTY ITEM