

SUMMARY OF QUANTITIES

ROUTE:	FAP 869 (IL 14)					
LOCATION:	RURAL - STP					
FUNDING:	80% FEDERAL / 20% STATE				80% FED/10%STATE/10% CITY	
COUNTY:	PERRY			FRANKLIN		
CONSTRUCTION TYPE:	ROADWAY	BRIDGE SN 073-0036	BRIDGE SN 073-0038	BOX CULVERT SN 073-2000	ROADWAY	BOX CULVERT SN 028-7119
TYPE CODE:	0004	0011	0011	0004	0004	0011

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY					
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1		
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1				1	
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1				1	
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1				1	
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1				1	
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	EACH	1				1	
50101000	REMOVAL OF EXISTING STRUCTURES NO. 8	EACH	1				1	
50101100	REMOVAL OF EXISTING STRUCTURES NO. 9	EACH	1				1	
50101200	REMOVAL OF EXISTING STRUCTURES NO. 10	EACH	1				1	
50101300	REMOVAL OF EXISTING STRUCTURES NO. 11	EACH	1				1	
50101400	REMOVAL OF EXISTING STRUCTURES NO. 12	EACH	1				1	
50101410	REMOVAL OF EXISTING STRUCTURES NO. 13	EACH	1				1	
50101415	REMOVAL OF EXISTING STRUCTURES NO. 14	EACH	1				1	
50101420	REMOVAL OF EXISTING STRUCTURES NO. 15	EACH	1				1	
50101421	REMOVAL OF EXISTING STRUCTURES NO. 16	EACH	1				1	
50102400	CONCRETE REMOVAL	CU YD	23				23	
50104650	SLOPE WALL REMOVAL	SQ YD	324		324			
50105220	PIPE CULVERT REMOVAL	FOOT	2271				2271	
50200100	STRUCTURE EXCAVATION	CU YD	476		226	250		
50300100	FLOOR DRAINS	EACH	24		14	10		
50300225	CONCRETE STRUCTURES	CU YD	229.8		64.8	165		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	598		301	297		
50300260	BRIDGE DECK GROOVING	SQ YD	1392		668	724		
50300280	CONCRETE ENCASEMENT	CU YD	15.7		6.6	9.1		
50300300	PROTECTIVE COAT	SQ YD	1741		834	907		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0.5	0.5		
50500505	STUD SHEAR CONNECTORS	EACH	4014		1242	2772		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	172,290		74,870	89,900		7520
50800515	BAR SPLICERS	EACH	1,500		701	799		
50901125	STEEL RAILING (TEMPORARY)	FOOT	188		188			
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1193			1193		
51201800	FURNISHING STEEL PILES HP14X73	FOOT	1044		1044			
51202305	DRIVING PILES	FOOT	2237		1044	1193		
51203600	TEST PILE STEEL HP12X53	EACH	4			4		
51500100	NAME PLATES	EACH	3		1	1		1

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\colemm\dms43654\d901823p1.m32		DRAWN -	REVISED -			869	(1-1,1,3,6)R-1,RS-3(1,3,6)B-2	*	299	7	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 98797					
PLOT DATE = 3/25/2011		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					