



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 6, 2022

SUBJECT: FAP Route 318 (IL 6)
Section (72-6HB-2)BRR
Peoria County
Contract No. 68G69
Item No. 43, June 17, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised the Table of Contents to the Special Provisions.
3. Revised pages 12-35 of the Special Provisions.
4. Revised sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MEMBRANE CURING METHOD.....	2
LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES	2
PCC QC/QA ELECTRONIC REPORTS SUBMITTAL	2
PCC AUTOMATIC BATCHING EQUIPMENT	3
TRAFFIC CONTROL PLAN	3
WORKING RESTRICTIONS & TRAFFIC CONTROL / STAGING NOTES.....	4
TRAFFIC CONTROL AND PROTECTION BLR 21	5
TRAFFIC CONTROL AND PROTECTION, SPECIAL.....	5
DETOUR SIGNING.....	6
STRUCTURAL STEEL REPAIR	6
CLEANING AND PAINTING CONTACT SURFACE AREAS OF EXISTING STEEL STRUCTURES	7
HOT DIP GALVANIZING FOR STRUCTURAL STEEL	36
BLENDED FINELY DIVIDED MINERALS (BDE).....	39
COMPENSABLE DELAY COSTS (BDE)	40
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	43
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)..	51
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE)	51
SPEED DISPLAY TRAILER (BDE)	52
STEEL COST ADJUSTMENT (BDE).....	53
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	56
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	57
SUBMISSION OF PAYROLL RECORDS (BDE).....	57
TRAFFIC SPOTTERS (BDE).....	57
WEEKLY DBE TRUCKING REPORTS (BDE).....	59
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....	59
WORKING DAYS (BDE).....	61

Revised June 6, 2022

The Contractor shall not combine solvents or other wastes with cleaning residue wastes. All waste streams shall be stored in separate containers.

The Contractor is responsible for the payment of any fines and undertaking any clean up activities mandated by State or federal environmental agencies for improper waste handling, storage, transportation, or disposal.

Contractor personnel shall be trained in the proper handling of hazardous waste, and the necessary notification and clean up requirements in the event of a spill. The Contractor shall maintain a copy of the personnel training records at each bridge site.

It is understood and agreed that the cost of all work outlined above, unless otherwise specified, has been included in the bid, and no extra compensation will be allowed.

Basis of Payment: This work will be considered included in the cost of "Furnishing and Erecting Structural Steel", "Erecting Structural Steel", or "Structural Steel Repair", as applicable, according to the Standard Specifications, unless otherwise specified on the plans.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022

This page left blank intentionally.

Revised June 6, 2022