

SUMMARY OF QUANTITIES - CONT

COUNTY:	Perry County	Perry County	Perry County
ROUTE:	127/13/154	127/13/154	127/13/154
FUNDING:	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
LOCATION:	Urban	Urban	Urban
	ROADWAY	ROADWAY	ROADWAY
	0005	0006	0021

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0005	0006	0021
* 88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	6			6
* 88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	4			4
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	10			10
* 88200510	TRAFFIC SIGNAL BACKPLATE, RETROREFLECTIVE	EACH	17			17
* 88800100	PEDESTRIAN PUSH BUTTON	EACH	10			10
* 89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1426			1426
89502380	REMOVE EXISTING HANDHOLE	EACH	7			7
* A2C19G06	TREE, CRAPE MYRTLE (SHELL PINK), 3' HEIGHT, CONTAINER GROWN	EACH	4		4	
* X0324915	RELOCATE LIGHTING UNITS AND POLES	EACH	16			16
* X0325922	CELLULAR MODEM	EACH	1			1
* X0326266	ETHERNET SWITCH	EACH	1			1
X0326767	PROFILE DIAMOND GRINDING CONCRETE PAVEMENT	SQ YD	7415		7415	
X0327009	REMOVE SIGN (SPECIAL)	EACH	3		3	
* X1400209	45' ALUMINUM LIGHT POLE WITH 15' DAVIT ARM	EACH	3			3

* SPECIALTY ITEM

▲ REVISED 6-6-2022

MODEL: Default
FILE: \\nas01-pw-bentley.com\PWDOT\Documents\DOT_Offices\Bhndt\B\Projects\78624\CADD\Drawings\Drawings\78624-510-03-500

USER NAME = TaylorND	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 3/29/2022	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(8,19,102)N-2;103RS-6	PERRY	245	15
CONTRACT NO. 78624				
ILLINOIS FED. AID PROJECT				

*FAP 42/FAP 841