

SUMMARY OF QUANTITIES

COUNTY:	FRANKLIN COUNTY	FRANKLIN COUNTY
ROUTE:	FAI 57	FAI 57
FUNDING:	100%STATE	100% STATE
LOCATION:	RURAL	RURAL
	CONTRACT MAINTENANCE	REST AREA
	0005	0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	20	0	20
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1,842	0	1,842
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,104	0	1,104
44200050	WELDED WIRE REINFORCEMENT	SQ YD	2,663	821	1,842
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	14	14	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	921	921	
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	153	153	
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	669	669	
44201299	DOWEL BARS 1 1/2"	EACH	2,515	2,515	
44213200	SAW CUTS	FOOT	8,267	8,267	
44213204	TIE BARS 3/4"	EACH	1,021	203	818
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	1,842	0	1,842
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.5	0.5



MODEL: Default  
FILE NAME: p:\illinois\center\com\rw\DOT\Documents\DOT Offices\District 9\Projects\78951\CA\Drawings\CA\Drawings\0978951-Sheets.dgn

REVISED 6-6-2022

	USER NAME = HORNJD	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -						57	*	FRANKLIN	13	4
	PLOT SCALE = 100.0000 " / in.	CHECKED -	REVISED -						CONTRACT NO. 78951				
	PLOT DATE = 5/12/2022	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

NB RAMP SHOULDER SCHEDULE

LOCATION STATION TO STATION	EXIST. SHOULDER LENGTH (INFO ONLY)	EXIST. HMA SHOULDER WIDTH (INFO ONLY)	EXIST. AGG SHOULDER WIDTH (INFO ONLY)	PCC SHOULDERS, (10")	TIE BARS 3/4"	WELDED WIRE REINFORCEMENT	PAVED SHOULDER REMOVAL	EXCAVATING & GRADING EXISTING SHOULDER	SUBBASE GRANULAR MATERIAL, TYPE A 12"
I 57 NORTHBOUND REST AREA	FOOT	FOOT	FOOT	SQ YD	EACH	SQ YD	SQ YD	UNIT	SQ YD
NORTHBOUND ENTRANCE RAMP									
	300	6	4	334	150	334	200	3	334
NORTHBOUND EXIT RAMP									
	24	1	4	27	12	27	3	1	27
	521	6	4	579	261	579	348	6	579
PROJECT TOTALS				940	423	940	551	10	940

SB RAMP SHOULDER SCHEDULE

LOCATION STATION TO STATION	EXIST. SHOULDER LENGTH (INFO ONLY)	EXIST. HMA SHOULDER WIDTH (INFO ONLY)	EXIST. AGG SHOULDER WIDTH (INFO ONLY)	PCC SHOULDERS, (10")	TIE BARS 3/4"	WELDED WIRE REINFORCEMENT	PAVED SHOULDER REMOVAL	EXCAVATING & GRADING EXISTING SHOULDER	SUBBASE GRANULAR MATERIAL, TYPE A 12"
I 57 SOUTHBOUND REST AREA	FOOT	FOOT	FOOT	SQ YD	EACH	SQ YD	SQ YD	UNIT	SQ YD
SOUTHBOUND EXIT RAMP									
	20	1	4	23	0	23	3	1	23
	740	6	4	823	370	823	494	8	823
	50	10		56	25	56	56	1	56
SB PROJECT TOTALS				902	395	902	553	10	902
NB PROJECT TOTALS				940	423	940	551	10	940
			PROJECT TOTALS	1842	818	1842	1104	20	1842

1 REvised 6-6-2022

MODEL Default  
FILE Name: p:\wuldet-cw.bentley.com\p\WIDOT\Documents\DOT Offices\Dirlet: 9\Projects\78951\CADDData\CAD\Sheets\0978951-Sheets.dgn

	USER NAME = HORNJD	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	RAMP SCHEDULE				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -						57	*	FRANKLIN	13	12
	PLOT SCALE = 100,0000 ' / in.	CHECKED -	REVISED -						CONTRACT NO. 78951				
	PLOT DATE = 6/6/2022	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

\*D9 Rest Area Patch 2022-1