

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY	
				0005	RURAL
20200100	EARTH EXCAVATION	CU YD	90	90	
20400800	FURNISHED EXCAVATION	CU YD	1700	1700	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	894	894	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	259	259	
28000400	PERIMETER EROSION BARRIER	FOOT	2099	2099	
28000500	INLET AND PIPE PROTECTION	EACH	10	10	
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	336	336	
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	134	134	
28200200	FILTER FABRIC	SQ YD	201	201	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	5	5	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	36981	36981	
40600370	LONGITUDINAL JOINT SEALANT	FOOT	25838	25838	
40600990	TEMPORARY RAMP	SQ YD	329	329	
40604050	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N50	TON	9204	9204	
40800029	BITUMINOUS MATERIALS (TACK COAT)	POUND	376	376	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY	
				0005	RURAL
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	94	94	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	451	451	
42400800	DETECTABLE WARNINGS	SQ FT	88	88	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	83015	83015	
44000600	SIDEWALK REMOVAL	SQ FT	425	425	
44201000	CLASS B PATCHES, TYPE IV, 12 INCH	SQ YD	492	492	
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	200	200	
44201298	DOWEL BARS 1 1/4"	EACH	160	160	
44213000	PATCHING REINFORCEMENT	SQ YD	492	492	
44213200	SAW CUTS	FOOT	1008	1008	
44213204	TIE BARS 3/4"	EACH	112	112	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	121	121	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1	

1 REVISED 5-27-2022 △ SPECIALTY ITEMS

△ SPECIALTY ITEMS

MODEL: SMODELMANES
FILE NAME: SFILES

BA BENTON & ASSOCIATES, INC.
CONSULTING ENGINEERS / LAND SURVEYORS
1920 WEST LAVERGNE AVE
JACKSONVILLE, IL 62452
PHONE: 312-292-4146 FAX: 312-292-4149
IL DESIGN FIRM REGISTRATION NO. 184-000833

USER NAME = SUSERS	DESIGNED - SIB	REVISED -
PLOT SCALE = 4S CALES	DRAWN - SJB	REVISED -
PLOT DATE = 5DATES	CHECKED - DSR	REVISED -
	DATE - 03/2022	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE:	SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	19-00108-00-R5	MORGAN	90	3
			CONTRACT NO. 93791	
ILLINOIS / FED. AID PROJECT				

