



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2022

SUBJECT FAI Route90/94 (I-91/94)
Project NHPP-WLYX(088)
Section 2014-012LS
Cook County
Contract No. 60X98
Item No. 179, June 17, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised pages 134 & 135 of the Special Provisions.
3. Revised sheets 5, 6, 8-13, 21, 22, 111, 115, 116, 118-121, 124, 129, 131, 137, 139, 141-144, 152, 153, 160, 162 & 166 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

- b. Reworking and moistening the soil surface shall not be measured for payment but included in the cost of Native Sodding (Special).
- c. The initial and additional watering before the period of establishment will not be measured for payment but considered included in the cost of Native Sodding (Special).
- d. Supplemental watering will be measured in units of 1000 gallons of water applied on the sodded areas. Watering performed during and after the period of establishment will be considered as supplemental watering.
- e. Weed Control, Native Landscape Enhancement will be measured in acres as specified in Weed Control, Native Landscape Enhancement.

Basis of Payment: NATIVE SODDING (SPECIAL) will be paid for at the contract unit price per square yard which price shall include all material, transport, loading, unloading, labor, initial watering, tools, and equipment necessary to furnish, install and establish the sod, initial watering and reworking of crusted topsoil as required, disposal, and incidental items required to complete the work as specified herein and to the satisfaction of the Engineer according to the following schedule.

- a. Initial payment. Upon placement of Native Sodding (Special), 60 percent of the pay item will be paid.
- b. Final Payment. Upon acceptance of sod, the remaining 40 percent of the pay item will be paid.
- c. Supplemental watering will be paid for at the contract unit price per unit for SUPPLEMENTAL WATERING.
- d. Weed Control, Native Landscape Enhancement will be paid for at the contract unit price per acre for WEED CONTROL, NATIVE LANDSCAPE ENHANCEMENT.

STONE RIPRAP, CLASS A4 (SPECIAL)

Description: This work shall be done in accordance with the applicable portion of Section 281 and Section 1005.01 of the Standard Specifications. This work shall consist of all labor and material necessary to furnish and satisfactorily install the Quartzite Stone Riprap as shown in the plans and as directed by the Engineer.

Qualifications:

- A. Contractor must provide evidence that his firm or other entity proposed for the rip rap work has specific experience meeting the following criteria:
 - 1. Experience installing natural stone using aggregate setting beds.
 - 2. Aggregate setting bed work shall not be sublet.

Revised 6/1/2022

Material: Stone Riprap Class A4 (Special) shall meet the following requirements:

- Material: Quartzite
- Color Range: Gray blue

Samples:

Contractor must submit to the Engineer a minimum 5 pound bag of class A4 gradation stone for approval of color variation prior to performing any work. Submittal shall indicate the full range of colors. Allow a minimum of thirty (30) working days prior to installation for approval.

Obtain quartzite stone from a single quarry (source) with resources to provide material of specified consistent quality. The quarry shall have sufficient capacity to quarry and deliver the stone on schedule.

Contractor shall check the stone upon delivery to assure that the proper material has been received.

Add the following to AArticle 281.03 Preparation:

The Contractor shall be responsible for all layout. The layout must be performed by qualified personnel. The stone riprap, Class A4 (Special) must be laid out as shown in the plans or as directed by the Engineer.

The stone riprap bed shall be marked out with flags to delineate the perimeter of the stone bed. Once the stone bed has been approved by the Roadside Development Unit, the perimeter shall be painted prior to excavation.

Method of Measurement: Final acceptance will not be made until the stone is place and adjusted to the satisfaction of the Engineer. STONE RIPRAP, CLASS A4 (SPECIAL) will be measured in place, and the area computed in square yards. The area for measurement will include the stone bed limits.

Weed Barrier Fabric will be measured for payment as specified in WEED BARRIER FABRIC.

Basis of Payment: STONE RIPRAP, CLASS A4 (SPECIAL) will be paid for at the contract unit price per square yard which unit price shall include the cost of all layout, labor, transportation, materials, hauling, loading, unloading, placing, installing, removing, equipment, disposal of all materials off-site, and incidentals required to complete the work as specified herein to the satisfaction of the Engineer.

The placement of Weed Barrier Fabric will be paid for at the contract unit price for WEED BARRIER FABRIC.

Revised 6/1/2022