

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				STP	NHPP		NHPP
				80% FED	80% FED	100% STATE	80% FED
				20% STATE	20% STATE	20% STATE	20% STATE
				ROADWAY	ROADWAY	ROADWAY	SIGNALS
				0005	0005	0005	0021
				URBAN	URBAN	URBAN	URBAN
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	216	204	12		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	8,360	8,052	308		
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	26	26			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	9	8	1		
60400105	FRAMES, TYPE 1	EACH	19	19			
60920012	PIPE CULVERTS TO BE CLEANED 12"	FOOT	100			100	
60920015	PIPE CULVERTS TO BE CLEANED 15"	FOOT	100			100	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	2,862.5	2,862.5			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1			
63200310	GUARDRAIL REMOVAL	FOOT	2,923	2,923			
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	10,179	10,179			
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	770 4,537	770 4,537			

*SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				STP	NHPP		NHPP
				80% FED	80% FED	100% STATE	80% FED
				20% STATE	20% STATE	20% STATE	20% STATE
				ROADWAY	ROADWAY	ROADWAY	SIGNALS
				0005	0005	0005	0021
				URBAN	URBAN	URBAN	URBAN
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	5 4	5 4			
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	LSUM	1	1			
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	LSUM	1	1			
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	10	10			
67100100	MOBILIZATION	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102634	TRAFFIC CONTROL AND PROTECTION, STANDARD 701611	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	14,400	13,392	1,008		
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	6,000	5,580	420		
70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	1,045	586	459		
70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	FOOT	52,902	49,248	3,654		

*SPECIALTY ITEM

FILE NAME = P102621-sh11-500.01.dgn



USER NAME = kandy.estimote	DESIGNED - KE	REVISED -
	DRAWN - KE	REVISED -
PLOT SCALE = 2.0000' / 1" =	CHECKED - CMP	REVISED -
PLOT DATE = 4/22/2022	DATE - 4/22/2022	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BRAINARD AVE FROM MUSKEGON AVE TO STATE LINE RD
SUMMARY OF QUANTITIES

SCALE: NONE SHEET OF SHEETS STA. TO STA.

REVISED SHEET 6/2/2022		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		3592	2021-011-R5-SR&SW	COOK	57	4
					CONTRACT NO. 62N72	
ILLINOIS FED. AID PROJECT						