


STRUCTURE NUMBER	FROM		TO			LENGTH IN FEET	INVERT DEPTH IN INCHES	DIAMETER IN INCHES	PAY ITEM NUMBER
	STATION	OFFSET	STRUCTURE NUMBER	STATION	OFFSET				
END CAP	908+13.00	0.0' RT	S822	908+13.00	17.3' LT	17.3	30	6	60108206



**NOTE**

PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.

PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.

MODEL: Default  
 FILE NAME: p:\subarea\pwr\_bentley\com\benesch\pwr\1125+00\10740\_001\Eng\_Docs\_Phase\_II\Drainage\1125+00\115-shr-underdrain-55-005.dgn  
 D:\62H15-shr-underdrain-55-005.dgn  
 50099  
 2012/11/30






USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>PIPE UNDERDRAIN PLAN</b>	
<b>I-55</b>	
SCALE: 1" = 50'	SHEET OF SHEETS
STA. Sta	TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	501
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				





**NOTE**

PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.

PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.

MODEL: Default  
 FILE NAME: p:\subarea\paw\_bentley\combase\tech\paw\1\Documents\1\02\005\103\40\_00\Eng\_Docx\_Phase\_1\Drainage\1\02\H15-shr-underdrain-55-007.dgn  
 D:\62H15-shr-underdrain-55-007.dgn  
 50099  
 2012/11/30





USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**PIPE UNDERDRAIN PLAN  
I-55**

SCALE: 1" = 50'    SHEET    OF    SHEETS    STA. Sta    TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	503
CONTRACT NO. 62H15				
FAI 55, FAP 338    ILLINOIS    FED. AID PROJECT				



**NOTE**

PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.

PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.

MODEL: Default  
 FILE NAME: p:\subarea\paw\_bentley\com\benetech\paw\102005\102140\_00\Eng\_Docs\_Phase\_1\Drainage\102140\15-shi-underdrain-55-008.dgn  
 D:\62H15-shi-underdrain-55-008.dgn  
 50099  
 2012/11/30




USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**PIPE UNDERDRAIN PLAN  
I-55**

SCALE: 1" = 50'    SHEET    OF    SHEETS    STA. Sta    TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	504
CONTRACT NO. 62H15				
FAI 55, FAP 338    ILLINOIS    FED. AID PROJECT				



MODEL: Default  
 FILE NAME: p:\subarea\sh-ubenech-pw-bentley.com\benecch-ene-01\Documents\107005\107040\_00\Eng\_Docs\_Phase\_1\Drainage [Thomas]\D162H15-sh-ubenech-drain-59-000.dgn



**NOTE**

PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.

PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.





USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**PIPE UNDERDRAIN PLAN  
IL RTE 59 NB**

SCALE: 1" = 50'    SHEET    OF    SHEETS    STA. Sta    TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	505
CONTRACT NO. 62H15				
* FAI 55, FAP 338    ILLINOIS    FED. AID PROJECT				



STRUCTURE NUMBER	FROM		TO		LENGTH IN FEET	INVERT DEPTH IN INCHES	DIAMETER IN INCHES	PAY ITEM NUMBER	
	STATION	OFFSET	STRUCTURE NUMBER	STATION					OFFSET
HIGH	6993+15.00	20.3' LT	S342	6993+15.00	46.8' LT	26.5	30	6	60108206
HIGH	6993+15.00	20.3' LT	S332	6993+15.00	6.9' LT	13.4	30	6	60108206
END CAP	6993+75.00	0.0' RT	S337	6993+75.00	25.3' RT	25.3	30	6	60108206
END CAP	6995+80.00	0.0' RT	S338	6995+80.00	37.3' RT	37.3	30	6	60108206
END CAP	6996+15.00	22.8' LT	S346	6996+15.00	48.1' LT	25.3	30	6	60108206
END CAP	6998+00.00	27.2' LT	S348	6998+00.00	52.7' LT	25.5	30	6	60108206
END CAP	6998+25.00	0.0' RT	S339	6998+25.00	37.3' RT	37.3	30	6	60108206



**NOTE**  
 PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.  
 PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.

MODEL: Default  
 FILE: NAME: p:\subarea\paw\_bentley.com\benesch-epw\1\Documents\11072025\107140\_000\Eng\_Docs\_Phase\_1\Drainage [Thomas]D162H15-shi-underdrain-59-001.dgn  
 D:\62H15-shi-underdrain-59-001.dgn  
 50099  
 2012/11/30




USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -


**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

<b>PIPE UNDERDRAIN PLAN IL RTE 59 NB</b>			
SCALE: 1" = 50'	SHEET	OF SHEETS	STA. Sta TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	506
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



STRUCTURE NUMBER	FROM		TO		LENGTH IN FEET	INVERT DEPTH IN INCHES	DIAMETER IN INCHES	PAY ITEM NUMBER
	STATION	OFFSET	STRUCTURE NUMBER	STATION				
END CAP	1015+49.02	0.0' RT	S809	1015+78.00	1.3' RT	30.3	30	60108206
END CAP	1016+00.00	0.0' RT	S809	1015+78.00	1.3' RT	24.8	30	60108206
END CAP	7013+61.90	28.1' RT	S813	7013+60.97	1.3' LT	29.4	30	60108206
HIGH	8001+80.01	0.0' RT	S306	8001+80.00	37.3' LT	37.3	30	60108206
HIGH	8001+80.01	0.0' RT	S305	8001+80.03	12.5' RT	12.5	30	60108206
HIGH	8003+25.00	0.0' RT	S308	8003+25.00	37.3' LT	37.3	30	60108206
HIGH	8003+25.00	0.0' RT	S307	8003+25.00	13.3' RT	13.3	30	60108206
END CAP	8004+35.00	36.0' LT	S310	8004+75.00	37.3' LT	41.4	30	60108206
END CAP	8004+35.00	12.0' RT	S315	8004+75.00	13.3' RT	41.4	30	60108206
END CAP	8004+75.00	36.0' LT	S311	8004+85.00	37.3' LT	11.4	30	60108206
END CAP	8004+75.00	12.0' RT	S316	8004+85.00	13.3' RT	11.4	30	60108206
END CAP	8004+95.00	36.0' LT	S311	8004+85.00	37.3' LT	11.4	30	60108206
END CAP	8004+95.00	12.0' RT	S316	8004+85.00	13.3' RT	11.4	30	60108206
END CAP	8005+40.00	36.0' LT	S304	8004+95.00	37.3' LT	46.4	30	60108206
END CAP	8005+40.00	12.0' RT	S313	8004+95.00	13.3' RT	46.4	30	60108206
END CAP	8007+75.00	0.0' RT	S301	8007+75.00	43.3' LT	43.3	30	60108206
END CAP	8010+28.00	0.0' RT	S810	8010+28.00	43.3' LT	43.3	30	60108206
END CAP	8012+30.00	42.0' LT	S811	8012+30.00	1.3' RT	43.3	30	60108206



**NOTE**

PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.



PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.

	USER NAME = VinceM	DESIGNED - VMICEK	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>PIPE UNDERDRAIN PLAN</b> <b>IL RTE 59 NB</b>			F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100,0000' / in.	CHECKED - NORF	REVISED -		SCALE: 1" = 50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta	ILLINOIS	1510
PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISED -								F.AI 55, FAP 338	CONTRACT NO. 62H15	


D:\162H15-shi-underdrain-59-002.dgn  
50099  
2012/11/30







STRUCTURE NUMBER	FROM		TO		LENGTH IN FEET	INVERT DEPTH IN INCHES	DIAMETER IN INCHES	PAY ITEM NUMBER	
	STATION	OFFSET	STRUCTURE NUMBER	STATION					OFFSET
HIGH	6060+00.00	0.0' RT	S195	6060+00.00	28.3' RT	28.3	30	6	60108206
HIGH	6060+00.00	0.0' RT	S197	6060+00.00	31.3' LT	31.3	30	6	60108206
END CAP	7031+11.00	0.0' RI	S232	7031+11.00	25.3' RI	25.3	30	6	60108206
END CAP	7035+75.00	23.1' LT	S212	7036+29.00	24.8' LT	55.2	30	6	60108206
END CAP	7036+00.00	36.0' RT	S207	7036+29.00	37.3' RT	30.4	30	6	60108206
END CAP	7036+29.00	24.0' LT	S213	7036+38.91	24.8' LT	11.1	30	6	60108206
END CAP	7036+29.00	36.0' RT	S208	7036+38.91	37.3' RT	11.3	30	6	60108206
END CAP	7036+49.00	24.0' LT	S213	7036+38.91	24.8' LT	11.2	30	6	60108206
END CAP	7036+49.00	36.0' RT	S208	7036+38.91	37.3' RT	11.4	30	6	60108206
END CAP	7036+79.00	24.0' LT	S210	7036+49.00	24.8' LT	31.2	30	6	60108206
END CAP	7036+79.00	36.0' RT	S205	7036+49.00	37.3' RT	31.4	30	6	60108206
END CAP	8029+50.00	0.0' RT	S230	8029+50.00	43.3' LT	43.3	30	6	60108206
END CAP	8034+40.00	24.0' LT	S217	8034+67.50	25.3' LT	28.9	30	6	60108206
END CAP	8034+67.50	24.0' LT	S218	8034+77.50	25.3' LT	11.4	30	6	60108206
END CAP	8034+87.50	24.0' LT	S218	8034+77.50	25.3' LT	11.4	30	6	60108206
END CAP	8035+18.00	22.0' LT	S215	8034+87.50	25.3' LT	31.9	30	6	60108206





**NOTE**

PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.


PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.

	USER NAME = VinceM	DESIGNED - VMICEK	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>PIPE UNDERDRAIN PLAN</b> <b>IL RTE 59 NB</b>			F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 100,0000' / in.	CHECKED - NORF	REVISED -		SCALE: 1" = 50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta	ILLINOIS	FED. AID PROJECT	1510
PLOT DATE = 3/10/2022	DATE = 03/16/2022	REVISED -										CONTRACT NO. 62H15	

D:\162H15-shi-underdrain-59-004.dgn  
50099  
2012/11/30




STRUCTURE NUMBER	FROM		TO		LENGTH IN FEET	INVERT DEPTH IN INCHES	DIAMETER IN INCHES	PAY ITEM NUMBER	
	STATION	OFFSET	STRUCTURE NUMBER	STATION					OFFSET
HIGH	6063+55.00	0.0' RT	S191	6063+55.00	20.2' LT	20.2	30	6	60108206
HIGH	6063+55.00	0.0' RT	S193	6063+55.00	19.3' RT	19.3	30	6	60108206
END CAP	6063+55.00	18.9' LT	S190	6064+68.00	19.3' LT	111.0	30	6	60108206
END CAP	6063+55.00	18.0' RT	S102	6064+68.00	19.3' RT	117.7	30	6	60108206
HIGH	6064+68.00	0.0' RT	S190	6064+68.00	19.3' LT	19.3	30	6	60108206
HIGH	6064+68.00	0.0' RT	S102	6064+68.00	19.3' RT	19.3	30	6	60108206
END CAP	6064+68.00	18.0' LT	S104	6064+88.00	19.3' LT	20.7	30	6	60108206
END CAP	6064+68.00	18.0' RT	S103	6064+88.00	19.3' RT	22.0	30	6	60108206
END CAP	6065+08.00	18.0' LT	S104	6064+88.00	19.3' LT	20.7	30	6	60108206
END CAP	6065+08.00	18.0' RT	S103	6064+88.00	19.3' RT	22.0	30	6	60108206
HIGH	6065+08.00	0.0' RT	S105	6065+08.00	19.3' LT	19.3	30	6	60108206
HIGH	6065+08.00	0.0' RT	S101	6065+08.00	19.3' RT	19.3	30	6	60108206
END CAP	6066+10.00	18.0' LT	S105	6065+08.00	19.3' LT	100.3	30	6	60108206
END CAP	6066+10.00	18.0' RT	S101	6065+08.00	19.3' RT	106.4	30	6	60108206
HIGH	6066+10.00	0.0' RT	S107	6066+10.00	19.3' LT	19.3	30	6	60108206
HIGH	6066+10.00	0.0' RT	S106	6066+10.00	19.3' RT	19.3	30	6	60108206
HIGH	6068+20.00	0.0' RT	S110	6068+20.00	19.3' LT	19.3	30	6	60108206
HIGH	6068+20.00	0.0' RT	S109	6068+20.00	19.3' RT	19.3	30	6	60108206
HIGH	6070+30.00	0.0' RT	S113	6070+30.00	19.3' LT	19.3	30	6	60108206
HIGH	6070+30.00	0.0' RT	S112	6070+30.00	19.1' RT	19.1	30	6	60108206




**NOTE**  
 PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.  
 PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.

	USER NAME = VinceM	DESIGNED - VMICEK	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>PIPE UNDERDRAIN PLAN</b> <b>ROCK RUN CROSSINGS DRIVE</b>			F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100,000' / in.	CHECKED - NORF	REVISED -		SCALE: 1" = 50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta	ILLINOIS	WILL
	PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISED -					CONTRACT NO. 62H15		FAI 55, FAP 338 ILLINOIS FED. AID PROJECT		

D:\62H15-shi-underdrain-RockRun-001.dgn  
 50099  
 2012/11/30



STRUCTURE NUMBER	FROM		TO		LENGTH IN FEET	INVERT DEPTH IN INCHES	DIAMETER IN INCHES	PAY ITEM NUMBER
	STATION	OFFSET	STRUCTURE NUMBER	STATION				
HIGH	6072+50.00	0.0' RT	S115	6072+50.00	19.3' LT	19.3	6	60108206
HIGH	6072+50.00	0.0' RT	S114	6072+50.00	19.3' RT	19.3	6	60108206
HIGH	6074+50.00	0.0' RT	S117	6074+50.00	19.3' LT	19.3	6	60108206
HIGH	6074+50.00	0.0' RT	S116	6074+50.00	19.3' RT	19.3	6	60108206
HIGH	6076+50.00	0.0' RT	S119	6076+50.00	19.3' LT	19.3	6	60108206
HIGH	6076+50.00	0.0' RT	S118	6076+50.00	19.3' RT	19.3	6	60108206
HIGH	6078+50.00	0.0' RT	S122	6078+50.00	19.3' LT	19.3	6	60108206
HIGH	6078+50.00	0.0' RT	S121	6078+50.00	19.3' RT	19.3	6	60108206
HIGH	6080+50.00	0.0' RT	S124	6080+50.00	19.3' LT	19.3	6	60108206
HIGH	6080+50.00	0.0' RT	S123	6080+50.00	19.3' RT	19.3	6	60108206
HIGH	6084+65.00	0.0' RT	S429	6084+65.00	13.3' LT	13.3	6	60108206
HIGH	6084+65.00	0.0' RT	S430	6084+65.00	13.3' RT	13.3	6	60108206





**NOTE**

PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.


PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.

	USER NAME = VinceM	DESIGNED - VMICEK	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>PIPE UNDERDRAIN PLAN</b> <b>ROCK RUN CROSSINGS DRIVE</b>			F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100,000' / in.	CHECKED - NORF	REVISED -					FAI	2018-075-R	WILL	1510	511
PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISED -		SCALE: 1" = 50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta	CONTRACT NO. 62H15		
							FAI 55, FAP 338 ILLINOIS FED. AID PROJECT					

MODEL: Default  
 FILE NAME: p:\subarea\paw\_bentley\com\benetech\paw\1\Documents\1\02140\_001\Eng\_Docs\_Phase\_1\Drainage\1\02140\_001\sh-Underdrain-RockRun-002.dgn  
 D:\62H15-sh-Underdrain-RockRun-002.dgn  
 50099  
 2012/11/30



STRUCTURE NUMBER	FROM STATION	OFFSET	TO STRUCTURE NUMBER	TO STATION	OFFSET	LENGTH IN FEET	INVERT DEPTH IN INCHES	DIAMETER IN INCHES	PAY ITEM NUMBER
HIGH	6085+85.00	0.0' RT	S428	6085+85.00	13.3' LT	13.3	30	6	60108206
HIGH	6085+85.00	0.0' RT	S427	6085+85.00	13.3' RT	13.3	30	6	60108206
END CAP	6086+75.00	12.0' LT	S420	6087+48.00	12.0' LT	74.4	30	6	60108206
END CAP	6086+75.00	12.0' LT	S419	6087+48.00	12.0' RT	71.6	30	6	60108206
END CAP	6087+58.00	12.0' LT	S420	6087+48.00	12.0' LT	10.2	30	6	60108206
END CAP	6087+58.00	12.0' RT	S419	6087+48.00	12.0' RT	9.8	30	6	60108206
HIGH	6087+58.00	0.0' RT	S417	6087+58.00	13.2' LT	13.2	30	6	60108206
HIGH	6087+58.00	0.0' RT	S418	6087+58.00	13.4' RT	13.4	30	6	60108206
END CAP	6088+10.00	12.0' LT	S417	6087+58.00	12.0' LT	53.0	30	6	60108206
END CAP	6088+10.00	12.0' RT	S418	6087+58.00	12.0' RT	51.0	30	6	60108206
HIGH	6089+00.00	0.0' RT	S414	6089+00.00	13.3' LT	13.3	30	6	60108206
HIGH	6089+00.00	0.0' RT	S410	6089+00.00	13.3' RT	13.3	30	6	60108206
HIGH	6092+25.00	0.0' RT	S408	6092+25.00	13.1' LT	13.1	30	6	60108206
HIGH	6092+25.00	0.0' RT	S407	6092+25.00	13.3' RT	13.3	30	6	60108206
HIGH	6093+75.00	0.0' RT	S406	6093+75.00	13.3' LT	13.3	30	6	60108206
HIGH	6093+75.00	0.0' RT	S405	6093+75.00	13.3' RT	13.3	30	6	60108206
END CAP	6093+75.00	12.0' LT	S404	6094+77.00	13.3' LT	104.6	30	6	60108206
END CAP	6093+75.00	12.0' RT	S401	6094+77.00	13.3' RT	102.1	30	6	60108206
HIGH	6094+77.00	0.0' RT	S404	6094+77.00	13.3' LT	13.3	30	6	60108206
HIGH	6094+77.00	0.0' RT	S401	6094+77.00	13.3' RT	13.3	30	6	60108206
END CAP	6094+77.00	12.0' LT	S403	6094+87.00	13.3' LT	11.5	30	6	60108206
END CAP	6094+77.00	12.0' RT	S402	6094+87.00	13.3' RT	11.2	30	6	60108206
END CAP	6095+75.00	12.0' LT	S403	6094+87.00	13.3' LT	90.2	30	6	60108206
END CAP	6095+75.00	12.0' RT	S402	6094+87.00	13.3' RT	88.5	30	6	60108206
HIGH	6095+75.00	0.0' RT	S461	6095+75.00	13.3' LT	13.3	30	6	60108206
HIGH	6095+75.00	0.0' RT	S462	6095+75.00	13.3' RT	13.3	30	6	60108206
HIGH	6097+50.00	0.0' RT	S471	6097+50.00	13.4' LT	13.4	30	6	60108206
HIGH	6097+50.00	0.0' RT	S472	6097+50.00	15.2' RT	15.2	30	6	60108206
END CAP	16098+44.52	86.8' RT	S486	16098+42.00	31.2' RT	60.8	30	6	60108206
END CAP	16099+13.05	12.4' RT	S486	16098+42.00	31.2' RT	80.5	30	6	60108206



**NOTE**  
 PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.  
 PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.


	USER NAME = VinceM	DESIGNED - VMICEK	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>PIPE UNDERDRAIN PLAN</b> <b>ROCK RUN CROSSINGS DRIVE</b>			F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 100,0000' / in.	CHECKED - NORF	REVISED -		SCALE: 1" = 50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta	FAI 55, FAP 338	ILLINOIS	FED. AID PROJECT
PLOT DATE = 3/10/2022	DATE = 03/16/2022	REVISED -	REVISED -								WILL	1510	512
											CONTRACT NO. 62H15		

MODEL: Default  
 FILE: 162H15-shi-underdrain-RockRun-003.dgn  
 PROJECT: 162H15-shi-underdrain-RockRun-003.dgn  
 USER: VinceM  
 DATE: 3/10/2022










STRUCTURE NUMBER	FROM		TO			LENGTH IN FEET	INVERT DEPTH IN INCHES	DIAMETER IN INCHES	PAY ITEM NUMBER
	STATION	OFFSET	STRUCTURE NUMBER	STATION	OFFSET				
HIGH	4006+83.00	5.1' LT	S512	4006+83.00	22.5' LT	17.4	30	6	60108206
HIGH	4006+83.00	5.1' LT	S511	4006+83.00	8.3' RT	13.4	30	6	60108206
END CAP	4008+52.63	26.1' LT	S518	4009+08.00	29.0' LT	56.9	30	6	60108206
END CAP	4008+53.19	18.0' RT	S514	4009+08.00	19.3' RT	56.2	30	6	60108206
END CAP	4009+08.00	27.7' LT	S520	4009+28.00	29.5' LT	21.5	30	6	60108206
END CAP	4009+48.00	28.8' LT	S520	4009+28.00	29.5' LT	21.3	30	6	60108206
END CAP	4009+97.48	30.2' LT	S519	4009+48.00	30.1' LT	50.8	30	6	60108206
END CAP	4009+88.00	24.1' RT	S515	4009+48.00	19.3' RT	42.2	30	6	60108206
HIGH	4012+63.00	12.0' LT	S611	4012+63.00	40.8' LT	28.8	30	6	60108206
HIGH	4012+63.00	12.0' LT	S610	4012+63.00	24.8' RT	36.8	30	6	60108206
END CAP	4014+80.00	13.4' LT	S607	4014+80.00	48.7' LT	35.3	30	6	60108206
END CAP	4014+80.00	8.2' LT	S604	4014+80.00	31.0' RT	39.2	30	6	60108206
END CAP	4016+55.00	24.0' LT	S603	4016+55.00	51.7' LT	27.7	30	6	60108206
HIGH	4016+55.00	6.0' LT	S602	4016+55.00	18.8' LT	12.8	30	6	60108206
HIGH	4016+55.00	6.0' LT	S601	4016+55.00	31.3' RT	37.3	30	6	60108206
END CAP	5543+50.01	40.4' RT	S532	5544+00.01	50.6' RT	53.3	30	6	60108206
END CAP	5544+51.45	114.6' RT	S531	5544+10.01	54.7' RT	80.3	30	6	60108206





**NOTE**  
 PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.  
 PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.

	USER NAME = VinceM	DESIGNED - VMICEK	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>PIPE UNDERDRAIN PLAN</b> <b>SEIL RD</b>			F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 100,000' / in.	CHECKED - NORF	REVISED -		SCALE: 1" = 50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta	FAI 55, FAP 338	ILLINOIS	FED. AID PROJECT
PLOT DATE = 3/10/2022	DATE = 03/16/2022	REVISED -									WILL	1510	516
											CONTRACT NO. 62H15		

D:\62H15-shi-underdrain-Seil-002.dgn  
 50099  
 2012/11/30





**NOTE**

PIPE UNDERDRAINS, TYPE 2, 6" THAT OUTLET TO HEADWALLS SHALL BE PLACED AT A DEPTH OF 36" BELOW THE TOP OF PROPOSED PAVEMENT OR AS DEEP AS NECESSARY.

PIPE UNDERDRAINS, TYPE 2, 6" THAT TIE INTO PROPOSED DRAINAGE STRUCTURES SHALL BE PLACED AT A DEPTH OF 30" UNLESS OTHERWISE NOTED.

MODEL: Default  
 FILE: \\na16c-pw-bentley.com\benetech\paw01\Documents\107005\107140\_00\Eng\_Docs\_Phase\_1\Drainage [Thomas]\D162H15-shi-underdrain-Seil-003.dgn  
 D:\162H15-shi-underdrain-Seil-003.dgn  
 50099  
 2012/11/30




USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
	DRAWN - JHAITSMA	REVISED -
PLOT SCALE = 100,0000' / in.	CHECKED - NORF	REVISED -
PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**PIPE UNDERDRAIN PLAN  
W FRONTAGE RD**

SCALE: 1" = 50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
-----------------	-------	----	--------	----------	---------------

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	517
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**DETENTION BASIN 55-1**  
 BASIN BOTTOM ELEV = 582.50  
 NORMAL WATER LEVEL = 583.50  
 WATER QUALITY VOLUME = 1.622 ACRE-FT  
 100-YR DETENTION VOLUME = 2.657 ACRE-FT  
 100-YR 24-HR HIGH WATER LEVEL = 585.00  
 100-YR 24-HR INFLOW = 19.1 CFS  
 100-YR 24-HR OUTFLOW = 12.7 CFS



MODEL: Default  
 FILE: \\nautilus\pub\benesch\paw\benesch\proj\Documents\107005\107040\_001\Eng\_Docs\_Phase II\Drainage\Thomas\107040\_001\107040\_001.dgn  
 D:\162H15-shi-drain-pond-001.dgn  
 50099  
 2012/11/30




USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**DRAINAGE PLAN  
 POND 55-1**

SCALE: 1" = 50'    SHEET    OF    SHEETS    STA. Sta    TO STA. ToSta



F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	518
CONTRACT NO. 62H15				
FAI 55, FAP 338    ILLINOIS    FED. AID PROJECT				



**DETENTION BASIN 59-1B**  
 BASIN BOTTOM ELEV = 586.50  
 NORMAL WATER LEVEL = 587.16  
 WATER QUALITY VOLUME = 0.213 ACRE-FT  
 100-YR DETENTION VOLUME = 1.910 ACRE-FT  
 100-YR 24-HR HIGH WATER LEVEL = 589.50  
 100-YR 24-HR INFLOW = 40.7 CFS  
 100-YR 24-HR OUTFLOW = 39.6 CFS

**DETENTION BASIN 59-1A**  
 BASIN BOTTOM ELEV = 588.70  
 NORMAL WATER LEVEL = 589.20  
 WATER QUALITY VOLUME = 0.728 ACRE-FT  
 100-YR DETENTION VOLUME = 7.049 ACRE-FT  
 100-YR 24-HR HIGH WATER LEVEL = 592.00  
 100-YR 24-HR INFLOW = 37.5 CFS  
 100-YR 24-HR OUTFLOW = 23.3 CFS

REINFORCED CONCRETE WEIR WALL  
 REFER TO STRUCTURAL PLANS



MODEL: Default  
 FILE: \\nautilus\pub\benetech-ar\benetech-ar\Documents\107000\107040\_000\Eng\_Docs\_Phase II\Drainage\Drawings\107040\_000\107040\_000\107040\_000.dgn  
 D:\162H15-Sht-drain-pond-002.dgn  
 50099  
 2012/11/30






USER NAME = VincEM	DESIGNED - VMICEK	REVISED -
	DRAWN - JHAITSMA	REVISED -
PLOT SCALE = 100,0000' / in.	CHECKED - NORF	REVISED -
PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**


<b>DRAINAGE PLAN</b>		F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
<b>POND 59-1A &amp; 59-1B</b>			2018-075-R	WILL	1510	519
SCALE: 1" = 50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta	CONTRACT NO. 62H15

F.A.I.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	519
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

**DETENTION BASIN 59-2A**  
 BASIN BOTTOM ELEV = 585.00  
 NORMAL WATER LEVEL = 586.00  
 WATER QUALITY VOLUME = 1.337 ACRE-FT  
 100-YR 24-HR HIGH WATER LEVEL = 588.00  
 100-YR 24-HR INFLOW = 40.3 CFS  
 100-YR 24-HR OUTFLOW = 29.4 CFS



**DETENTION BASIN 59-2B**  
 BASIN BOTTOM ELEV = 579.50  
 NORMAL WATER LEVEL = 580.50  
 WATER QUALITY VOLUME = 0.347 ACRE-FT  
 100-YR 24-HR HIGH WATER LEVEL = 585.00  
 100-YR 24-HR INFLOW = 63.7 CFS  
 100-YR 24-HR OUTFLOW = 59.3 CFS



MODEL: Default  
 FILE: M:\GIS\GIS\Research\pwr\_bentley.com\research\pwr\_01\Documents\107005\107140\_000\Eng\_Docs\_Phase II\Drainage\Drawings\15-shi-drain-pond-003.dgn  
 D:\162H15-shi-drain-pond-003.dgn  
 50099  
 2012/11/30




USER NAME = vinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**DRAINAGE PLAN  
 POND 59-2A & 59-2B**

SCALE: 1" = 50'    SHEET    OF    SHEETS    STA. Sta    TO STA. ToSta

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	520
CONTRACT NO. 62H15				
FAI 55, FAP 338    ILLINOIS    FED. AID PROJECT				




**DETENTION BASIN 55-10**  
 BASIN BOTTOM ELEV = 574.50  
 NORMAL WATER LEVEL = 575.20  
 WATER QUALITY VOLUME = 0.869 ACRE-FT  
 100-YR DETENTION VOLUME = 5.851 ACRE-FT  
 100-YR 24-HR HIGH WATER LEVEL = 578.40  
 100-YR 24-HR INFLOW = 16.0 CFS  
 100-YR 24-HR OUTFLOW = 5.7 CFS

EXISTING SPILLWAY  
 REFER TO DETAIL

EXISTING  
 DETENTION BASIN

BASIN 55-10



MODEL: Default  
 FILE: M:\GIS\pub\benetech-ar\benetech-ar\Documents\107005\107040\_001\Eng\_Docs\_Phase II\Drainage\Thomas\107005\107040\_001\shd-drain-pond-004.dgn  
 D:\62H15-shd-drain-pond-004.dgn  
 50099  
 2012/11/30



USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**



**DRAINAGE PLAN  
 POND 55-10**

SCALE: 1" = 50'    SHEET    OF    SHEETS    STA. Sta    TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAI 55, FAP 338	2018-075-R	WILL	1510	521
CONTRACT NO. 62H15				
ILLINOIS FED. AID PROJECT				





# BASIN 55-1



STRUCTURE NUMBER	STATION	OFFSET	MANHOLE DIAMETER (FT)	FRAME AND GRATE	RIM ELEVATION	RESTRICTOR TYPE	RESTRICTOR DIAMETER	RESTRICTOR INVERT	TOP OF WEIR ELEVATION	BOTTOM OF SLAB TOP ELEVATION	HEAD OVER WEIR PLATE (FT)
5971	7027+66.30	122.0' RT	0	TYPE 1 FRAME CLOSED LID	588.50	SHARP EDGE	0.75' H X 3.33' L	583.50	585.00	586.75	1.75

# BASIN 55-10

EX EMERGENCY SPILLWAY DETAIL



MODEL: Default  
 FILE: M:\MFC\_Plan\Benech-pw-bentley.com\Benech-pw-01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\Drainage [Thomas]\D162H15-shi-drain-det-01.dgn  
 D:\62H15-shi-drain-det-01.dgn  
 50099  
 2012/11/30



USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 20,0000 * / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**



**DETENTION BASIN  
CROSS SECTIONS**

SCALE: SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2018-075-R	WILL	1510	523
CONTRACT NO. 62H15				
* FAI 55, FAP 338		ILLINOIS FED. AID PROJECT		







PR SLOTTED DRAIN 12" WITH VARIABLE SLOT, 50 FT

CONN PR SLOTTED DRAIN TO EX CATCH BASIN

297

298

EX Q I-55

PR SLOTTED DRAIN 12" WITH VARIABLE SLOT, 50 FT

CONN PR SLOTTED DRAIN TO EX CATCH BASIN

299

I-55 SB

I-55 NB

I-55 NB AUX LANE

MODEL: Default  
 FILE: \\na11c:\pub\uberech-pw\benfey.com\benfey.com\benfey.com\Documents\107005\107140\_001\Eng\_Docs\_Phase\_1\Drainage [Thomas]\D162H15-shl-drain-det-013.dgn



USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 20,0000 * / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**DRAINAGE DETAILS**

SCALE:	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
--------	-------	----	--------	----------	---------------

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	525
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

D162H15-shl-drain-det-013.dgn  
50099  
2012/11/30



MODEL: Default  
 FILE NAME: p:\bentley\compobase\encl\1\Documents\10700\107140\_001\Eng\_Docs\_Phase\_1\Drainage\_1\Thomas\162H15-shl-drain-det-014.dgn  
 D:\62H15-shl-drain-det-014.dgn  
 50099  
 2012/11/30



USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 20,0000 * / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**


**DRAINAGE DETAILS**

SCALE:	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
--------	-------	----	--------	----------	---------------


F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	526
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

**NOTES**


1. SLOTTED PAVEMENT DRAINS SHALL BE 12" DIAMETER, 16 GAUGE, FULL BITUMINOUS COATED WITH PAVED INVERT UNLESS OTHER SPECIFIED.
2. SLOTTED PAVEMENT DRAINS SHALL BE INSTALLED IN A CONTOURED TRENCH AND BACKFILLED WITH SI CONCRETE.
3. THE UPSTREAM END OF EACH SLOTTED DRAIN PAVEMENT DRAIN SHALL BE SEALED WITH A WELDED END PLATE IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.
4. DEPTH OF SLOT SHALL BE VARIED FROM 6" MINIMUM TO 12" MAXIMUM TO INCREASE SLOPE OF PIPE.
5. SLOTTED PAVEMENT DRAIN SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR SLOTTED DRAIN 12" WITH VARIABLE SLOT. THIS PRICE SHALL INCLUDE ALL MATERIAL AND LABOR NECESSARY TO COMPLETE THE WORK AS SHOWN OR AS DIRECTED BY THE ENGINEER.



**TYPICAL SECTION**



**DETAIL**



**CONNECTION TO EX DRAINAGE STRUCTURE**

MODEL: Default  
 FILE: \\nafe-pw-bentley.com\benesch-pw-01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\Drainage [Thomas]\D162H15-shl-drain-det-012.dgn  
 D:\62H15-shl-drain-det-012.dgn  
 50099  
 2012/11/30




USER NAME = VinceM	DESIGNED - VMICEK	REVISED -
PLOT SCALE = 20,0000 * / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - NORF	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**DRAINAGE DETAILS**

SCALE: SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2018-075-R	WILL	1510	527
CONTRACT NO. 62H15				
* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**FRAME AND GRATE TYPE 11 AND 11V**




**CONSTRUCTION SEQUENCE**

1. PRIOR TO SS INSTALLATION, PLACE AND COMPACT EMBANKMENT 2 FEET ABOVE THE PR T/P ELEV.
2. EXCAVATE TRENCH WITHIN NEWLY COMPACTED EMBANKMENT PER THE IDOT SSRBC.
3. INSTALL STORM SEWER PER PLAN, PLACE AND COMPACT TRENCH BACKFILL TO 2 FEET ABOVE THE T/P.
4. PLACE AND COMPACT REMAINING EMBANKMENT TO FINISHED GRADE PER THE IDOT SSRBC.


**PIPE LOCATIONS**

P300	P900
P600	P901
P603	P920
P701	P930
P706	P980
P740	P981
P800	P982
P830	


**TRENCH BACKFILL - NON-TYPICAL INSTALLATION**




**CATCH BASIN TYPE B**




**FRAME AND GRATE TYPE 12**




**TYPE 20 AND TYPE 21 FRAME & GRATE**




**TYPE 8 GRATE**




**FRAME AND GRATE TYPE 24**



**HEADWALL OR SLOPED HEADWALL**



**PRECAST REINFORCED CONCRETE FLARED END SECTION**



**MANHOLES WITH TYPE 1 FRAME AND LIDS**

MODEL: Default  
 FILE: M:\MFC\_Plan\Benech-pw-bentley.com\Benech-pw-01\Documents\107005\10740\_001\Eng\_Docs\_Phase\_1\Drainage [Thomas]10740\_001\SS-Drain-det-008.dgn  
 D:\62H15-shl-drain-det-008.dgn  
 50099  
 2012/11/30



USER NAME	= VinceM
PLOT SCALE	= 20,0000 * / in.
PLOT DATE	= 3/10/2022

DESIGNED	- VMICEK
DRAWN	- JHAITSMA
CHECKED	- NORF
DATE	- 03/16/2022



REVISED	-
REVISED	-
REVISED	-
REVISED	-

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**DRAINAGE DETAILS**

SCALE:	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
--------	-------	----	--------	----------	---------------

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
=	2018-075-R	WILL	1510	528
CONTRACT NO. 62H15				
© FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**NOTE:**  
1 - TO BE PAID FOR AS "FIRE HYDRANT TO BE RELOCATED"



MODEL: Default  
FILE: \\nafile\pub\benesch\pub\benesch.com\benesch\new01\Documents\107005\10740\_000\Eng\_Docs\_Phase\_I\Utilities\162H15-shi-wm-001.dgn  
D:\162H15-shi-wm-001.dgn  
51337  
2012/11/30



USER NAME = jworthington	DESIGNED - KPEARSON	REVISED -
	DRAWN - JWORTHINGTON	REVISED -
PLOT SCALE = 480,0000' / ft.	CHECKED - POBRIEN	REVISED -
PLOT DATE = 2/1/2022	DATE - 02/04/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**FIRE HYDRANT RELOCATION PLAN**

SCALE: 1" = 20' SHEET OF SHEETS STA. TO STA.


F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	529
CONTRACT NO. 62H15				
FAY 515, FAP 338 ILLINOIS FED. AID PROJECT				

Benchmarks: BM-302 set 2" diameter aluminum disc in bridge wall at northwest corner of existing NB IL-59 ramp bridge over I-55. EL. 625.23.

Existing Structure: Seil Road box culvert, Sta. 4016+73.50 (SN 099-C022) is a dual 5'-0" x 3'-0" precast concrete box culvert. The existing culvert length is 157'-0" and was constructed in 2008 under IDOT Contract 60363. Portions of the existing box culvert and the culvert end sections and aprons to be removed.


Traffic Control: The culvert extensions will be performed under staged construction.

No Salvage



**LONGITUDINAL SECTION**  
Looking Upstation

(Roadway dimensions and slopes given at right angles to Exist.  $\bar{C}$  Seil Road, U.N.O.)



**PLAN**

(All longitudinal dimensions measured along  $\bar{C}$  Proposed and Exist. Culverts, U.N.O.) \* Measured at right angles to Exist.  $\bar{C}$  Seil Road

**LOADING HS20-44**

Allow 50 psf for future wearing surface


**DESIGN SPECIFICATIONS**

2002 AASHTO Standard Specifications for Highway Bridges, 17th Edition (LFD)


2017 IDOT Culvert Manual

**DESIGN STRESSES**

**FIELD UNITS:**  
 $f'_c = 3,500$  psi  
 $f_y = 60,000$  psi (Reinforcement)  
**PRECAST UNITS:**  
 $f'_c = 5,000$  psi  
 $f_y = 65,000$  psi (Welded Wire Reinforcement)



EXPIRATION DATE 11-30-2022  
DATE: 02-04-2022



**LOCATION SKETCH**

**GENERAL PLAN AND ELEVATION**  
**SEIL ROAD DOUBLE BOX CULVERT EXTENSION**  
**SECTION 2018-075-R**  
**WILL COUNTY**  
**STATION 4016+73.50**  
**STRUCTURE NO. 099-C022**

MODEL: D:\p\aut...  
 FILE: \Bene...  
 \Documents\107709\107748\08\Eng\_Docs\_Phase 1\Structures\Culvert\_Sn1\Road\Final\Sheets\01620115-C022-general-plan-0201.dgn



USER NAME	E0skoul	DESIGNED	- EAO	REVISED	-
CHECKED	- KJN	CHECKED	- KJN	REVISED	-
PLOT SCALE	- NTS	DRAWN	- AJB	REVISED	-
DATE	02/04/2022	CHECKED	- KJN	REVISED	-

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

SHEET CA-01 OF CA-11 SHEETS

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	2018-075-R	WILL	1510	530
CONTRACT NO. 62H15				
* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

**GENERAL NOTES:**

- The design fill height for this box is 17.2 ft. The precast box culvert sections shall conform to the requirements of ASTM C 1577.
- Drain holes shall be provided on exterior culvert walls for each precast box segment with a clear rise greater than 3 ft. The drain hole shall be located within 1/3 of the clear rise of the box culvert, shall not intercept the haunch, and shall conform to the requirements of Article 503.11 of the Standard Specification.
- Nonwoven geotextile fabric shall conform to the requirements of Art. 1080.01 of the Standard Specifications. The minimum weight of the fabric shall be 6 ounces per square yard. Precast concrete box culverts and box culvert end sections shall be backfilled with Porous Granular Embankment below the top of the box culvert extending to a vertical plane 2 ft from the exterior sides of the culvert, 2 ft from the back face of the end sections, and not closer than 2 ft from the face of embankment.
- The 6 in. thick layer of porous granular material required for the precast concrete box culvert per Art. 540.06 of the Standard Specifications shall also apply to the end sections. Cost of the porous granular material will not be paid for separately but shall be included in the unit price of the work for which it is required.
- Reinforcement bars designated (E) shall be epoxy coated.
- Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contactor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
- Membrane Waterproofing for Buried Structures shall be applied to the full length of the precast concrete box culverts and end sections for the limits shown on Sheets CA-03 and CA-04.

**INDEX OF SHEETS**

CA-01	General Plan & Elevation
CA-02	General Notes, Total Bill of Material & Index of Sheets
CA-03	Removal & Precast Concrete Box Details
CA-04	Multi-Cell Precast Box Culvert Tapered End Sections (1 of 2)
CA-05	Multi-Cell Precast Box Culvert Tapered End Sections (2 of 2)
CA-06	Traversable Pipe Grate for Box Culverts (1 of 2)
CA-07	Traversable Pipe Grate for Box Culverts (2 of 2)
CA-08	Existing Plans (1 of 2)
CA-09	Existing Plans (2 of 2)
CA-10	Soil Boring Logs (1 of 2)
CA-11	Soil Boring Logs (2 of 2)

**DESIGN SCOUR TABLE**

Design Scour Elevation	Upstream	Downstream
	582.58	582.32

**TOTAL BILL OF MATERIAL**


ITEM	UNIT	TOTAL
Porous Granular Embankment	Cu. Yd.	95
Structure Excavation	Cu. Yd.	40
Box Culvert End Sections, Culvert No. 1	Each	4
Precast Concrete Box Culverts 5' x 3'	Foot	110
Traversable Pipe Grate for Concrete End Section	Foot	47
Geocomposite Wall Drain	Sq. Yd.	91
Membrane Waterproofing System for Buried Structures	Sq. Yd.	91
Box Culvert Removal	Foot	32
Remove Concrete Box Culvert End Section	Each	2

**WATERWAY INFORMATION**

Ex. Drainage Area = 59.59 Ac.		Sq. Miles 0.093		Exist. Overtopping Elev.: 592.98		@ Sta 4010+50				
Prop. Drainage Area = 65.18 Ac.		Sq. Miles 0.102		Prop. Overtopping Elev.: 592.98		@ Sta 4010+50				
Flood	Freq. Yr.	Ex. Discharge C.F.S.	Pr. Discharge C.F.S.	Waterway Opening - Sq. Ft.		Nat. H.W.E.	Head - Ft.		Headwater El.	
				Exist.	Prop.		Exist.	Prop.	Exist.	Prop.
	2	31.1	26.2	14.10	13.80	587.46	0.15	0.08	587.61	587.54
	10	60.9	54.4	15.40	15.10	587.59	0.30	0.21	587.89	587.80
Design	50	123.5	109.4	20.60	20.30	588.11	0.88	0.70	588.99	588.81
Base	100	162.7	144.9	23.40	23.10	588.39	1.18	0.98	589.57	589.37
OVT(E)*	>500	319.92								
OVT(P)**	>500		311.62							

\* Existing Overtopping Event  
 \*\* Proposed Overtopping Event

10-Year Outlet Velocity from Existing Structure = 3.07 fps  
 10-Year Outlet Velocity from Proposed Structure = 2.98 fps



**PROFILE GRADE**

(PGL Seil Road,  
 6.00' Rt. of Exist. C Seil Road)

MODEL: D:\p\11\benesch\pub\benesch\p\11\Documents\107209\10748\08\Eng\_Docs\_Phase\_1\Structures\Culvert\_Sect\Road\Final\Sheets\062H15-CA02-0111 of material-081.dgn  
 FILE: \\P:\11\benesch\pub\benesch\p\11\Documents\107209\10748\08\Eng\_Docs\_Phase\_1\Structures\Culvert\_Sect\Road\Final\Sheets\062H15-CA02-0111 of material-081.dgn



USER NAME - EOskaul	DESIGNED - EAO	REVISED -
PLOT SCALE - NTS	CHECKED - KJN	REVISED -
DATE - 02/04/2022	DRAWN - AJB	REVISED -
	CHECKED - KJN	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**


**SEIL ROAD DOUBLE BOX CULVERT EXTENSION  
 GENERAL NOTES, TOTAL BILL OF MATERIAL & INDEX OF SHEETS**

SHEET CA-02 OF CA-11 SHEETS


F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2018-075-R	WILL	1510	531
CONTRACT NO. 62H15				
* FAI 55, FAP 338		ILLINOIS	FED. AID PROJECT	









**ELEVATION**



**END VIEW**




**PLAN**




**SECTION A-A**

(All costs associated with furnishing and constructing the above drain detail will not be measured for payment but shall be included in the contract unit price for the associated work.)




**RESTRAINT ANGLE DETAIL**



**SECTION B-B**

(Showing end section tie details)



**TIE PLATE DETAIL**

**GENERAL NOTES**

Box Culvert End Sections shall be constructed according to the requirements of Section 540 of the Standard Specifications except as modified herein. This work will be measured for payment as each, with each end of each culvert being one each. End sections will be paid for at the contract unit price per each for Box Culvert End Sections of the culvert number specified.

Typical box section dimensions, materials, and reinforcement details for Box Culvert End Sections shall be according to the requirements of ASTM C 1577 as required for the design of the portion of the culvert within the limits of Precast Concrete Box Culverts except as modified herein.

Number of segments shown in Elevation is for example only. Length and number of precast box sections required to construct Box Culvert End Sections shall be determined by the Contractor.

See roadway plans for embankment slope (V:H).

1" diameter anchor rods for the culvert ties shall conform to the requirements of ASTM F1554, Grade 105. Structural steel for tie plate and restraint angle shall conform to the requirements of Article 1006.04 of the Standard Specifications. All components of the culvert tie detail shall be galvanized according to the requirements of AASHTO M 111 or M 232 as applicable. 2 1/4" x 2 1/4" x 5/16" plate washers shall be provided under each nut required for the anchor rods. Anchor rods connecting precast sections shall be brought to a snug tight condition followed by an additional 1/2 turn on one of the nuts for anchor rods installed in the walls. Match marks shall be provided on the bolt and nut to verify relative rotation between the bolt and the nut. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of using formed holes.

All costs associated with furnishing and installing or constructing the toewall and culvert ties will not be measured for payment but shall be included in the contract unit price for Box Culvert End Sections of the culvert number specified.

Drain holes shall conform to the requirements of Article 503.11 of the Standard Specifications unless noted otherwise.

Nonwoven geotextile fabric shall conform to the requirements of Article 1080.01. The minimum weight of the fabric shall be 6 oz. / sq. yd..

For end sections with traversable pipe grate systems, see grate detail sheet for required modifications.

The 3" nominal space between adjacent end sections shall be filled with Class SI concrete in accordance with Article 540.06 of the Standard Specifications. Cost included with Box Culvert End Sections.

Details for double cell box culvert shown. Details for other multi-cell box culverts similar.


MODEL: Defaul...  
 FILE: \\BENESCH-PUBLIC\benesch\com\benesch\p-91\Documents\107209\10748\08\Eng\Docs\Phase II\Structures\Culvert\_Ser1\BoxEnd\Sheets\062H15-CA04-culvert\_end-001.dgn

MCB-TES

2-17-2017


(Sheet 1 of 2)

 Alfred Benesch & Company 35 W Wacker Drive, Suite 3300 Chicago, Illinois 60601 312-465-0450 Job No. 10740	USER NAME - E0skoul DESIGNED - EAO CHECKED - KJN PLOT SCALE - NTS DATE - 02/04/2022	DESIGNED - EAO CHECKED - KJN DRAWN - AJB CHECKED - KJN	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SEIL ROAD DOUBLE BOX CULVERT EXTENSION</b> <b>MULTI-CELL PRECAST BOX CULVERT TAPERED END SECTIONS (1 OF 2)</b>	F.A./P.RTE. - SECTION - 2018-075-R COUNTY - WILL TOTAL SHEETS - 1510 SHEET NO. - 533	CONTRACT NO. 62H15
	SHEET CA-04 OF CA-11 SHEETS	* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT					




(Design Earth Cover  $\geq$  2 ft) (Design Earth Cover < 2 ft)

**SECTION C-C**



**SECTION D-D**



**ALTERNATE SECTION D-D**


As1m REINFORCEMENT (in. <sup>2</sup> /ft)											
Rise (ft)	2	3	4	5	6	7	8	9	10	11	12
4	0.19	0.17									
5	0.26	0.21	0.18								
6	0.22	0.26	0.23	0.22							
7	0.25	0.33	0.29	0.27	0.28						
8	0.40	0.35	0.43	0.39	0.36	0.34	0.40				
9	0.44	0.39	0.35	0.43	0.40	0.37	0.36	0.48			
10	0.48	0.42	0.38	0.47	0.44	0.41	0.38	0.42	0.56		
11	0.52	0.45	0.54	0.50	0.46	0.44	0.41	0.46	0.50	0.65	
12	0.55	0.49	0.58	0.54	0.50	0.48	0.45	0.46	0.46	0.61	0.75

(As1m reinforcement based upon welded wire reinforcement conforming to AASHTO M 55 or M 221).

**l1 DIMENSION**


- #3 bar = 2'-0"
- #4 bar = 2'-8"
- #5 bar = 3'-4"
- #6 bar = 3'-11"

**Notes:**  
 Alternate Section D-D is provided to allow the Contractor the option of casting the bottom slab of the end section first followed by construction of the sidewalls using conventional forming methods. Shop drawings that detail slab thickness and reinforcement layout shall be submitted to the Engineer for review and approval when using Alternate Section D-D.  
 The size and spacing of the v2 bars shall provide a minimum reinforcement area along each face of the walls (in.<sup>2</sup>/ft.) equal to 1.10\*(As1m). v2 bars may consist of #3 thru #6 size reinforcement bars and the longitudinal spacing shall not exceed the lesser of the wall thickness or 8 inches.  
 Bonded construction joints shall be prepared according to Article 503.09 of the Standard Specifications.  
 Sections C-C, D-D, and Headwall Elevation are symmetric about the culvert through 180° rotation.




**HEADWALL ELEVATION**

(Allow sidewall reinforcement to extend into end of headwall.)




**SECTION F-F**



**BAR s**

**BAR s1**



**SECTION E-E**

**TOEWALL CONSTRUCTION SEQUENCE**

1. Perform excavation and construct toewall.
2. Backfill according to the applicable paragraphs of Article 502.10 of the Standard Specifications and place bedding for precast box culvert end sections.
3. Set precast box culvert end section.
4. Drill and epoxy grout reinforcement in toewall in accordance with Section 584 of the Standard Specifications.
5. Pressure grout voids using non-shrink grout conforming to Section 1024 of the Standard Specifications.

\* The Contractor may furnish a precast or cast-in-place toewall. The Contractor shall be responsible for the strength and stability of the precast toewall during handling. Additional lifting points may be required depending upon the length of the toewall or the Contractor may need to modify the design of the toewall for the proposed handling the method.

\*\* If soil conditions permit, the sides of the toewall may be poured directly against the soil. The clear cover on the sides of the toewall shall be increased to 3" by increasing the thickness of the toewall.

MCB-TES 2-17-2017

(Sheet 2 of 2)



USER NAME	EOSkouf	DESIGNED	- EAO	REVISED	-
CHECKED	- KJN	CHECKED	- KJN	REVISED	-
PLOT SCALE	- NTS	DRAWN	- AJB	REVISED	-
DATE	02/04/2022	CHECKED	- KJN	REVISED	-

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**SEIL ROAD DOUBLE BOX CULVERT EXTENSION  
MULTI-CELL PRECAST BOX CULVERT TAPERED END SECTIONS (2 OF 2)**

F.A./P.R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2018-075-R	WILL	1510	534
CONTRACT NO. 62H15				
* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				








SHEET CA-05 OF CA-11 SHEETS

**GENERAL NOTES**

The minimum edge distance from the center of a hole to the free edge of a structural shape or plate shall be 1 1/2" unless noted otherwise.  
 This standard shall only be used on concrete end sections not skewed more than ±15 degrees with roadway.  
 The Contractor may install the thru bolts using drilling and grouting in lieu of providing a formed hole using steel pipe. Installation shall be in accordance with Article 509.06 using a method that results in the annulus surrounding the bolt being completely filled with adhesive. The method of drilling shall not result in spalled concrete at the exit face. Epoxy grouted thru bolts shall be snug tightened followed by an additional 1/2 turn on the interior nut at final installation. Cost included with Traversable Pipe Grate.



\* Provide intermediate support for grate pipe lengths > 20'-0".



(See Detail A for dimensions and details not shown.)

TPGBC-ZS

2-17-2017

(Sheet 1 of 2)



USER NAME	Eoskoul
DESIGNED	EAO
CHECKED	KJN
PLOT SCALE	NTS
DATE	02/04/2022

DESIGNED	EAO	REVISED	-
CHECKED	KJN	REVISED	-
DRAWN	AJB	REVISED	-
CHECKED	KJN	REVISED	-

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SEIL ROAD DOUBLE BOX CULVERT EXTENSION  
TRAVERSABLE PIPE GRATE FOR BOX CULVERTS (1 OF 2)

SHEET CA-06 OF CA-11 SHEETS

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2018-075-R	WILL	1510	535
CONTRACT NO. 62H15				
* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

MODEL D:\Defaul...  
 FILE NAME: P...  
 PROJECT: ...  
 SHEET: ...  
 DATE: ...  
 JOB NO: 10740

**PIPE-GRATE SCHEDULE FOR BOX CULVERT END SECTIONS**

Precast Box Culvert Dimensions			Slope of End Section								
			1:3			1:4			1:6		
S (ft)	R (ft)	Tt (in)	Main Pipe No. / Length	Int. Support No. / Length	Total Length of Pipe	Main Pipe No. / Length	Int. Support No. / Length	Total Length of Pipe	Main Pipe No. / Length	Int. Support No. / Length	Total Length of Pipe
4	2	7.5	1 @ 8'-10"	N/A	8'-10"	1 @ 11'-7"	N/A	11'-7"	1 @ 17'-2"	N/A	17'-2"
4	2	5	1 @ 8'-2"	N/A	8'-2"	1 @ 10'-8"	N/A	10'-8"	1 @ 15'-11"	N/A	15'-11"
4	3	7.5	1 @ 12'-0"	N/A	12'-0"	1 @ 15'-8"	N/A	15'-8"	1 @ 23'-3"	1 @ 3'-7"	26'-10"
4	3	5	1 @ 11'-4"	N/A	11'-4"	1 @ 14'-10"	N/A	14'-10"	1 @ 22'-0"	1 @ 3'-7"	25'-7"
4	4	7.5	1 @ 15'-2"	N/A	15'-2"	1 @ 19'-10"	1 @ 3'-7"	23'-5"	1 @ 29'-4"	2 @ 3'-7"	36'-6"
4	4	5	1 @ 14'-6"	N/A	14'-6"	1 @ 18'-11"	N/A	18'-11"	1 @ 28'-1"	2 @ 3'-7"	35'-3"
5	2	8	1 @ 8'-11"	N/A	8'-11"	1 @ 11'-9"	N/A	11'-9"	1 @ 17'-5"	N/A	17'-5"
5	2	6	1 @ 8'-5"	N/A	8'-5"	1 @ 11'-1"	N/A	11'-1"	1 @ 16'-5"	N/A	16'-5"
5	3	8	1 @ 12'-1"	N/A	12'-1"	1 @ 15'-10"	N/A	15'-10"	1 @ 23'-6"	1 @ 4'-7"	28'-1"
5	3	6	1 @ 11'-7"	N/A	11'-7"	1 @ 15'-2"	N/A	15'-2"	1 @ 22'-6"	1 @ 4'-7"	27'-1"
5	4	8	1 @ 15'-3"	N/A	15'-3"	1 @ 20'-0"	1 @ 4'-7"	24'-7"	1 @ 29'-7"	2 @ 4'-7"	38'-9"
5	4	6	1 @ 14'-9"	N/A	14'-9"	1 @ 19'-3"	N/A	19'-3"	1 @ 28'-7"	2 @ 4'-7"	37'-9"
5	5	8	1 @ 18'-5"	N/A	18'-5"	1 @ 24'-1"	2 @ 4'-7"	33'-3"	1 @ 35'-8"	3 @ 4'-7"	49'-5"
5	5	6	1 @ 17'-11"	N/A	17'-11"	1 @ 23'-5"	1 @ 4'-7"	28'-0"	1 @ 34'-8"	2 @ 4'-7"	43'-10"
6	2	8	2 @ 8'-11"	N/A	17'-10"	2 @ 11'-9"	N/A	23'-6"	2 @ 17'-5"	N/A	34'-10"
6	2	7	2 @ 8'-8"	N/A	17'-4"	2 @ 11'-5"	N/A	22'-10"	2 @ 16'-11"	N/A	33'-10"
6	3	8	2 @ 12'-1"	N/A	24'-2"	2 @ 15'-10"	N/A	31'-8"	2 @ 23'-6"	1 @ 5'-7"	52'-7"
6	3	7	2 @ 11'-10"	N/A	23'-8"	2 @ 15'-6"	N/A	31'-0"	2 @ 23'-0"	1 @ 5'-7"	51'-7"
6	4	8	2 @ 15'-3"	N/A	30'-6"	2 @ 20'-0"	1 @ 5'-7"	45'-7"	2 @ 29'-7"	2 @ 5'-7"	70'-4"
6	4	7	2 @ 15'-0"	N/A	30'-0"	2 @ 19'-8"	1 @ 5'-7"	44'-11"	2 @ 29'-1"	2 @ 5'-7"	69'-4"
6	5	8	2 @ 18'-5"	N/A	36'-10"	2 @ 24'-1"	2 @ 5'-7"	59'-4"	2 @ 35'-8"	3 @ 5'-7"	88'-1"
6	5	7	2 @ 18'-2"	N/A	36'-4"	2 @ 23'-9"	2 @ 5'-7"	58'-8"	2 @ 35'-2"	2 @ 5'-7"	81'-6"
6	6	8	2 @ 21'-7"	1 @ 5'-7"	48'-9"	2 @ 28'-3"	2 @ 5'-7"	67'-8"	2 @ 41'-9"	3 @ 5'-7"	100'-3"
6	6	7	2 @ 21'-4"	1 @ 5'-7"	48'-3"	2 @ 27'-11"	2 @ 5'-7"	67'-0"	2 @ 41'-3"	3 @ 5'-7"	99'-3"
7	2	8	2 @ 8'-11"	N/A	17'-10"	2 @ 11'-9"	N/A	23'-6"	2 @ 17'-5"	N/A	34'-10"
7	3	8	2 @ 12'-1"	N/A	24'-2"	2 @ 15'-10"	N/A	31'-8"	2 @ 23'-6"	2 @ 6'-7"	60'-2"
7	4	8	2 @ 15'-3"	N/A	30'-6"	2 @ 20'-0"	2 @ 6'-7"	53'-2"	2 @ 29'-7"	3 @ 6'-7"	78'-11"
7	5	8	2 @ 18'-5"	N/A	36'-10"	2 @ 24'-1"	3 @ 6'-7"	67'-11"	2 @ 35'-8"	4 @ 6'-7"	97'-8"
7	6	8	2 @ 21'-7"	2 @ 6'-7"	56'-4"	2 @ 28'-3"	3 @ 6'-7"	76'-3"	2 @ 41'-9"	5 @ 6'-7"	116'-5"
7	7	8	2 @ 24'-9"	3 @ 6'-7"	69'-3"	2 @ 32'-4"	4 @ 6'-7"	91'-0"	2 @ 47'-10"	6 @ 6'-7"	135'-2"
8	2	8	3 @ 8'-11"	N/A	26'-9"	3 @ 11'-9"	N/A	35'-3"	3 @ 17'-5"	N/A	52'-3"
8	3	8	3 @ 12'-1"	N/A	36'-3"	3 @ 15'-10"	N/A	47'-6"	3 @ 23'-6"	2 @ 7'-7"	85'-8"
8	4	8	3 @ 15'-3"	N/A	45'-9"	3 @ 20'-0"	2 @ 7'-7"	75'-2"	3 @ 29'-7"	3 @ 7'-7"	111'-6"
8	5	8	3 @ 18'-5"	N/A	55'-3"	3 @ 24'-1"	3 @ 7'-7"	95'-0"	3 @ 35'-8"	4 @ 7'-7"	137'-4"
8	6	8	3 @ 21'-7"	2 @ 7'-7"	79'-11"	3 @ 28'-3"	3 @ 7'-7"	107'-6"	3 @ 41'-9"	5 @ 7'-7"	163'-2"
8	7	8	3 @ 24'-9"	3 @ 7'-7"	97'-0"	3 @ 32'-4"	4 @ 7'-7"	127'-4"	3 @ 47'-10"	6 @ 7'-7"	189'-0"
8	8	8	3 @ 27'-11"	3 @ 7'-7"	106'-6"	3 @ 36'-6"	4 @ 7'-7"	139'-10"	3 @ 53'-11"	6 @ 7'-7"	207'-3"
9	2	9	3 @ 9'-3"	N/A	27'-9"	3 @ 12'-1"	N/A	36'-3"	3 @ 17'-11"	N/A	53'-9"
9	3	9	3 @ 12'-4"	N/A	37'-0"	3 @ 16'-2"	N/A	48'-6"	3 @ 24'-0"	3 @ 8'-7"	97'-9"
9	4	9	3 @ 15'-6"	N/A	46'-6"	3 @ 20'-4"	2 @ 8'-7"	78'-2"	3 @ 30'-1"	3 @ 8'-7"	116'-0"
9	5	9	3 @ 18'-8"	N/A	56'-0"	3 @ 24'-5"	3 @ 8'-7"	99'-0"	3 @ 36'-2"	4 @ 8'-7"	142'-10"
9	6	9	3 @ 21'-10"	2 @ 8'-7"	82'-8"	3 @ 28'-7"	3 @ 8'-7"	111'-6"	3 @ 42'-3"	5 @ 8'-7"	169'-8"
9	7	9	3 @ 25'-0"	3 @ 8'-7"	100'-9"	3 @ 32'-8"	4 @ 8'-7"	132'-4"	3 @ 48'-4"	6 @ 8'-7"	196'-6"
9	8	9	3 @ 28'-2"	3 @ 8'-7"	110'-3"	3 @ 36'-10"	4 @ 8'-7"	144'-10"	3 @ 54'-5"	6 @ 8'-7"	214'-9"
9	9	9	3 @ 31'-4"	3 @ 8'-7"	119'-9"	3 @ 40'-11"	5 @ 8'-7"	165'-8"	3 @ 60'-6"	7 @ 8'-7"	241'-7"
10	2	10	3 @ 9'-6"	N/A	28'-6"	3 @ 12'-5"	N/A	37'-3"	3 @ 18'-5"	N/A	55'-3"
10	3	10	3 @ 12'-8"	N/A	38'-0"	3 @ 16'-6"	N/A	49'-6"	3 @ 24'-6"	3 @ 9'-7"	102'-3"
10	4	10	3 @ 15'-10"	N/A	47'-6"	3 @ 20'-8"	2 @ 9'-7"	81'-2"	3 @ 30'-7"	3 @ 9'-7"	120'-6"
10	5	10	3 @ 19'-0"	N/A	57'-0"	3 @ 24'-9"	3 @ 9'-7"	103'-0"	3 @ 36'-8"	4 @ 9'-7"	148'-4"
10	6	10	3 @ 22'-1"	2 @ 9'-7"	85'-5"	3 @ 28'-11"	3 @ 9'-7"	115'-6"	3 @ 42'-9"	5 @ 9'-7"	176'-2"
10	7	10	3 @ 25'-3"	3 @ 9'-7"	104'-6"	3 @ 33'-0"	4 @ 9'-7"	137'-4"	3 @ 48'-10"	6 @ 9'-7"	204'-0"
10	8	10	3 @ 28'-5"	3 @ 9'-7"	114'-0"	3 @ 37'-2"	4 @ 9'-7"	149'-10"	3 @ 54'-11"	6 @ 9'-7"	222'-3"
10	9	10	3 @ 31'-7"	4 @ 9'-7"	133'-1"	3 @ 41'-3"	5 @ 9'-7"	171'-8"	3 @ 61'-0"	7 @ 9'-7"	250'-1"
10	10	10	3 @ 34'-9"	4 @ 9'-7"	142'-7"	3 @ 45'-5"	5 @ 9'-7"	184'-2"	3 @ 67'-1"	8 @ 9'-7"	277'-11"
11	2	11	4 @ 9'-9"	N/A	39'-0"	4 @ 12'-9"	N/A	51'-0"	4 @ 18'-11"	N/A	75'-8"
11	3	11	4 @ 12'-11"	N/A	51'-8"	4 @ 16'-11"	N/A	67'-8"	4 @ 25'-0"	3 @ 10'-7"	131'-9"
11	4	11	4 @ 16'-1"	N/A	64'-4"	4 @ 21'-0"	2 @ 10'-7"	105'-2"	4 @ 31'-1"	3 @ 10'-7"	156'-1"
11	6	11	4 @ 22'-5"	2 @ 10'-7"	110'-10"	4 @ 29'-3"	3 @ 10'-7"	148'-9"	4 @ 43'-3"	5 @ 10'-7"	225'-11"
11	8	11	4 @ 28'-9"	3 @ 10'-7"	146'-9"	4 @ 37'-6"	4 @ 10'-7"	192'-4"	4 @ 55'-5"	6 @ 10'-7"	285'-2"
11	10	11	4 @ 35'-0"	4 @ 10'-7"	182'-4"	4 @ 45'-9"	5 @ 10'-7"	235'-11"	4 @ 67'-7"	8 @ 10'-7"	355'-0"
11	11	11	4 @ 38'-2"	4 @ 10'-7"	195'-0"	4 @ 49'-10"	6 @ 10'-7"	262'-10"	4 @ 73'-8"	9 @ 10'-7"	389'-11"
12	2	12	4 @ 10'-0"	N/A	40'-0"	4 @ 13'-1"	N/A	52'-4"	4 @ 19'-5"	N/A	77'-8"
12	3	12	4 @ 13'-2"	N/A	52'-8"	4 @ 17'-3"	N/A	69'-0"	4 @ 25'-6"	3 @ 11'-7"	136'-9"
12	4	12	4 @ 16'-4"	N/A	65'-4"	4 @ 21'-4"	2 @ 11'-7"	108'-6"	4 @ 31'-7"	4 @ 11'-7"	172'-8"
12	6	12	4 @ 22'-8"	2 @ 11'-7"	113'-10"	4 @ 29'-7"	3 @ 11'-7"	153'-1"	4 @ 43'-9"	5 @ 11'-7"	232'-11"
12	8	12	4 @ 29'-0"	3 @ 11'-7"	150'-9"	4 @ 37'-10"	4 @ 11'-7"	197'-8"	4 @ 55'-11"	7 @ 11'-7"	304'-9"
12	10	12	4 @ 35'-4"	4 @ 11'-7"	187'-8"	4 @ 46'-1"	5 @ 11'-7"	242'-3"	4 @ 68'-1"	8 @ 11'-7"	365'-0"
12	12	12	4 @ 41'-8"	5 @ 11'-7"	224'-7"	4 @ 54'-4"	6 @ 11'-7"	286'-10"	4 @ 80'-3"	10 @ 11'-7"	436'-10"

(Sheet 2 of 2)

TPGBC-ZS

2-17-2017

MODEL: Defaul...  
 FILE: \\BENESCH\benesch\combenech\p-01\Documents\07709\07748\08\Eng\_Docs\_Phase II\Structures\Culvert\_Sat\_1\Box\Final\Sheets\062H15-CA07-culvert\_and\_grate\_002.dgn



USER NAME	EOKoul	DESIGNED	- EAO	REVISED	-
CHECKED	- KJN	CHECKED	- KJN	REVISED	-
PLOT SCALE	- NTS	DRAWN	- AJB	REVISED	-
DATE	02/04/2022	CHECKED	- KJN	REVISED	-

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SEIL ROAD DOUBLE BOX CULVERT EXTENSION  
TRAVERSABLE PIPE GRATE FOR BOX CULVERTS (2 of 2)**

SHEET CA-07 OF CA-11 SHEETS

F.A.I.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	2018-075-R	WILL	1510	536
CONTRACT NO. 62H15				
* FAI 55, FAP 338		ILLINOIS	FED. AID PROJECT	





F.A.I.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	*	WILL	608	391
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
* (26, 26HB-1 & 114) R-2 CONTRACT NO. 60363				



**SOIL BORING LOG**

Page 1 of 1  
Date 9/4/07

ROUTE FAI 55 & FAP 338 (IL 59) DESCRIPTION IL 59 (I-55 TO DUPAGE RIVER) AND INTERSTATE 55 AT IL RTE 59 LOGGED BY G. Schaertl

SECTION 26HB-1BR & 114R-1 LOCATION BOX CULVERT UNDER SEIL ROAD SEC. 21 TWP. 35 N. RING. 9 E. PM. 3rd

COUNTY WILL DRILLING METHOD HOLLOW STEM AUGER HAMMER TYPE AUTOMATIC

STRUCT. NO.	099-C022	D	B	U	M	Surface Water Elev.	ft	D	B	U	M
Station	4016+73.5	E	L	C	O	Stream Bed Elev.	ft	E	L	C	O
BORING NO.	B-305	P	O	S	I			P	O	S	I
Station	4016+78	T	W	S		Groundwater Elev.:		T	W	S	
Offset	79.0 ft RT.	H	S	Q	T	First Encounter	569.2 ft	H	S	Q	T
Northing	1,762,888.97					Upon Completion	576.2 ft				
Easting	1,020,853.23					After	Hrs.				
Ground Surface Elev.	590.2 ft	(R)	(6")	(tsf)	(%)			(R)	(6")	(tsf)	(%)

TOPSOIL		589.7			Extremely Dense, Brown GRAVEL	18					
Stiff to Hard, Brown SILTY CLAY trace - gravel	588.7	3			some - sand	504.2			6.0		
		5	2.1	25.0	End of Boring						
		3									
		4	4.3	21.0							
		5	B								
		3									
		5	4.5	29.0							
		9	B								
		4									
		6	6.4	21.0							
		11	B								
Gray below 11 feet		4									
		7	2.5	22.0							
		9	B								
		4									
		5	3.1	19.0							
		8	B								
		2									
		3	1.5	14.0							
		4	B								
Medium Dense, Gray SILTY LOAM little - gravel	572.2	8									
		10		11.0							
		11									

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)  
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)



**SOIL BORING LOG**

Page 1 of 1  
Date 9/4/07

ROUTE FAI 55 & FAP 338 (IL 59) DESCRIPTION IL 59 (I-55 TO DUPAGE RIVER) AND INTERSTATE 55 AT IL RTE 59 LOGGED BY G. Schaertl

SECTION 26HB-1BR & 114R-1 LOCATION BOX CULVERT UNDER SEIL ROAD SEC. 16 TWP. 35 N. RING. 9 E. PM. 3rd

COUNTY WILL DRILLING METHOD HOLLOW STEM AUGER HAMMER TYPE AUTOMATIC

STRUCT. NO.	099-C022	D	B	U	M	Surface Water Elev.	ft	D	B	U	M
Station	4016+73.5	E	L	C	O	Stream Bed Elev.	ft	E	L	C	O
BORING NO.	B-306	P	O	S	I			P	O	S	I
Station	4016+78	T	W	S		Groundwater Elev.:		T	W	S	
Offset	77.0 ft LT.	H	S	Q	T	First Encounter	570.1 ft	H	S	Q	T
Northing	1,763,044.73					Upon Completion	565.1 ft				
Easting	1,020,843.68					After	Hrs.				
Ground Surface Elev.	689.1 ft	(R)	(6")	(tsf)	(%)			(R)	(6")	(tsf)	(%)

TOPSOIL		588.5									
Very Stiff to Hard, Brown SILTY CLAY trace - roots, gravel	588.5	3			Dense, Gray SILTY LOAM little - gravel	568.1			5		
		4	2.7	24.0	Dense, Gray GRAVEL some - sand	567.1			11	10.0	
		5	B			564.6			25	5.0	
		3									
		5	2.9	16.0	End of Boring						
		6	B								
		6									
		8	4.7	16.0							
		10	B								
		5									
		8	4.3	25.0							
		11	B								
Medium Dense, Gray SILTY trace - gravel	576.1	5									
		9		18.0							
		8									
Stiff, Gray SILTY CLAY trace - gravel	573.6	3									
		3	1.2	33.0							
		4	B								
Medium Dense, Gray SILTY CLAY LOAM trace - gravel	571.1	9									
		6		11.0							
		8									

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)  
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

SHT. BCE-3 OF BCE-3

REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.P. ROUTE 338 (ILLINOIS ROUTE 59)  
SEIL ROAD DOUBLE BOX CULVERT  
SECTION (26, 26HB-1 & 114) R-2  
STRUCTURE NUMBER 099-C022  
STATION 4016+73.50, WILL COUNTY

SOIL BORING LOGS

DRAWN BY: MDB  
CHECKED BY:

DATE: 03/14/08

**TENG**

7800 N. HARSHMAN AVE. CHICAGO, ILLINOIS 60630  
312-231-1100 FAX 312-231-1101  
WWW.TENG.COM

FOR INFORMATION ONLY

MODEL: D:\p\aut\...  
 FILE: \\E:\...  
 ...



USER NAME	Eoskoul	DESIGNED	- EAO	REVISED	-
PLOT SCALE	NTS	CHECKED	- KJN	REVISED	-
DATE	02/04/2022	DRAWN	- AJB	REVISED	-
		CHECKED	- KJN	REVISED	-

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SEIL ROAD DOUBLE BOX CULVERT EXTENSION  
SOIL BORING LOGS (1 OF 2)

SHEET CA-10 OF CA-11 SHEETS

F.A.I.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2018-075-R	WILL	1510	539
CONTRACT NO. 62H15				
* FAI 55, FAP 338		ILLINOIS	FED. AID PROJECT	






Benchmarks: BM-302 set 2" diameter aluminum disc in bridge wall at northwest corner of existing NB IL-59 ramp bridge over I-55. EL. 625.23.

Existing Structure: IL-59 box culvert, sta. 7003+50.00 (Exist. SB IL-59) (SN 099-0351) is a dual 5' x 3' precast concrete box culvert. The existing culvert length is 202'-0" and was constructed in 2008 under IDOT contract 60363. Portions of the existing box culvert and the culvert end sections and aprons to be removed.

Traffic Control: The culvert extensions will be performed under staged construction.

No Salvage



**UNFOLDED LONGITUDINAL SECTION**  
Looking West


**LOADING HS20-44**  
Allow 50 psf for future wearing surface

**DESIGN SPECIFICATIONS**  
2002 AASHTO Standard Specifications for Highway Bridges, 17th Edition (LFD)  
2017 IDOT Culvert Manual

**DESIGN STRESSES**

**FIELD UNITS:**  
 $f'_c = 3,500$  psi  
 $f_y = 60,000$  psi (Reinforcement)


**PRECAST UNITS:**  
 $f'_c = 5,000$  psi  
 $f_y = 65,000$  psi (Welded Wire Reinforcement)



**PLAN**

(All longitudinal dimensions along  $\bar{C}$  Proposed and Existing Culverts)

- NOTE:**
1. All stations and offsets are measured from the Prop.  $\bar{C}$  IL Rte 59 SB.
  2. Provide a 4 ft. inside diameter precast concrete riser with steps per IDOT Highway Standard 602401-07 and 602701-02 at each location noted (4 locations). Do not install steps inside the precast concrete box culvert section. Provide a Type 1 frame with closed lid at each riser location. Provide an opening in the top slab of the precast concrete box culvert section at each riser location to match the inside diameter of the riser. The cost for the risers, steps, frames with closed lids, and openings in the precast concrete box culverts shall be included in the pay item Precast Concrete Box Culverts 5' x 3'.



**LOCATION SKETCH**

**GENERAL PLAN AND ELEVATION, 1 OF 2**  
**IL RTE 59 DOUBLE BOX CULVERT EXTENSION**  
F.A.P. RTE. 338  
SECTION 2018-075-R  
WILL COUNTY  
STATION 7003+56.43 (SB IL 59)  
STRUCTURE NO. 099-0351

MODEL: D:\p\aut\1\benesch\pub\benesch\p\01\Documents\107709\107748\08\Eng\_Docs\_Phase\_II\Structures\Culvert\_IL\_59\Final\Sheets\02\H15-CB01-general-plan-001.dgn  
 FILE: \\NAE1\p\aut\1\benesch\pub\benesch\p\01\Documents\107709\107748\08\Eng\_Docs\_Phase\_II\Structures\Culvert\_IL\_59\Final\Sheets\02\H15-CB01-general-plan-001.dgn




USER NAME: EOskaul	DESIGNED: EAO	REVISED: -
PLOT SCALE: NTS	CHECKED: TPS	REVISED: -
DATE: 02/04/2022	DRAWN: AJB	REVISED: -
	CHECKED: TPS	REVISED: -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

SHEET CB-01 OF CB-13 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	541
CONTRACT NO. 62H15				
* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**LONGITUDINAL SECTION**  
Looking North  
(All Roadway dimensions and Slopes Given at Right Angles to Prop. IL Rte 59 NB, U.N.O.)



**PLAN**  
(All longitudinal dimensions measured along CL Proposed and Exist. Culverts)

**NOTE:**  
1. All station points are measured from the Prop. IL Rte 59 SB, U.N.O.

**GENERAL PLAN AND ELEVATION, 2 OF 2**  
**IL RTE 59 DOUBLE BOX CULVERT EXTENSION**  
F.A.P. RTE. 338  
SECTION 2018-075-R  
WILL COUNTY  
STATION 7003+56.43 (SB IL 59)  
STRUCTURE NO. 099-0351

MODEL: D:\p\11\benesch\pub\benesch\p\91\Documents\107709\107748\08\Eng\_Docs\_Phase II\Structures\Culvert\_IL\_59\Final\Sheets\022H15-CB02-general.pln-082.dgn  
 FILE: \\P:\11\benesch\pub\benesch\p\91\Documents\107709\107748\08\Eng\_Docs\_Phase II\Structures\Culvert\_IL\_59\Final\Sheets\022H15-CB02-general.pln-082.dgn



USER NAME - EOskaul	DESIGNED - EAO	REVISD -
PLOT SCALE - NTS	CHECKED - TPS	REVISD -
DATE - 02/04/2022	DRAWN - AJB	REVISD -
	CHECKED - TPS	REVISD -


**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

SHEET CB-02 OF CB-13 SHEETS


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2018-075-R	WILL	1510	542	
CONTRACT NO. 62H15				
* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				









**ELEVATION**



**END VIEW**




**PLAN**




**SECTION A-A**

(All costs associated with furnishing and constructing the above drain detail will not be measured for payment but shall be included in the contract unit price for the associated work.)




**RESTRAINT ANGLE DETAIL**



**SECTION B-B**

(Showing end section tie details)



**TIE PLATE DETAIL**

**GENERAL NOTES**

Box Culvert End Sections shall be constructed according to the requirements of Section 540 of the Standard Specifications except as modified herein. This work will be measured for payment as each, with each end of each culvert being one each. End sections will be paid for at the contract unit price per each for Box Culvert End Sections of the culvert number specified.

Typical box section dimensions, materials, and reinforcement details for Box Culvert End Sections shall be according to the requirements of ASTM C 1577 as required for the design of the portion of the culvert within the limits of Precast Concrete Box Culverts except as modified herein.

Number of segments shown in Elevation is for example only. Length and number of precast box sections required to construct Box Culvert End Sections shall be determined by the Contractor.

See roadway plans for embankment slope (V:H).

1" Ø anchor rods for the culvert ties shall conform to the requirements of ASTM F1554, Grade 105. Structural steel for tie plate and restraint angle shall conform to the requirements of Article 1006.04 of the Standard Specifications. All components of the culvert tie detail shall be galvanized according to the requirements of AASHTO M 111 or M 232 as applicable. 2 1/4" x 2 1/4" x 5/16" plate washers shall be provided under each nut required for the anchor rods. Anchor rods connecting precast sections shall be brought to a snug tight condition followed by an additional 1/2 turn on one of the nuts for anchor rods installed in the walls. Match marks shall be provided on the bolt and nut to verify relative rotation between the bolt and the nut. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of using formed holes.

All costs associated with furnishing and installing or constructing the toewall and culvert ties will not be measured for payment but shall be included in the contract unit price for Box Culvert End Sections of the culvert number specified.

Drain holes shall conform to the requirements of Article 503.11 of the Standard Specifications unless noted otherwise.

Nonwoven geotextile fabric shall conform to the requirements of Article 1080.01. The minimum weight of the fabric shall be 6 oz. / sq. yd..

For end sections with traversable pipe grate systems, see grate detail sheet for required modifications.

The 3" nominal space between adjacent end sections shall be filled with Class S1 concrete in accordance with Article 540.06 of the Standard Specifications. Cost included with Box Culvert End Sections.

Details for double cell box culvert shown. Details for other multi-cell box culverts similar.

MODEL: D:\Defaul...  
 FILE: \\Benesch\pub\ben\cl\com\benesch\p-01\Documents\107209\10748\08\Eng\_Docs\_Phase\_11\Structures\Culvert\_1L\_59\Final\Sheets\052H15-CB05-culvert\_end-001

**MCB-TES**

Alfred Benesch & Company  
 35 W Wacker Drive, Suite 3300  
 Chicago, Illinois 60601  
 312-465-0450 Job No. 10740

USER NAME	EOSkoul	DESIGNED	- EAO	REVISED	-
PLOT SCALE	NTS	CHECKED	- TPS	REVISED	-
DATE	02/04/2022	DRAWN	- AJB	REVISED	-
		CHECKED	- TPS	REVISED	-


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL RTE 59 DOUBLE BOX CULVERT EXTENSION  
MULTI-CELL PRECAST BOX CULVERT TAPERED END SECTIONS (1 OF 2)**

(Sheet 1 of 2)


F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2018-075-R	WILL	1510	545
CONTRACT NO. 62H15				
* FAI 55, FAP 338		ILLINOIS	FED. AID PROJECT	

SHEET CB-05 OF CB-13 SHEETS




(Design Earth Cover  $\geq$  2 ft) (Design Earth Cover < 2 ft)

**SECTION C-C**



**SECTION D-D**



**ALTERNATE SECTION D-D**


As1m REINFORCEMENT (in. <sup>2</sup> /ft)											
Rise (ft) \ Ts (in.)	2	3	4	5	6	7	8	9	10	11	12
4	0.19	0.17									
5	0.26	0.21	0.18								
6	0.22	0.26	0.23	0.22							
7	0.25	0.33	0.29	0.27	0.28						
8	0.40	0.35	0.43	0.39	0.36	0.34	0.40				
9	0.44	0.39	0.35	0.43	0.40	0.37	0.36	0.48			
10	0.48	0.42	0.38	0.47	0.44	0.41	0.38	0.42	0.56		
11	0.52	0.45	0.54	0.50	0.46	0.44	0.41	0.46	0.50	0.65	
12	0.55	0.49	0.58	0.54	0.50	0.48	0.45	0.46	0.46	0.61	0.75

(As1m reinforcement based upon welded wire reinforcement conforming to AASHTO M 55 or M 221).


**l1 DIMENSION**

- #3 bar = 2'-0"
- #4 bar = 2'-8"
- #5 bar = 3'-4"
- #6 bar = 3'-11"


**Notes:**  
 Alternate Section D-D is provided to allow the Contractor the option of casting the bottom slab of the end section first followed by construction of the sidewalls using conventional forming methods. Shop drawings that detail slab thickness and reinforcement layout shall be submitted to the Engineer for review and approval when using Alternate Section D-D.  
 The size and spacing of the v2 bars shall provide a minimum reinforcement area along each face of the walls (in.<sup>2</sup>/ft.) equal to 1.10\*(As1m). v2 bars may consist of #3 thru #6 size reinforcement bars and the longitudinal spacing shall not exceed the lesser of the wall thickness or 8 inches.  
 Bonded construction joints shall be prepared according to Article 503.09 of the Standard Specifications.  
 Sections C-C, D-D, and Headwall Elevation are symmetric about the culvert through 180° rotation.



**HEADWALL ELEVATION**




**SECTION F-F**



**BAR s**

**BAR s1**



**SECTION E-E**

**TOEWALL CONSTRUCTION SEQUENCE**

1. Perform excavation and construct toewall.
2. Backfill according to the applicable paragraphs of Article 502.10 of the Standard Specifications and place bedding for precast box culvert end sections.
3. Set precast box culvert end section.
4. Drill and epoxy grout reinforcement in toewall in accordance with Section 584 of the Standard Specifications.
5. Pressure grout voids using non-shrink grout conforming to Section 1024 of the Standard Specifications.

\* The Contractor may furnish a precast or cast-in-place toewall. The Contractor shall be responsible for the strength and stability of the precast toewall during handling. Additional lifting points may be required depending upon the length of the toewall or the Contractor may need to modify the design of the toewall for the proposed handling the method.

\*\* If soil conditions permit, the sides of the toewall may be poured directly against the soil. The clear cover on the sides of the toewall shall be increased to 3" by increasing the thickness of the toewall.

MODEL: D:\p\1\benesch\p\ban\cl\com\benesch\p\91\Documents\107709\10748\08\Eng\_Docs\_Phase II\Structures\Culvert-IL\_59\Final\Sheets\052H15-CB06-culvert\_end-002.dwg  
 FILE: 052H15-CB06-culvert\_end-002.dwg  
 USER: EOskaul  
 DATE: 02/04/2022

MCB-TES

2-17-2017

(Sheet 2 of 2)



USER NAME	E0skaul	DESIGNED	- EAO	REVISED	-
CHECKED	- TPS	CHECKED	- TPS	REVISED	-
PLOT SCALE	- NTS	DRAWN	- AJB	REVISED	-
DATE	02/04/2022	CHECKED	- TPS	REVISED	-

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**









**IL RTE 59 DOUBLE BOX CULVERT EXTENSION  
MULTI-CELL PRECAST BOX CULVERT TAPERED END SECTIONS (2 OF 2)**

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2018-075-R	WILL	1510	546
CONTRACT NO. 62H15				
* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

SHEET CB-06 OF CB-13 SHEETS

**GENERAL NOTES**

The minimum edge distance from the center of a hole to the free edge of a structural shape or plate shall be 1 1/2" unless noted otherwise.  
 This standard shall only be used on concrete end sections not skewed more than ±15 degrees with roadway.  
 The Contractor may install the thru bolts using drilling and grouting in lieu of providing a formed hole using steel pipe. Installation shall be in accordance with Article 509.06 using a method that results in the annulus surrounding the bolt being completely filled with adhesive. The method of drilling shall not result in spalled concrete at the exit face. Epoxy grouted thru bolts shall be snug tightened followed by an additional 1/3 turn on the interior nut at final installation. Cost included with Traversable Pipe Grate.



\*\* Measured perpendicular to top of culvert wall. In addition, formed hole shall be located a minimum of 6" measured horizontally from any vertical joints necessary for construction of the culvert end section.

(Sheet 1 of 2)

MODEL: D:\p\aut\1\benesch\pub\benesch\comb\benesch.p\01\Documents\107709\107748\08\Eng\_Docs\_Phase II\Structures\Culvert\_1L\_59\Final\Sheets\052115-CB07-culvert\_end\_grate-020.dgn  
 FILE: \\benesch-pub\benesch\comb\benesch.p\01\Documents\107709\107748\08\Eng\_Docs\_Phase II\Structures\Culvert\_1L\_59\Final\Sheets\052115-CB07-culvert\_end\_grate-020.dgn

TPGBC-ZS  
 2-17-2017  
  
 Alfred Benesch & Company  
 35 W Wacker Drive, Suite 3300  
 Chicago, Illinois 60601  
 312-465-0450 Job No. 10740

USER NAME	Eoskoul	DESIGNED	EAO	REVISED	-
PLOT SCALE	NTS	CHECKED	TPS	REVISED	-
DATE	02/04/2022	DRAWN	AJB	REVISED	-
		CHECKED	TPS	REVISED	-

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**IL RTE 59 DOUBLE BOX CULVERT EXTENSION  
 TRAVERSABLE PIPE GRATE FOR BOX CULVERTS (1 OF 2)**

SHEET CB-07 OF CB-13 SHEETS

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2018-075-R	WILL	1510	547
CONTRACT NO. 62H15				
* FAI 55, FAP 338		ILLINOIS		FED. AID PROJECT

**PIPE-GRATE SCHEDULE FOR BOX CULVERT END SECTIONS**

Precast Box Culvert Dimensions			Slope of End Section								
			1:3			1:4			1:6		
S (ft)	R (ft)	Tt (in)	Main Pipe No. / Length	Int. Support No. / Length	Total Length of Pipe	Main Pipe No. / Length	Int. Support No. / Length	Total Length of Pipe	Main Pipe No. / Length	Int. Support No. / Length	Total Length of Pipe
4	2	7.5	1 @ 8'-10"	N/A	8'-10"	1 @ 11'-7"	N/A	11'-7"	1 @ 17'-2"	N/A	17'-2"
4	2	5	1 @ 8'-2"	N/A	8'-2"	1 @ 10'-8"	N/A	10'-8"	1 @ 15'-11"	N/A	15'-11"
4	3	7.5	1 @ 12'-0"	N/A	12'-0"	1 @ 15'-8"	N/A	15'-8"	1 @ 23'-3"	1 @ 3'-7"	26'-10"
4	3	5	1 @ 11'-4"	N/A	11'-4"	1 @ 14'-10"	N/A	14'-10"	1 @ 22'-0"	1 @ 3'-7"	25'-7"
4	4	7.5	1 @ 15'-2"	N/A	15'-2"	1 @ 19'-10"	1 @ 3'-7"	23'-5"	1 @ 29'-4"	2 @ 3'-7"	36'-6"
4	4	5	1 @ 14'-6"	N/A	14'-6"	1 @ 18'-11"	N/A	18'-11"	1 @ 28'-1"	2 @ 3'-7"	35'-3"
5	2	8	1 @ 8'-11"	N/A	8'-11"	1 @ 11'-9"	N/A	11'-9"	1 @ 17'-5"	N/A	17'-5"
5	2	6	1 @ 8'-5"	N/A	8'-5"	1 @ 11'-1"	N/A	11'-1"	1 @ 16'-5"	N/A	16'-5"
5	3	8	1 @ 12'-1"	N/A	12'-1"	1 @ 15'-10"	N/A	15'-10"	1 @ 23'-6"	1 @ 4'-7"	28'-1"
5	3	6	1 @ 11'-7"	N/A	11'-7"	1 @ 15'-2"	N/A	15'-2"	1 @ 22'-6"	1 @ 4'-7"	27'-1"
5	4	8	1 @ 15'-3"	N/A	15'-3"	1 @ 20'-0"	1 @ 4'-7"	24'-7"	1 @ 29'-7"	2 @ 4'-7"	38'-9"
5	4	6	1 @ 14'-9"	N/A	14'-9"	1 @ 19'-3"	N/A	19'-3"	1 @ 28'-7"	2 @ 4'-7"	37'-9"
5	5	8	1 @ 18'-5"	N/A	18'-5"	1 @ 24'-1"	2 @ 4'-7"	33'-3"	1 @ 35'-8"	3 @ 4'-7"	49'-5"
5	5	6	1 @ 17'-11"	N/A	17'-11"	1 @ 23'-5"	1 @ 4'-7"	28'-0"	1 @ 34'-8"	2 @ 4'-7"	43'-10"
6	2	8	2 @ 8'-11"	N/A	17'-10"	2 @ 11'-9"	N/A	23'-6"	2 @ 17'-5"	N/A	34'-10"
6	2	7	2 @ 8'-8"	N/A	17'-4"	2 @ 11'-5"	N/A	22'-10"	2 @ 16'-11"	N/A	33'-10"
6	3	8	2 @ 12'-1"	N/A	24'-2"	2 @ 15'-10"	N/A	31'-8"	2 @ 23'-6"	1 @ 5'-7"	52'-7"
6	3	7	2 @ 11'-10"	N/A	23'-8"	2 @ 15'-6"	N/A	31'-0"	2 @ 23'-0"	1 @ 5'-7"	51'-7"
6	4	8	2 @ 15'-3"	N/A	30'-6"	2 @ 20'-0"	1 @ 5'-7"	45'-7"	2 @ 29'-7"	2 @ 5'-7"	70'-4"
6	4	7	2 @ 15'-0"	N/A	30'-0"	2 @ 19'-8"	1 @ 5'-7"	44'-11"	2 @ 29'-1"	2 @ 5'-7"	69'-4"
6	5	8	2 @ 18'-5"	N/A	36'-10"	2 @ 24'-1"	2 @ 5'-7"	59'-4"	2 @ 35'-8"	3 @ 5'-7"	88'-1"
6	5	7	2 @ 18'-2"	N/A	36'-4"	2 @ 23'-9"	2 @ 5'-7"	58'-8"	2 @ 35'-2"	2 @ 5'-7"	81'-6"
6	6	8	2 @ 21'-7"	1 @ 5'-7"	48'-9"	2 @ 28'-3"	2 @ 5'-7"	67'-8"	2 @ 41'-9"	3 @ 5'-7"	100'-3"
6	6	7	2 @ 21'-4"	1 @ 5'-7"	48'-3"	2 @ 27'-11"	2 @ 5'-7"	67'-0"	2 @ 41'-3"	3 @ 5'-7"	99'-3"
7	2	8	2 @ 8'-11"	N/A	17'-10"	2 @ 11'-9"	N/A	23'-6"	2 @ 17'-5"	N/A	34'-10"
7	3	8	2 @ 12'-1"	N/A	24'-2"	2 @ 15'-10"	N/A	31'-8"	2 @ 23'-6"	2 @ 6'-7"	60'-2"
7	4	8	2 @ 15'-3"	N/A	30'-6"	2 @ 20'-0"	2 @ 6'-7"	53'-2"	2 @ 29'-7"	3 @ 6'-7"	78'-11"
7	5	8	2 @ 18'-5"	N/A	36'-10"	2 @ 24'-1"	3 @ 6'-7"	67'-11"	2 @ 35'-8"	4 @ 6'-7"	97'-8"
7	6	8	2 @ 21'-7"	2 @ 6'-7"	56'-4"	2 @ 28'-3"	3 @ 6'-7"	76'-3"	2 @ 41'-9"	5 @ 6'-7"	116'-5"
7	7	8	2 @ 24'-9"	3 @ 6'-7"	69'-3"	2 @ 32'-4"	4 @ 6'-7"	91'-0"	2 @ 47'-10"	6 @ 6'-7"	135'-2"
8	2	8	3 @ 8'-11"	N/A	26'-9"	3 @ 11'-9"	N/A	35'-3"	3 @ 17'-5"	N/A	52'-3"
8	3	8	3 @ 12'-1"	N/A	36'-3"	3 @ 15'-10"	N/A	47'-6"	3 @ 23'-6"	2 @ 7'-7"	85'-8"
8	4	8	3 @ 15'-3"	N/A	45'-9"	3 @ 20'-0"	2 @ 7'-7"	75'-2"	3 @ 29'-7"	3 @ 7'-7"	111'-6"
8	5	8	3 @ 18'-5"	N/A	55'-3"	3 @ 24'-1"	3 @ 7'-7"	95'-0"	3 @ 35'-8"	4 @ 7'-7"	137'-4"
8	6	8	3 @ 21'-7"	2 @ 7'-7"	79'-11"	3 @ 28'-3"	3 @ 7'-7"	107'-6"	3 @ 41'-9"	5 @ 7'-7"	163'-2"
8	7	8	3 @ 24'-9"	3 @ 7'-7"	97'-0"	3 @ 32'-4"	4 @ 7'-7"	127'-4"	3 @ 47'-10"	6 @ 7'-7"	189'-0"
8	8	8	3 @ 27'-11"	3 @ 7'-7"	106'-6"	3 @ 36'-6"	4 @ 7'-7"	139'-10"	3 @ 53'-11"	6 @ 7'-7"	207'-3"
9	2	9	3 @ 9'-3"	N/A	27'-9"	3 @ 12'-1"	N/A	36'-3"	3 @ 17'-11"	N/A	53'-9"
9	3	9	3 @ 12'-4"	N/A	37'-0"	3 @ 16'-2"	N/A	48'-6"	3 @ 24'-0"	3 @ 8'-7"	97'-9"
9	4	9	3 @ 15'-6"	N/A	46'-6"	3 @ 20'-4"	2 @ 8'-7"	78'-2"	3 @ 30'-1"	3 @ 8'-7"	116'-0"
9	5	9	3 @ 18'-8"	N/A	56'-0"	3 @ 24'-5"	3 @ 8'-7"	99'-0"	3 @ 36'-2"	4 @ 8'-7"	142'-10"
9	6	9	3 @ 21'-10"	2 @ 8'-7"	82'-8"	3 @ 28'-7"	3 @ 8'-7"	111'-6"	3 @ 42'-3"	5 @ 8'-7"	169'-8"
9	7	9	3 @ 25'-0"	3 @ 8'-7"	100'-9"	3 @ 32'-8"	4 @ 8'-7"	132'-4"	3 @ 48'-4"	6 @ 8'-7"	196'-6"
9	8	9	3 @ 28'-2"	3 @ 8'-7"	110'-3"	3 @ 36'-10"	4 @ 8'-7"	144'-10"	3 @ 54'-5"	6 @ 8'-7"	214'-9"
9	9	9	3 @ 31'-4"	3 @ 8'-7"	119'-9"	3 @ 40'-11"	5 @ 8'-7"	165'-8"	3 @ 60'-6"	7 @ 8'-7"	241'-7"
10	2	10	3 @ 9'-6"	N/A	28'-6"	3 @ 12'-5"	N/A	37'-3"	3 @ 18'-5"	N/A	55'-3"
10	3	10	3 @ 12'-8"	N/A	38'-0"	3 @ 16'-6"	N/A	49'-6"	3 @ 24'-6"	3 @ 9'-7"	102'-3"
10	4	10	3 @ 15'-10"	N/A	47'-6"	3 @ 20'-8"	2 @ 9'-7"	81'-2"	3 @ 30'-7"	3 @ 9'-7"	120'-6"
10	5	10	3 @ 19'-0"	N/A	57'-0"	3 @ 24'-9"	3 @ 9'-7"	103'-0"	3 @ 36'-8"	4 @ 9'-7"	148'-4"
10	6	10	3 @ 22'-1"	2 @ 9'-7"	85'-5"	3 @ 28'-11"	3 @ 9'-7"	115'-6"	3 @ 42'-9"	5 @ 9'-7"	176'-2"
10	7	10	3 @ 25'-3"	3 @ 9'-7"	104'-6"	3 @ 33'-0"	4 @ 9'-7"	137'-4"	3 @ 48'-10"	6 @ 9'-7"	204'-0"
10	8	10	3 @ 28'-5"	3 @ 9'-7"	114'-0"	3 @ 37'-2"	4 @ 9'-7"	149'-10"	3 @ 54'-11"	6 @ 9'-7"	222'-3"
10	9	10	3 @ 31'-7"	4 @ 9'-7"	133'-1"	3 @ 41'-3"	5 @ 9'-7"	171'-8"	3 @ 61'-0"	7 @ 9'-7"	250'-1"
10	10	10	3 @ 34'-9"	4 @ 9'-7"	142'-7"	3 @ 45'-5"	5 @ 9'-7"	184'-2"	3 @ 67'-1"	8 @ 9'-7"	277'-11"
11	2	11	4 @ 9'-9"	N/A	39'-0"	4 @ 12'-9"	N/A	51'-0"	4 @ 18'-11"	N/A	75'-8"
11	3	11	4 @ 12'-11"	N/A	51'-8"	4 @ 16'-11"	N/A	67'-8"	4 @ 25'-0"	3 @ 10'-7"	131'-9"
11	4	11	4 @ 16'-1"	N/A	64'-4"	4 @ 21'-0"	2 @ 10'-7"	105'-2"	4 @ 31'-1"	3 @ 10'-7"	156'-1"
11	6	11	4 @ 22'-5"	2 @ 10'-7"	110'-10"	4 @ 29'-3"	3 @ 10'-7"	148'-9"	4 @ 43'-3"	5 @ 10'-7"	225'-11"
11	8	11	4 @ 28'-9"	3 @ 10'-7"	146'-9"	4 @ 37'-6"	4 @ 10'-7"	192'-4"	4 @ 55'-5"	6 @ 10'-7"	285'-2"
11	10	11	4 @ 35'-0"	4 @ 10'-7"	182'-4"	4 @ 45'-9"	5 @ 10'-7"	235'-11"	4 @ 67'-7"	8 @ 10'-7"	355'-0"
11	11	11	4 @ 38'-2"	4 @ 10'-7"	195'-0"	4 @ 49'-10"	6 @ 10'-7"	262'-10"	4 @ 73'-8"	9 @ 10'-7"	389'-11"
12	2	12	4 @ 10'-0"	N/A	40'-0"	4 @ 13'-1"	N/A	52'-4"	4 @ 19'-5"	N/A	77'-8"
12	3	12	4 @ 13'-2"	N/A	52'-8"	4 @ 17'-3"	N/A	69'-0"	4 @ 25'-6"	3 @ 11'-7"	136'-9"
12	4	12	4 @ 16'-4"	N/A	65'-4"	4 @ 21'-4"	2 @ 11'-7"	108'-6"	4 @ 31'-7"	4 @ 11'-7"	172'-8"
12	6	12	4 @ 22'-8"	2 @ 11'-7"	113'-10"	4 @ 29'-7"	3 @ 11'-7"	153'-1"	4 @ 43'-9"	5 @ 11'-7"	232'-11"
12	8	12	4 @ 29'-0"	3 @ 11'-7"	150'-9"	4 @ 37'-10"	4 @ 11'-7"	197'-8"	4 @ 55'-11"	7 @ 11'-7"	304'-9"
12	10	12	4 @ 35'-4"	4 @ 11'-7"	187'-8"	4 @ 46'-1"	5 @ 11'-7"	242'-3"	4 @ 68'-1"	8 @ 11'-7"	365'-0"
12	12	12	4 @ 41'-8"	5 @ 11'-7"	224'-7"	4 @ 54'-4"	6 @ 11'-7"	286'-10"	4 @ 80'-3"	10 @ 11'-7"	436'-10"

(Sheet 2 of 2)

TPGBC-ZS

2-17-2017

MODEL: Defaul...  
 FILE: \\benesch\pub\benesch\p-01\Documents\07709\0748\08\Eng\_Docs\_Phase II\Structures\Culvert\_IL\_59\Final\Sheets\022H15-CB08-culvert\_end\_grate\_022.dgn



USER NAME: EOsoul	DESIGNED: EAO	REvised: -
PLOT SCALE: NTS	CHECKED: TPS	REvised: -
DATE: 02/04/2022	DRAWN: AJB	REvised: -
	CHECKED: TPS	REvised: -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**IL RTE 59 DOUBLE BOX CULVERT EXTENSION  
TRAVERSABLE PIPE GRATE FOR BOX CULVERTS (2 of 2)**

SHEET CB-08 OF CB-13 SHEETS


F.A.I.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	548
CONTRACT NO. 62H15				
FAI 55, FAP 338		ILLINOIS	FED. AID PROJECT	




MODEL: D:\p\aut\1\benesch\pub\benesch\cb-09\0709\0748\08\Eng\_Docs\_Phase\_II\Structures\Culvert\_IL\_59\Final\Sheets\02H15-CB09-Weir-Wall  
 FILE: 02H15-CB09-Weir-Wall.dwg




**Weir Wall Elevation**  
(View B-B)




**Weir Wall Elevation**  
(View A-A)




**Weir Wall Elevation**  
(View C-C)




**Weir Wall Plan**  
(Wall reinforcement not shown for clarity)



**SECTION D-D**



**BAR n(E)**



**BAR h4(E)**

**BILL OF MATERIAL**

Bar	No.	Size	Length	Shape
v(E)	115	#4	5'-10"	—
v1(E)	3	#4	4'-0"	—
h(E)	24	#4	16'-7"	—
h1(E)	8	#4	33'-6"	—
h2(E)	4	#4	18'-7"	—
h3(E)	4	#4	12'-7"	—
h4(E)	24	#4	6'-0"	└
t(E)	118	#4	3'-8"	—
n(E)	69	#4	3'-11"	┌
w(E)	20	#4	18'-5"	—
w1(E)	10	#4	37'-2"	—
Structure Excavation			Cu. Yd.	33
Concrete Structures			Cu. Yd.	22.7
Reinforcement Bars, Epoxy Coated			Pound	2,050



USER NAME	Eoskoul	DESIGNED	- EAO	REVISED	-
CHECKED	- TPS	REVISIONS	-	REVISED	-
PLOT SCALE	- NTS	DRAWN	- AJB	REVISED	-
DATE	02/04/2022	CHECKED	- TPS	REVISED	-


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL RTE 59 DOUBLE BOX CULVERT EXTENSION  
WEIR WALL DETAILS**

SHEET CB-09 OF CB-13 SHEETS

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	549
CONTRACT NO. 62H15				
* FAI 55, FAP 338		ILLINOIS	FED. AID PROJECT	


F.A.I.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59		WILL	608	392
STA. TO STA.		FED. AID PROJECT		
FED. ROAD DIST. NO. 1		ILLINOIS		
CONTRACT NO. 60363		R-2		



**Benchmark:** TBM#6: Square cut on top of concrete foundation (1/2" west edge) for the high mast light pole on west side of I-55 near Station 124+00. Elev. 592.98

**Exist. Structure:** None.

**Staging:** None.




**LONGITUDINAL SECTION**

(All dimensions and slopes given at right angles to centerline U.N.O.)

**DESIGN SCOUR TABLE**

Design Scour Elevation	Upstream	Downstream
	584.50	584.30



**DESIGN SPECIFICATIONS**

2002 AASHTO Standard Specifications for Highway Bridges

**LOADING HS20-44**

Allow 50 psf for future wearing surface

**DESIGN STRESSES**

**FIELD UNITS**

f'c = 3,500 psi  
fy = 60,000 psi (reinforcement bars)

**PRECAST UNITS**


f'c = 3,500 psi  
fy = 60,000 psi (welded wire fabric)

**DESIGN FILL HEIGHT**

Maximum Fill Height = 18.9'

**GENERAL NOTES:**

- Cast-in-Place Concrete:** All exposed concrete edges shall have a 3/8" chamfer unless noted otherwise. Chamfer on vertical edges shall be continued a minimum of one foot below finished ground level.
- Reinforcement Bars:** Reinforcement bars shall conform to the requirements of ASTM A 706 Gr. 60 (IL Modified). See Special Provisions.
- Construction:** For backfilling and embankment, see Standard Specifications.
- Precast Box Culvert sections shall conform to the requirements of Article 540.06 of the Standard Specifications and the applicable requirements of AASHTO M 259.
- Lifting holes shall be filled with concrete plugs and mastic after box sections are in place.
- All construction joints shall be bonded.



**PLAN - CULVERT NO. 5**

**LEGEND**


Soil Boring Location

**INDEX OF SHEETS**


- BCF-1 GENERAL PLAN AND ELEVATION
- BCF-2 BOX CULVERT END SECTIONS
- BCF-3 SOIL BORING LOGS

**WATERWAY INFORMATION**

Drainage Area = 60.94 Acres		Low Grade Elev. 607.01 @ Sta. 8030+50				
Flood	Freq. Yr.	Q C.F.S.	Opening - Sq. Ft.	Nat. H.W.E.	Head - Ft.	Headwater El.
Design	50	63.6	n/a	13.47	589.10	n/a
Base	100	83.0	n/a	15.60	593.31	n/a
Max. Calc.	500	141.3	n/a	20.77	589.82	n/a



**PROFILE GRADE SB ILLINOIS ROUTE 59**



**PROFILE GRADE NB ILLINOIS ROUTE 59**

**TOTAL BILL OF MATERIAL**

DESCRIPTION	UNIT	TOTAL
Porous Granular Embankment	Cu. Yd.	240
Box Culvert End Section, Culvert No. 5	Each	2
Precast Concrete Box Culvert 5' X 3' (M259)	Ft.	404

**SHT. BCF-1 OF BCF-3**

REVISIONS	DATE
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.P. ROUTE 338 (ILLINOIS ROUTE 59)  
IL 59 DOUBLE BOX CULVERT  
SECTION (26, 26HB-1 & 114) R-2  
STRUCTURE NUMBER 099-0351  
STATION 7003+50.00 (SB IL 59), WILL COUNTY  
GENERAL PLAN & ELEVATION

DATE: 03/14/08  
DRAWN BY: MDB  
CHECKED BY:

**TENG**

FOR INFORMATION ONLY

MODEL: D:\Defaul...  
 FILE: I:\Bene...  
 ...\Documents\02708\02708-08\Eng\_Docs\_Phase II\Structures\Culvert\_1\_IL\_59\Final\Sheets\02708-08-01-existing\_plans\_021.dgn  
 4-10-2008, 10:26:53  
 ...\Documents\02708\02708-08\Eng\_Docs\_Phase II\Structures\Culvert\_1\_IL\_59\Final\Sheets\02708-08-01-existing\_plans\_021.dgn  
 color: Tables, K:\STANDARDS\TEMP\LA\COLORTABLE.tbl  
 ...\Documents\02708\02708-08\Eng\_Docs\_Phase II\Structures\Culvert\_1\_IL\_59\Final\Sheets\02708-08-01-existing\_plans\_021.dgn  
 4-10-2008, 10:26:53  
 ...\Documents\02708\02708-08\Eng\_Docs\_Phase II\Structures\Culvert\_1\_IL\_59\Final\Sheets\02708-08-01-existing\_plans\_021.dgn  
 color: Tables, K:\STANDARDS\TEMP\LA\COLORTABLE.tbl  
 ...\Documents\02708\02708-08\Eng\_Docs\_Phase II\Structures\Culvert\_1\_IL\_59\Final\Sheets\02708-08-01-existing\_plans\_021.dgn  
 4-10-2008, 10:26:53  
 ...\Documents\02708\02708-08\Eng\_Docs\_Phase II\Structures\Culvert\_1\_IL\_59\Final\Sheets\02708-08-01-existing\_plans\_021.dgn  
 color: Tables, K:\STANDARDS\TEMP\LA\COLORTABLE.tbl






USER NAME	EOSkoul	DESIGNED	- EAO	REVISED	-
CHECKED	- TPS	REVISIONS	-	REVISIONS	-
PLOT SCALE	- NTS	DRAWN	- AJB	REVISIONS	-
DATE	02/04/2022	CHECKED	- TPS	REVISIONS	-

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL RTE 59 DOUBLE BOX CULVERT EXTENSION  
EXISTING PLANS (1 OF 2)  
SHEET CB-10 OF CB-13 SHEETS

F.A.I.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	550
CONTRACT NO. 62H15				
FAI 55, FAP 338		ILLINOIS	FED. AID PROJECT	

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59		WILL	608	393
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
* (25, 26HB-1 & 114) R-2				
CONTRACT NO. 60363				






**STANDARD BOX CULVERT SECTION**

**BAR LIST**



Bar	No.	Size	Length	Shape
b200	4	#4	15'-3"	—
b201	2	#4	17'-4"	—
b202	2	#4	19'-5"	—
b203	6	#4	21'-1"	—
d200	30	#4	6'-4"	—
h200	2	#4	24'-3"	—
h201	16	#4	5'-6"	—
s200	8	#4	19'-3"	—
v200	12	#4	8'-10"	—
<b>Item</b>	<b>Unit</b>	<b>Total</b>		
Reinforcement Bars***	lbs	570		
Concrete Structures***	Cu Yd	10.1		

\*\*\* For information only, cost included with Box Culvert End Section, Culvert No. 5.




**Reinforcement Notes:**  
 (1) Bend bars in the field to fit as required.  
 (2) Cut bars according to Cutting Diagram and use remainder in opposite end.

**Notes:**  
 I, B, F indicates Back Face  
 F, F, indicates Front Face  
 E, F, indicates Each Face



**APRON END SECTION**



**SHT. BCF-2 OF BCF-3**

REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.P. ROUTE 338 (ILLINOIS ROUTE 59)  
 IL 59 DOUBLE BOX CULVERT  
 SECTION (26, 26HB-1 & 114) R-2  
 STRUCTURE NUMBER 099-0351  
 STATION 7003+50.00 (SB IL 59), WILL COUNTY

BOX CULVERT END SECTIONS

DATE: 03/14/08  
 DRAWN BY: MOB  
 CHECKED BY:

**TENG**

FOR INFORMATION ONLY

MODEL: D:\p\11\benesch\pub\benesch\p\11\Documents\107209\10740\08\Eng\_Docs\_Phase\_11\Structures\Culvert\_IL\_59\Final\Sheets\02H15-CB11-existing\_plans-202.dwg  
 FILE: 10740\11\benesch\pub\benesch\p\11\Documents\107209\10740\08\Eng\_Docs\_Phase\_11\Structures\Culvert\_IL\_59\Final\Sheets\02H15-CB11-existing\_plans-202.dwg



USER NAME	Eoskoul	DESIGNED	- EAO	REVISED	-
		CHECKED	- TPS	REVISED	-
PLOT SCALE	NTS	DRAWN	- AJB	REVISED	-
DATE	02/04/2022	CHECKED	- TPS	REVISED	-

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

IL RTE 59 DOUBLE BOX CULVERT EXTENSION  
 EXISTING PLANS (2 OF 2)

F.A.I.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	551
CONTRACT NO. 62H15				
* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

SHEET CB-11 OF CB-13 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	*	WILL	608	394
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
* (26, 26HB-1 & 114) R-2				
CONTRACT NO. 60363				



### SOIL BORING LOG

Page 1 of 1  
Date 9/30/7

ROUTE FAI 55 & FAP 338 (IL 59) DESCRIPTION IL 59 (I-55 TO DUPAGE RIVER AND INTERSTATE 55 AT IL RTE 59) LOGGED BY G. Schaefer

SECTION 26HB-1BR & 114R-1 LOCATION BOX CULVERT UNDER IL 59 SEC. 21 TWP. 35 N. RNG. 9 E. PM. 3rd

COUNTY WILL DRILLING METHOD HOLLOW STEM AUGER HAMMER TYPE AUTOMATIC

STRUCT. NO.	099-C023	D	B	U	M	Surface Water Elev.	ft	D	B	U	M
Station	7003+50.00	E	L	C	O	Stream Bed Elev.	ft	E	L	C	O
BORING NO.	B-301	P	O	S	I	Groundwater Elev.:		P	O	S	I
Station	7003+59	T	W	S		First Encounter	585.7	T	W	S	
Offset	132.0 ft. I.T.	H	S	Qu	T	Upon Completion	573.2	H	S	Qu	T
Northing	1,762,576.77					After	Hrs.				
Easting	1,021,046.77										
Ground Surface Elev.	592.2	ft	(ft)	(6")	(tsf)	(%)					

TOPSOIL	591.4					Medium Dense, Gray GRAVEL with Sand (continued)					
Stiff to Hard, Brown SILTY CLAY trace - gravel	2										
	4	4.5	18.0			End of Boring	570.7				
	6	B									
	4										
	9	5.2	20.0								
	11	B									
	4										
Medium Dense, Brown SAND trace - gravel	583.7										
	6	1.4	21.0								
	5	B	17.0								
Stiff to Hard, Gray SILTY CLAY trace - gravel	584.2										
	1										
	2	1.2	15.0								
	3	B									
	5										
	7	3.4	19.0								
	9	B									
	8										
	12	5.2	18.0								
	13	B									
	7										
	8	2.1	14.0								
	8	B									
Medium Dense, Gray SILTY CLAY LOAM little - gravel	574.2										
	5										
	6		27.0								
	8		15.0								

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)  
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T266)



### SOIL BORING LOG

Page 1 of 1  
Date 9/30/7

ROUTE FAI 55 & FAP 338 (IL 59) DESCRIPTION IL 59 (I-55 TO DUPAGE RIVER AND INTERSTATE 55 AT IL RTE 59) LOGGED BY G. Schaefer

SECTION 26HB-1BR & 114R-1 LOCATION BOX CULVERT UNDER IL 59 SEC. 21 TWP. 35 N. RNG. 9 E. PM. 3rd

COUNTY WILL DRILLING METHOD HOLLOW STEM AUGER HAMMER TYPE AUTOMATIC

STRUCT. NO.	099-C023	D	B	U	M	Surface Water Elev.	ft	D	B	U	M
Station	7003+50.00	E	L	C	O	Stream Bed Elev.	ft	E	L	C	O
BORING NO.	B-302	P	O	S	I	Groundwater Elev.:		P	O	S	I
Station	7003+42	T	W	S		First Encounter	585.0	T	W	S	
Offset	66.0 ft. RT.	H	S	Qu	T	Upon Completion		H	S	Qu	T
Northing	1,762,658.16					After	Hrs.				
Easting	1,020,863.66										
Ground Surface Elev.	591.5	ft	(ft)	(6")	(tsf)	(%)					

TOPSOIL	590.0					Extremely Dense, Brown GRAVEL with Sand					
Hard, Brown SILTY CLAY trace - gravel	2										
	3	4.3	20.0								
	5	B									
	2										
	5	6.4	18.0								
	8	B									
	7										
Medium Dense, Brown SAND trace - gravel	586.0										
	8	6.0	18.0								
	7	B	19.0								
Stiff to Hard, Gray SILTY CLAY trace - gravel	583.5										
	5										
	7	3.2	23.0								
	10	B									
	5										
	9	3.2	22.0								
	12	B									
	5										
	12	4.3	15.0								
	13	B									
	3										
	4	1.6	31.0								
	5	B									
Medium Dense, Gray SILTY CLAY LOAM little - gravel	573.0										
	4										
	6		9.0								
	6	500*	6.0								

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)  
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T266)

SHT. BCF-3 OF BCF-3

REVISIONS	DATE
NAME	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.P. ROUTE 338 (ILLINOIS ROUTE 59)  
IL 59 DOUBLE BOX CULVERT  
SECTION (26, 26HB-1 & 114) R-2  
STRUCTURE NUMBER 099-0351  
STATION 7003+50.00 (SB IL 59), WILL COUNTY

SOIL BORING LOGS

DRAWN BY: MDB  
CHECKED BY:  
DATE: 03/14/08

FOR INFORMATION ONLY

MODEL: D:\p\... \benesch\p\benesch\combenesch\p\91\Documents\07709\07748\08\Eng\_Docs\_Phase II\Structures\Culvert-IL 59\Final\Sheets\02H15-CB12-soil boring-021.dgn  
 FILE NAME: ... \benesch\p\benesch\combenesch\p\91\Documents\07709\07748\08\Eng\_Docs\_Phase II\Structures\Culvert-IL 59\Final\Sheets\02H15-CB12-soil boring-021.dgn  
 3-15-2008, 15:49:37  
 User: ...  
 Plot: ...  
 Plot Scale: ...  
 Date: ...



USER NAME	E0skoul	DESIGNED	- EAO	REVISED	-
PLOT SCALE	NTS	CHECKED	- TPS	REVISED	-
DATE	02/04/2022	DRAWN	- AJB	REVISED	-
		CHECKED	- TPS	REVISED	-

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL RTE 59 DOUBLE BOX CULVERT EXTENSION  
SOIL BORING LOGS (1 OF 2)

SHEET CB-12 OF CB-13 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
59	2018-075-R	WILL	1510	552
CONTRACT NO. 62H15				
* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

# SOIL BORING LOG

Page 1 of 1

Date 8/26/2018

ROUTE Interstate Route 55 DESCRIPTION Culvert Crossing at IL 59 and Seil Road LOGGED BY SSA  
SECTION N/A LOCATION NE 1/4, SEC. S21 TWP. T35N, RNG. R9E 3rd PM  
COUNTY WILL DRILLING METHOD 3.25" HSA: backfilled upon completion HAMMER TYPE GEOPROBE

STRUCT. NO.	Station	D E P T H (ft)	B L O W S (/6")	U C S Qu (tsf)	M O I S T (%)	Surface Water Elev.	Stream Bed Elev.	Groundwater Elev.:	First Encounter	Upon Completion	After	D E P T H (ft)	B L O W S (/6")	U C S Qu (tsf)	M O I S T (%)
Culvert SN 099-0351	N/A					N/A	N/A								
CB-03	7002+84								4	N.E.					
	80' RT														
	591.12														
TOPSOIL: 8" thick, black SILTY CLAY LOAM 590.45															
FILL: Very stiff, brown and gray, SILTY CLAY, trace gravel, moist 589.12															
Hard, brown and gray, SILTY CLAY, trace gravel, moist															
Sample at 2.0 to 4.0'															
--L <sub>c</sub> (%)=39--															
--P <sub>c</sub> (%)=21--															
--%Gravel=1.1--															
--%Sand=7.0--															
--%Silt=52.5--															
--%Clay=39.5--															
581.12 -10															
End of Boring															
-15															
-20															
-30															
-35															
-40															

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)  
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, from 137 (Rev. 8-99)

# SOIL BORING LOG

Page 1 of 1

Date 8/28/2018

ROUTE Interstate Route 55 DESCRIPTION Culvert Crossing at IL 59 and Seil Road LOGGED BY SSA  
SECTION N/A LOCATION NE 1/4, SEC. S21 TWP. T35N, RNG. R9E 3rd PM  
COUNTY WILL DRILLING METHOD 3.25" HSA: backfilled upon completion HAMMER TYPE ATV D-25 (93%)

STRUCT. NO.	Station	D E P T H (ft)	B L O W S (/6")	U C S Qu (tsf)	M O I S T (%)	Surface Water Elev.	Stream Bed Elev.	Groundwater Elev.:	First Encounter	Upon Completion	After	D E P T H (ft)	B L O W S (/6")	U C S Qu (tsf)	M O I S T (%)
Culvert SN 099-0351	N/A					N/A	N/A								
CB-04	8033+42								5.5	11					
	104' RT														
	591.97														
TOPSOIL: 8" thick, black SILTY CLAY LOAM 591.30															
FILL: Hard, brown and gray, SILTY CLAY, trace gravel, moist															
7 4.5+p 16															
9															
10															
588.97															
Hard, brown and gray, SILTY CLAY, trace gravel, moist															
7 5.7S 21															
Sample at 3.5' to 5.0'															
11															
14															
--LL(%)=40, --PL(%)=20															
586.47															
--%Gravel=0.3--															
5 NP 22															
--%Sand=4.7--															
4															
--%Silt=51.7--															
583.97															
--%Clay=43.3--															
4 2.1S 15															
3															
5															
-10															
Loose, brown and gray, coarse grained SAND, saturated															
Very stiff to hard, gray, SILTY CLAY, trace gravel, moist															
9 4.9S 22															
11															
16															
5 2.9S 21															
10															
16															
576.97 -15															
End of Boring															
-20															

The Unconfined Compressive Strength (UCS) Failure Mode is indicated by (B-Bulge, S-Shear, P-Penetrometer)  
The SPT (N value) is the sum of the last two blow values in each sampling zone (AASHTO T206)

BBS, from 137 (Rev. 8-99)

C:\Users\benesch\Documents\07709\07709-08-Eng-Docs-Phase-1\Structures\Culvert-IL-59\Final\Sheets\022H15-CB13-ssl-borings-2018.dgn

## EROSION CONTROL GENERAL NOTES

- THE EROSION CONTROL MEASURES INDICATED ON THE PLANS ARE THE MINIMUM REQUIREMENTS. ADDITIONAL MEASURES MAY BE REQUIRED, AS DIRECTED BY THE ENGINEER. EROSION CONTROL ITEMS ARE CONSIDERED TO BE A HIGH PRIORITY ON THIS CONTRACT. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE RE.
- IDOT SPECIFICATION 280.03 REQUIRES WORK TO BE COORDINATED SO THAT NO MORE THAN 10 ACRES ARE DISTURBED AT A TIME, PARTICULARLY AREAS WHICH DISCHARGE TO WETLAND/WOUS SITES. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG FINAL GRADING AND SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED AT ONCE.
- THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PREVENT POLLUTION OF STORM WATER AND SHALL FOLLOW IEPA & IDOT CONSTRUCTION MEMORANDUM NO. 02-60.
- SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. SOIL STABILIZATION MEASURES SHALL CONSIDER THE TIME OF YEAR, SITE CONDITIONS AND THE USE OF TEMPORARY OR PERMANENT MEASURES.
- THE MAINTENANCE AND REPAIR OR REPLACEMENT OF EROSION CONTROL ITEMS, WHEN DIRECTED BY THE ENGINEER, WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED PAY ITEMS. ALL ESC MEASURES WILL BE MAINTAINED IN ACCORDANCE WITH THE IDOT EROSION AND SEDIMENT CONTROL FIELD GUIDE FOR CONSTRUCTION INSPECTION AND IDOT'S BEST MANAGEMENT PRACTICES MAINTENANCE GUIDE: ([HTTP://WWW.IDOT.ILLINOIS.GOV/TRANSPORTATION-SYSTEM/ENVIRONMENT/EROSION-AND-SEDIMENT-CONTROL](http://www.idot.illinois.gov/transportation-system/environment/erosion-and-sediment-control))
- ALL STORM SEWER FACILITIES THAT ARE OR WILL BE FUNCTIONING DURING CONSTRUCTION SHALL BE PROTECTED, FILTERED OR OTHERWISE TREATED TO REMOVE SEDIMENT. MUD AND SEDIMENT DEPOSITS SHALL BE REMOVED FROM THE ROADWAY AT THE END OF EACH WORK DAY BY SHOVELING AND/OR SWEEPING.
- INLET FILTERS SHALL BE PLACED ON ALL CATCH BASINS, INLETS, AND MANHOLES WITH OPEN GRATES.
- TEMPORARY EROSION CONTROL SEEDING MIXTURE WILL DEPEND ON THE TIME OF YEAR SEED IS TO BE APPLIED AND SHALL BE IN ACCORDANCE WITH ARTICLE 1081.15(G) OF THE STANDARD SPECIFICATIONS. STABILIZATION OF ALL AREAS DISTURBED BY CONSTRUCTION SHALL COMMENCE WITH 1 DAY AND BE COMPLETE WITHIN 14 DAYS FOR ANY PORTION OF THE SITE THAT WILL BE IDLE FOR MORE THAN 14 DAYS. IF THAT PORTION OF THE SITE WILL BECOME ACTIVE AGAIN AFTER 14 DAYS, TEMPORARY STABILIZATION MEASURES CAN BE USED.
- THE CONTRACTOR SHALL ATTACH A MINIMUM OF 2 ALUMINUM SIGNS WITH THE FOLLOWING TEXT: PROTECTED WETLAND NO INTRUSION. THE SIGN(S) SHALL BE ATTACHED TO THE TEMPORARY FENCE BY A METHOD APPROVED BY THE ENGINEER. THESE SIGNS SHALL BE PLACED AT THE BOUNDARY OF ALL UN-IMPACTED WETLANDS OR WOUS SITES. THE SIGN(S) WILL BE PROVIDED BY THE DEPARTMENT AND SHALL BE PICKED UP BY THE CONTRACTOR FROM THE DISTRICT ONE ROADSIDE DEVELOPMENT LANDSCAPE ARCHITECT IN SCHAUMBURG, ILLINOIS. SCHEDULING THE PICKUP OF THE SIGNS CAN BE ARRANGED BY CONTACTING THE DISTRICT ONE ROADSIDE DEVELOPMENT UNIT AT (847) 705-4171. WHEN WORK HAS BEEN COMPLETED, UNDAMAGED OR REPLACED SIGNS SHALL BE RETURNED TO THE DISTRICT ONE ROADSIDE DEVELOPMENT UNIT. THE COST OF PICKING UP AND RETURNING THE SIGNS WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR TEMPORARY FENCE.
- DUST CONTROL MEASURES WILL BE IMPLEMENTED IN ACCORDANCE WITH ARTICLE 107.36 OF THE STANDARD SPECIFICATIONS.
- WHENEVER DURING CONSTRUCTION OPERATIONS, LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC., SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF THE CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- BROADCASTING OF THE SEED BY MACHINE, HAND METHODS, HYDRAULIC SEEDING OR OTHER METHODS APPROVED BY THE ENGINEER WILL BE ALLOWED FOR TEMPORARY EROSION CONTROL SEEDING.
- TOPSOIL AND FERTILIZER NUTRIENTS ARE NOT REQUIRED FOR TEMPORARY EROSION CONTROL SEEDING.
- SEED BED PREPARATION WILL NOT BE REQUIRED FOR TEMPORARY EROSION CONTROL SEEDING IF THE SOIL IS IN A LOOSE CONDITION. LIGHT DISKING SHALL BE DONE IF THE SOIL IS HARD PACKED OR CAKED.
- ALL PERIMETER EROSION BARRIER AND TEMPORARY FENCE SHALL BE INSTALLED WITHIN THE TEMPORARY EASEMENT, PROPOSED RIGHT-OF-WAY OR EXISTING RIGHT-OF-WAY.
- EROSION CONTROL BLANKET SHALL BE PLACED IN ACCORDANCE WITH THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS AFTER TEMPORARY EROSION CONTROL SEEDING HAS BEEN COMPLETED ON ALL AREAS WITH SLOPES OF 1:3 (V:H) OR STEEPER, AS SHOWN ON THE PLANS, OR AS DIRECTED BY THE ENGINEER.
- THE CONSTRUCTION LIMITS WILL BE STAKED BY THE CONTRACTOR PRIOR TO COMMENCING CONSTRUCTION. THE CONSTRUCTION LIMITS MAY BE ADJUSTED BY THE ENGINEER AND NO ADDITIONAL COMPENSATION WILL BE PAID TO THE CONTRACTOR FOR CHANGED CONSTRUCTION LIMITS.
- ALL EXISTING STRUCTURES OR PIPES NOT SHOWN ON EROSION CONTROL PLANS SHALL BE REMOVED OR PLUGGED UNTIL REMOVAL IS POSSIBLE DURING THE CONSTRUCTION SO THAT NO SEDIMENT CAN ENTER THE DRAINAGE SYSTEM. THIS SHALL BE CONSIDERED IN THE COST OF THE REMOVAL OF EXISTING STRUCTURES.
- ALL TEMPORARY CONNECTIONS FOR TEMPORARY PIPE CULVERTS INTO EXISTING/PROPOSED STRUCTURES/PIPES SHALL BE CONSIDERED INCLUDED IN THE UNIT PRICE FOR PIPE CULVERT OF THE CLASS, TYPE, SIZE (TEMPORARY).
- ANY REQUIRED ADJUSTMENT AND/OR RECONSTRUCTION OF THE PROPOSED STRUCTURE TO FINAL RIM ELEVATION SHALL NOT BE PAID FOR SEPARATELY, THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE PROPOSED STRUCTURE.
- ALL RIM AND INVERTS FOR TEMPORARY DRAINAGE STRUCTURES ARE ESTIMATES AND NEED TO BE FIELD VERIFIED, NOTIFY THE ENGINEER OF ANY DISCREPANCIES PRIOR TO INSTALLATION. NO EXTRA COMPENSATION WILL BE PROVIDED FOR ANY DISCREPANCIES DETERMINED IN THE FIELD.
- SALVAGED TOPSOIL SHALL BE PLACED ON WELL DRAINED LAND AWAY FROM INTERMITTENT AND LIVE STEAMS OR WETLANDS WITH THE APPROPRIATE RUNOFF CONTROL AND SEDIMENT CONTROL MEASURES INSTALLED AROUND THE STORAGE SITE, AND STABILIZED IN ACCORDANCE WITH MULCH METHOD 2 IMMEDIATELY WHEN THE TOPSOIL SHALL BE UNDISTURBED FOR 14 DAYS, AND STABILIZATION SHALL BE COMPLETED WITHIN 14 DAYS. THE CONTRACTOR WILL PROVIDE AN ADEQUATE QUANTITY OF SILT FENCE TO CONTROL THE PERIMETER OF THE STOCK PILE. SUGGESTED STOCKPILE LOCATIONS HAVE BEEN INCLUDED IN THE PLANS. ACTUAL STOCKPILE LOCATIONS SHALL BE DETERMINED BY THE CONTRACTOR AND SUBMITTED TO THE ENGINEER FOR APPROVAL.
- SEDIMENT LADEN DEWATERING DISCHARGE MUST BE DIRECTED TO AN APPROVED SEDIMENT TRAPPING MEASURE PRIOR TO RELEASE FROM THE SITE.
- ALL EROSION AND SEDIMENT CONTROL (ESC) MEASURES SHOULD BE CHECKED WEEKLY AND AFTER EACH RAINFALL, 0.5 INCHES OR GREATER IN A 24 HOUR PERIOD, OR EQUIVALENT SNOWFALL. ADDITIONALLY DURING WINTER MONTHS, ALL MEASURES SHOULD BE CHECKED AFTER EACH SIGNIFICANT SNOWFALL.
- THIS PROJECT REQUIRES A US ARMY CORPS OF ENGINEERS (USACE) 404 PERMIT THAT WILL BE SECURED BY THE DEPARTMENT. AS A CONDITION OF THIS PERMIT, THE CONTRACTOR WILL NEED TO SUBMIT AN IN-STREAM WORK PLAN TO THE DEPARTMENT FOR APPROVAL. GUIDELINES ON ACCEPTABLE IN-STREAM WORK TECHNIQUES CAN BE FOUND ON THE USACE WEBSITE ([WWW.LRC.USACE.ARMY.MIL/](http://www.lrc.usace.army.mil/)). THE USACE DEFINES AND DETERMINES IN-STREAM WORK. THE COST OF ALL MATERIALS AND LABOR NECESSARY TO COMPLY WITH THE ABOVE PROVISIONS TO PREPARE AND IMPLEMENT AN IN-STREAM WORK PLAN WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- PIPES BEING CONSTRUCTED IN STAGE SHALL BE PLUGGED BEFORE BACKFILLING AND FREE OF DEBRIS WHEN FINAL CONNECTION IS MADE.
- THE CONTRACTOR SHOULD PROVIDE TO THE RE A PLAN TO ENSURE THAT A STABILIZED FLOW LINE WILL BE PROVIDED DURING STORM SEWER CONSTRUCTION. THE USE OF A STABILIZED FLOW LINE BETWEEN INSTALLED STORM SEWER AND OPEN DISTURBANCE WILL REDUCE THE POTENTIAL FOR THE OFFSITE DISCHARGE OF SEDIMENT-BEARING WATERS, ESPECIALLY WHEN RAIN IS FORECASTED, SO THAT FLOW WILL NOT ERODE. LACK OF APPROVED PLAN OR FAILURE TO COMPLY WILL RESULT IN AN ESC DEFICIENCY DEDUCTION.
- ALL ESC MEASURES WILL BE MAINTAINED IN ACCORDANCE WITH THE IDOT EROSION AND SEDIMENT CONTROL FIELD GUIDE FOR CONSTRUCTION INSPECTION FOUND ON THE CONSTRUCTION TAB AT. ([HTTP://WWW.IDOT.ILLINOIS.GOV/TRANSPORTATION-SYSTEM/ENVIRONMENTAL/EROSION-AND-SEDIMENT-CONTROL](http://www.idot.illinois.gov/transportation-system/environmental/erosion-and-sediment-control/))
- TEMPORARY OR PERMANENT STABILIZATION SHALL BE INITIATED IMMEDIATELY UPON COMPLETION OF DISTURBANCE OR IF THE WORK AREA IS TO BE LEFT UNDISTURBED FOR 14 DAYS OR MORE.
- UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG FINAL GRADING AND SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED AT ONE TIME.
- EROSION CONTROL ITEMS ARE CONSIDERED TO BE A HIGH PRIORITY ON THIS CONTRACT. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE RE.
- THIS PROJECT REQUIRES A US ARMY CORPS OF ENGINEERS (USACE) 404 PERMIT THAT WILL BE SECURED BY THE DEPARTMENT. AS A CONDITION OF THIS PERMIT, THE CONTRACTOR WILL NEED TO SUBMIT AN IN-STREAM WORK PLAN TO THE DEPARTMENT FOR APPROVAL. GUIDELINES ON ACCEPTABLE IN-STREAM WORK TECHNIQUES CAN BE FOUND ON THE USACE WEBSITE. THE USACE DEFINES AND DETERMINES IN-STREAM WORK. THE COST OF ALL MATERIALS AND LABOR NECESSARY TO COMPLY WITH THE ABOVE PROVISIONS TO PREPARE AND IMPLEMENT AN IN-STREAM WORK PLAN WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED WITH THE EXCEPTION OF COFFERDAMS WHICH WILL BE PAID FOR AS COFFERDAM (TYPE 1) (IN-STREAM /WETLAND WORK) WITH A BASIS OF PAYMENT OF EACH.

MODEL: Default  
FILE: \\na16c1-pub\bea\tech-pub\bea\tech-pub\01\Documents\107005\107040\_001\Eng\_Docs\_Phase 1\FESC (Thomas)\D162H15-shi-ESC-gennote-001.dgn



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
	DRAWN - JHAITSMA	REVISED -
PLOT SCALE = 20,0000 */ in.	CHECKED - VMICEK	REVISED -
PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL PLAN  
GENERAL NOTES**

SCALE: SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2018-075-R	WILL	1510	554
CONTRACT NO. 62H15				
* FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

D:\62H15-shi-ESC-gennote-001.dgn  
50103  
2012/11/30

STONE RIPRAP AND FILTER FABRIC table with columns: STATION, OFFSET, STONE RIPRAP CLASS A3, STONE RIPRAP CLASS A4, STONE RIPRAP CLASS A5, FILTER FABRIC (SQ YD), W1 (FEET), W2 (FEET), LA (FEET). Includes sections for EX I-55, EX E FRONTAGE RD, EX W FRONTAGE RD, and EX SEIL RD.

STONE RIPRAP AND FILTER FABRIC table with columns: STATION, OFFSET, STONE RIPRAP CLASS A3, STONE RIPRAP CLASS A4, STONE RIPRAP CLASS A5, FILTER FABRIC (SQ YD), W1 (FEET), W2 (FEET), LA (FEET). Includes sections for EX IL RTE 59, PR IL RTE 59 SB, PR IL RTE 59 NB, PR RAMP B NB, PR RAMP C NB, PR RAMP D SB, and PR ROCK RUN CROSSINGS DR. Includes a PROJECT TOTAL row.

PERIMETER EROSION BARRIER table with columns: STATION, OFFSET, STATION, OFFSET, QUANTITY (FT). Includes sections for IL RTE 59 SB STAGE 1, RAMP D SB STAGE 1, ROCK RUN CROSSINGS DR STAGE 1, SEIL RD STAGE 1, and W FRONTAGE RD STAGE 1. Includes a STAGE 1 TOTAL row.

TEMPORARY FENCE table with columns: STATION, OFFSET, STATION, OFFSET, QUANTITY (FT). Includes EX IL RTE 59 STAGE 1 and STAGE 1 TOTAL.

TEMPORARY FENCE table with columns: STATION, OFFSET (FT), STATION, OFFSET (FT), QUANTITY (FT). Includes I-55 STAGE 2 and STAGE 2 TOTAL.

STABILIZED CONSTRUCTION ENTRANCE table with columns: STAGE, STATION, OFFSET, QUANTITY (SQ YD). Includes a TOTAL row.

PERIMETER EROSION BARRIER table with columns: STATION, OFFSET, STATION, OFFSET, QUANTITY (FT). Includes W FRONTAGE RD STAGE 1A and STAGE 1A TOTAL.

PERIMETER EROSION BARRIER table with columns: STATION, OFFSET, STATION, OFFSET, QUANTITY (FT). Includes SEIL RD STAGE 2 and STAGE 2 TOTAL.



USER NAME = Vincem
DESIGNED - JCROSS
DRAWN - JHAITSMA
PLOT SCALE = 2,000' / in.
PLOT DATE = 3/10/2022

REVISD -
REVISD -
CHECKED - VMICEK
DATE - 03/16/2022

REVISD -
REVISD -
REVISD -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
EROSION AND SEDIMENT CONTROL

SCALE: SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
= 2018-075-R WILL 1510 555
CONTRACT NO. 62H15

MODEL: Default
FILE: 62h15-shi-FSC-schedule-01.dgn
D:\62h15-shi-FSC-schedule-01.dgn
50103
2012/11/30





INLET & PIPE PROTECTION		
STATION	OFFSET	QUANTITY (EACH)
<b>I-55 STAGE 1</b>		
290+90	83.1' RT	1
<b>EX IL 59 STAGE 1</b>		
7489+51	70.7' RT	1
7489+56	79.6' RT	1
7492+32	95.0' RT	1
<b>EX RAMP C STAGE 1</b>		
8011+28	115.5' RT	1
8035+40	128.2' RT	1
<b>EX RAMP D STAGE 1</b>		
7007+05	45.0' RT	1
<b>PR IL RTE 59 SB STAGE 1</b>		
7027+61	36.5' LT	1
7029+36	18.1' LT	1
7031+11	15.9' LI	1
7033+00	15.0' LT	1
7037+00	58.4' RT	1
<b>PR IL RTE 59 NB STAGE 1</b>		
8035+39	68.8' LT	1
<b>RAMP B N STAGE 1</b>		
1107+26	75.8' RT	1
1108+93	40.3' LT	1
1110+06	111.4' LT	1
1110+50	54.4' RT	1
1118+00	28.0' RT	1
1118+50	58.5' LT	1
1119+50	19.6' RT	1
1127+23	47.1' RT	1
1128+23	89.8' RT	1
<b>RAMP D SB STAGE 1</b>		
404+32	66.0' RT	1
408+50	112.8' LT	1
410+14	89.5' LT	1
<b>ROCK RUN CROSSINGS DR STAGE 1</b>		
6063+55	32.1' LT	1
6078+50	32.8' RT	1
6089+10	33.0' RT	1
6095+50	32.0' RT	1
<b>EX E FRONTAGE RD STAGE 1</b>		
16098+67	35.3' RT	1
<b>W FRONTAGE RD STAGE 1</b>		
5543+76	24.9' LT	1
5544+08	78.2' RT	1
<b>SEIL RD STAGE 1</b>		
3997+95	22.1' LT	1
4001+16	25.6' LT	1
4001+58	17.8' RT	1
4002+45	18.0' RT	1
4002+45	26.8' RT	1
4003+25	18.2' RT	1
4003+84	28.0' RT	1
4005+61	21.6' RT	1
4009+28	43.2' RT	1
<b>STAGE 1 TOTAL</b>		<b>41</b>

INLET & PIPE PROTECTION		
STATION	OFFSET	QUANTITY (EACH)
<b>I-55 STAGE 2</b>		
279+00	86.5' LT	1
290+90	92.6' RT	1
296+00	105.5' RT	1
301+50	82.5' RT	1
309+18	78.8' RT	1
310+50	85.0' RT	1
329+00	88.2' RT	1
329+06	92.3' LT	1

INLET & PIPE PROTECTION		
STATION	OFFSET	QUANTITY (EACH)
330+94	102.6' LT	1
335+88	107.8' LT	1
337+64	65.7' RT	1
<b>PR IL RTE 59 NB STAGE 2</b>		
8001+36	145.1' LT	1
8007+10	83.0' RT	1
8010+73	101.5' LT	1
8014+00	87.0' LT	1
8021+95	1.3' RT	1
<b>RAMP C NB STAGE 2</b>		
809+08	75.9' RT	1
<b>RAMP D SB STAGE 2</b>		
418+65	49.0' LT	1
<b>EX E FRONTAGE RD STAGE 2</b>		
16112+82	24.7' RT	1
<b>W FRONTAGE RD STAGE 2</b>		
5541+69	45.0	1
<b>SEIL RD STAGE 2</b>		
4005+65	24.0' RT	1
<b>STAGE 2 TOTAL</b>		<b>21</b>

INLET & PIPE PROTECTION		
STATION	OFFSET	QUANTITY (EACH)
<b>PR IL RTE 59 NB STAGE 2A</b>		
8010+73	101.5' LT	1
8014+00	87.0' LT	1
<b>RAMP B NB STAGE 2A</b>		
1108+93	40.3' LT	1
<b>RAMP C NB STAGE 2A</b>		
812+30	22.0' RT	1
<b>STAGE 2A TOTAL</b>		<b>4</b>

INLET & PIPE PROTECTION		
STATION	OFFSET	QUANTITY (EACH)
<b>SEIL RD STAGE 3</b>		
4009+98	52.0' LT	1
<b>STAGE 3 TOTAL</b>		<b>1</b>

TEMPORARY DITCH CHECK		
STATION	OFFSET	QUANTITY (FT)
<b>I-55 STAGE 1</b>		
252+24	99.4' RT	10
253+49	105.9' RT	10
253+65	109.5' RT	10
253+82	113.2' RT	10
253+98	116.9' RT	10
270+84	75.3' RT	10
272+50	73.5' LT	10
273+00	90.2' RT	10
277+50	82.3' LT	10
282+50	74.6' LT	10
283+50	105.4' RT	10
284+18	67.7' LT	10
285+31	95.8' RT	10
287+00	93.5' RT	10
287+81	91.9' RT	10
290+00	88.6' RT	10
<b>PR IL RTE 59 SB STAGE 1</b>		
7002+50	102.0' RT	10
7025+27	41.1' LT	10



TEMPORARY DITCH CHECK		
STATION	OFFSET	QUANTITY (FT)
7025+54	46.1' LT	10
7025+81	49.6' LT	10
7026+09	50.8' LT	10
7026+36	50.8' LT	10
7026+64	48.5' LT	10
7026+89	44.6' LT	10
7027+13	40.4' LT	10
7027+37	38.5' LT	10
7027+85	32.7' LT	10
7028+42	26.1' LT	10
7029+00	21.2' LT	10
7030+50	63.8' RT	10
7032+50	56.0' RT	10
7034+50	59.9' RT	10
7036+50	59.1' RT	10
<b>PR IL RTE 59 NB STAGE 1</b>		
8025+45	110.6' LT	10
8025+98	115.3' LT	10
8028+00	95.1' LT	10
8029+89	75.7' LT	10
8031+89	58.1' LT	10
8033+89	55.8' LT	10
<b>RAMP B NB STAGE 1</b>		
1108+50	67.5' RT	10
1111+50	59.0' RT	10
1111+50	85.3' LT	10
1112+50	52.4' RT	10
1113+00	79.1' LT	10
1113+50	45.2' RT	10
1114+00	74.1' LT	10
1114+28	38.6' RT	10
1114+68	34.9' RT	10
1115+00	68.6' LT	10
1115+09	33.1' RT	10
1115+25	67.2' LT	10
1115+50	40.4' RT	10
1115+50	66.5' LT	10
1117+50	20.3' RT	10
1117+85	68.4' LT	10
1118+72	54.4' LT	10
1119+00	19.7' RT	10
1119+03	50.7' LT	10
1119+34	47.5' LT	10
<b>RAMP B SB STAGE 1</b>		
1202+00	92.7' LT	10
1203+00	87.7' LT	10
1203+06	39.1' RT	10
1203+41	54.8' RT	10
1203+73	71.2' RT	10
1204+00	82.4' LT	10
1204+05	72.6' RT	10
1204+37	58.7' RT	10
<b>RAMP D SB STAGE 1</b>		
400+26	54.1' RT	10
400+37	55.0' RT	10
400+48	55.9' RT	10
400+59	56.8' RT	10
400+95	62.2' RT	10
401+20	66.6' RT	10
401+34	66.7' RT	10
401+48	66.9' RT	10
401+62	67.0' RT	10
402+87	69.3' RT	10
404+12	67.5' RT	10
405+62	42.6' LT	10
406+00	60.5' RT	10
406+02	59.9' LT	10
406+43	77.1' LT	10
406+91	91.9' LT	10

TEMPORARY DITCH CHECK		
STATION	OFFSET	QUANTITY (FT)
407+42	103.0' LT	10
407+95	110.0' LT	10
408+00	53.8' RT	10
409+50	46.6' RT	10
411+17	66.0' LT	10
412+13	38.6' LT	10
413+00	35.9' RT	10
<b>ROCK RUN CROSSINGS STAGE 1</b>		
6062+50	41.1' LT	10
6079+50	35.9' RT	10
6080+50	35.3' RT	10
6081+39	36.0' RT	10
6088+00	25.7' RT	10
6091+50	36.2' RT	10
6091+89	28.3' LT	10
6092+07	31.3' LT	10
6092+18	33.5' LT	10
6092+65	40.0' LT	10
6093+12	46.3' LT	10
6093+59	48.8' LT	10
6094+00	32.9' RT	10
6096+24	31.6' RT	10
6096+80	31.6' RT	10
6097+48	31.7' RT	10
<b>STAGE 1 TOTAL</b>		<b>1,060</b>

TEMPORARY DITCH CHECK		
STATION	OFFSET	QUANTITY (FT)
<b>RAMP D SB STAGE 1A</b>		
415+00	32.1' RT	10
416+68	68.8' LT	10
417+00	34.7' RT	10
417+68	69.7' LT	10
418+85	60.4' LT	10
419+65	56.4' RT	10
419+66	22.5' RT	10
420+32	22.7' RT	10
<b>STAGE 1A TOTAL</b>		<b>80</b>

TEMPORARY DITCH CHECK		
STATION	OFFSET	QUANTITY (FT)
<b>I-55 STAGE 2</b>		
258+00	68.0' RT	10
258+50	74.7' RT	10
262+00	77.2' RT	10
264+00	80.1' RT	10
265+00	81.9' RT	10
265+50	77.3' LT	10
265+99	71.1' RT	10
266+50	75.6' LT	10
266+99	68.4' RT	10
267+50	74.5' LT	10
267+99	67.9' RT	10
268+50	75.8' LT	10
269+18	69.8' RT	10
269+50	73.5' LT	10
270+25	73.5' LT	10
272+50	73.5' LT	10
280+19	90.1' RT	10
280+38	90.1' RT	10
280+50	90.1' RT	10
281+00	94.0' RT	10
281+50	100.8' RT	10

TEMPORARY DITCH CHECK		
STATION	OFFSET	QUANTITY (FT)
282+00	114.1' RT	10
283+50	105.4' RT	10
285+31	95.8' RT	10
287+00	93.5' RT	10
287+81	91.9' RT	10
290+00	88.6' RT	10
291+50	90.1' RT	10
293+13	91.5' RT	10
293+76	95.8' RT	10
294+39	98.7' RT	10
295+02	101.5' RT	10
295+65	104.3' RT	10
296+17	103.3' RT	10
296+35	100.7' RT	10
296+52	98.0' RT	10
296+69	95.3' RT	10
296+90	91.9' RT	10
298+00	89.6' RT	10
298+50	86.4' RT	10
299+50	81.5' RT	10
299+50	109.7' LT	10
300+50	79.9' RT	10
301+50	100.5' LT	10
303+00	83.0' RT	10
303+34	107.1' LT	10
305+00	82.3' RT	10
306+67	106.0' LT	10
307+00	79.9' RT	10
310+00	107.0' LT	10
311+00	105.1' LT	10
312+00	84.6' RT	10
312+00	103.1' LT	10
313+00	101.0' LT	10
313+25	98.9' LT	10
315+50	100.0' LT	10
317+00	85.0' RT	10
317+50	99.8' LT	10
318+00	83.1' RT	10
319+00	82.7' RT	10
319+50	97.3' LT	10
320+00	81.5' RT	10
320+50	81.5' RT	10
321+00	81.5' RT	10
321+50	88.6' LT	10
322+00	81.5' RT	10
322+50	81.5' RT	10
322+50	89.0' LT	10
323+00	81.5' RT	10
323+00	89.0' LT	10
323+50	81.5' RT	10
323+50	89.9' LT	10
324+00	81.5' RT	10
324+00	88.7' LT	10
324+50	81.5' RT</	



TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET, TYP

TEMPORARY DITCH CHECK, TYP


TEMPORARY PAVEMENT, TYP

INLET FILTER PLACED IN PREVIOUS STAGE, TYP

**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: h:\a11\esc\p1\subareaesc\p1\subareaesc.dwg  
 D:\162H15-shi-ESC-55-stage1-003.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1**

SCALE: 1"=50'    SHEET    OF    SHEETS    STA. Sta    TO STA. ToSta


F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	558
CONTRACT NO. 62H15				
FAI 55, FAP 338    ILLINOIS    FED. AID PROJECT				



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: h:\m\esc\_p\subareaesc-pw-bentley.com\benesc-esc-01\Documents\1107005\10740\_00\Eng\_Docs\_Phase\_1\FESC-[Thomas]D162H15-shi-ESC-55-stage1-004.dgn  
 D:\62H15-shi-ESC-55-stage1-004.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------


F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	559
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: 62H15-shi-ESC-55-stage1-005.dgn  
 MODEL: Default  
 FILE: 62H15-shi-ESC-55-stage1-005.dgn  
 MODEL: Default  
 FILE: 62H15-shi-ESC-55-stage1-005.dgn



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1**

SCALE: 1"=50'    SHEET    OF    SHEETS    STA. Sta    TO STA. ToSta

F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	560
CONTRACT NO. 62H15				
FAI 55, FAP 338    ILLINOIS    FED. AID PROJECT				


D:\62H15-shi-ESC-55-stage1-005.dgn  
50103  
2012/11/30



**EROSION CONTROL LEGEND**

- WORK ZONE AREA
- TEMPORARY PAVEMENT
- STABILIZED CONSTRUCTION ENTRANCE
- TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
- TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
- ITEM PLACED IN PREVIOUS STAGE
- PERIMETER EROSION BARRIER
- TEMPORARY FENCE
- WASHOUT BASIN
- INLET AND PIPE PROTECTION
- INLET FILTER
- TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: h:\m\esc\_p\subareaesc-pw-bentley.com\benefit\esc-pw-01\Documents\10700510740\_001\Eng\_Docs\_Phase\_1\FESC\_T\Thomas\1062H15-shi-ESC-55-stage1-006.dgn  
 D:\62H15-shi-ESC-55-stage1-006.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta	F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
							2018-075-R	WILL	1510	561
						CONTRACT NO. 62H15				
						FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

- WORK ZONE AREA
- TEMPORARY PAVEMENT
- STABILIZED CONSTRUCTION ENTRANCE
- TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
- TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
- ITEM PLACED IN PREVIOUS STAGE
- PERIMETER EROSION BARRIER
- TEMPORARY FENCE
- WASHOUT BASIN
- INLET AND PIPE PROTECTION
- INLET FILTER
- TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: 62H15-shi-ESC-55-stage1-007.dgn  
 D:\62H15-shi-ESC-55-stage1-007.dgn Phase 1\ESC (Thomas)\62H15-shi-ESC-55-stage1-007.dgn





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>EROSION AND SEDIMENT CONTROL</b>	
<b>I-55 - STAGE 1</b>	
SCALE: 1"=50'	SHEET OF SHEETS STA. Sta TO STA. ToSta


F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	562
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

D:\62H15-shi-ESC-55-stage1-007.dgn  
50103  
2012/11/30



**EROSION CONTROL LEGEND**

- WORK ZONE AREA
- TEMPORARY PAVEMENT
- STABILIZED CONSTRUCTION ENTRANCE
- TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
- TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
- ITEM PLACED IN PREVIOUS STAGE
- PERIMETER EROSION BARRIER
- TEMPORARY FENCE
- WASHOUT BASIN
- INLET AND PIPE PROTECTION
- INLET FILTER
- TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: 62H15-shi-ESC-55-stage1-008.dgn  
 PROJECT: 62H15-shi-ESC-55-stage1-008.dgn  
 USER: VinceM  
 DATE: 3/10/2022



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1**

SCALE: 1"=50'    SHEET OF SHEETS    STA. Sta    TO STA. ToSta

F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	563
CONTRACT NO. 62H15				
FAI 55, FAP 338    ILLINOIS    FED. AID PROJECT				


D:\62H15-shi-ESC-55-stage1-008.dgn  
50103  
2012/11/30



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: h:\mfc\p\subareaesc\p\subareaesc.dwg  
 D:\62H15-shi-ESC-55-stage1-009.dgn  
 50103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1**

SCALE: 1"=50' SHEET OF SHEETS STA. Sta TO STA. ToSta


F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	564
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				





**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\na11c:\pub\subarea\esc\pwr\ben\by.com\ben\esc\pwr\01\Documents\1107005\10740\_00\Eng\_Docs\_Phase\_1\FESC (Thomas)\D162H15-shi-ESC-55-stage1-010.dgn  
 D:\62H15-shi-ESC-55-stage1-010.dgn  
 50103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	565
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				


**NOTE**  
 PR DRAINAGE STRUCTURES TO BE INSTALLED THAT CANNOT BE BROUGHT TO FINAL GRADE SHALL BE CAPPED WITH A STEEL PLATE UNTIL FINAL ADJUSTMENT CAN BE MADE. THE STEEL PLATE AND FINAL ADJUSTMENT SHALL BE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION, (SPECIAL).



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: h:\mfg\p\subareaesc\p\subareaesc.dwg  
 USER: vince  
 PLOT DATE: 3/10/2022  
 PLOT SCALE: 100,0000' / in.  
 D:\62H15-shi-FSC-IL59-RampD-stage1-001.dgn  
 50103  
 2012/11/30





USER NAME = vinceM	DESIGNED - JCROSS	REVISED -
	DRAWN - JHAITSMA	REVISED -
PLOT SCALE = 100,0000' / in.	CHECKED - VMICEK	REVISED -
PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**


**EROSION AND SEDIMENT CONTROL  
 IL 59 - STAGE 1**

SCALE: 1"=50' SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	566
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



EROSION CONTROL LEGEND	
	WORK ZONE AREA
	TEMPORARY PAVEMENT
	STABILIZED CONSTRUCTION ENTRANCE
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
	ITEM PLACED IN PREVIOUS STAGE
	PERIMETER EROSION BARRIER
	TEMPORARY FENCE
	WASHOUT BASIN
	INLET AND PIPE PROTECTION
	INLET FILTER
	TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: thomas\_e\_group\subarea\esc\p\62h15-shi-esc-il-59-rampd-stage1-002.dgn  
 PROJECT: 62H15-shi-esc-il-59-rampd-stage1-002.dgn  
 DATE: 3/10/2022



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
IL 59 - STAGE 1**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	567
CONTRACT NO. 62H15				
FAY 515, FAP 338 ILLINOIS FED. AID PROJECT				


D:\62H15-shi-esc-il-59-rampd-stage1-002.dgn  
50103  
2012/11/30



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: thomas\_group\subarea\esc\p\62h15-shi-esc-il-59-rampd-stage1-003.dgn  
 MODEL: Default  
 FILE: thomas\_group\subarea\esc\p\62h15-shi-esc-il-59-rampd-stage1-003.dgn



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
RAMP C & D - STAGE 1**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------


F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	568
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

D:\62H15-shi-esc-il-59-rampd-stage1-003.dgn  
50103  
2012/11/30



**EROSION CONTROL LEGEND**

- |  |   |  |  |
|--|---|--|--|
|  | WORK ZONE AREA  |  | PERIMETER EROSION BARRIER                |
|  | TEMPORARY PAVEMENT  |  | TEMPORARY FENCE                          |
|  | STABILIZED CONSTRUCTION ENTRANCE                              |  | WASHOUT BASIN                            |
|  | TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2              |  | INLET AND PIPE PROTECTION                |
|  | TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET |  | INLET FILTER                             |
|  | ITEM PLACED IN PREVIOUS STAGE                                 |  | TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT |



MODEL: Default  
 FILE NAME: p:\ubenech-pw\benfry.com\benfry.com\benfry.com\11\Documents\11\0205\10740\_00\Eng\_Docs\_Phase 2\FESC [Thomas]\D162H15-shi-ESC-il-59-RampD-stage1-004.dgn  
 D:\162H15-shi-ESC-il-59-RampD-stage1-004.dgn  
 50103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000 ' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
RAMP C & D - STAGE 1**

SCALE: 1"=50'


SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	569
CONTRACT NO. 62H15				
FAI 55, FAP 338		ILLINOIS FED. AID PROJECT		



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE NAME: p:\subarea\esc-ramp\by-comb\esc-ramp-01\Documents\10700510740\_001\Eng\_Docs\_Phase\_1\FESC\_T\Thomas\10700510740\_001\FESC-Ramp-C-stage1-001.dgn  
 D:\62H15-shi-FSC-Ramp-C-stage1-001.dgn  
 50103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -













**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**




**EROSION AND SEDIMENT CONTROL  
RAMP C & D - STAGE 1**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	570
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

### EROSION CONTROL LEGEND

- |   |   |   |  |
|---|---|---|--|
|  | WORK ZONE AREA  |  | PERIMETER EROSION BARRIER                |
|  | TEMPORARY PAVEMENT  |  | TEMPORARY FENCE                          |
|  | STABILIZED CONSTRUCTION ENTRANCE                              |  | WASHOUT BASIN                            |
|  | TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2              |  | INLET AND PIPE PROTECTION                |
|  | TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET |  | INLET FILTER                             |
|  | ITEM PLACED IN PREVIOUS STAGE                                 |  | TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT |



MODEL: Default  
 FILE: h:\mfg\p\subarea\esc-ramp\esc-ramp-stage1-002.dgn  
 D:\62H15-shi-ESC-RampC-stage1-002.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
DRAWN - JHAITSMA	REVISOR -	
PLOT SCALE = 100,0000' / in.	CHECKED - VMICEK	REVISOR -
PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISOR -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
RAMP C & D - STAGE 1**

SCALE: 1"=50'      SHEET      OF      SHEETS      STA. Sta      TO STA. ToSta


F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	571
CONTRACT NO. 62H15				
FAI 55, FAP 338      ILLINOIS      FED. AID PROJECT				



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE NAME: p:\subareaesc-rampc-stage1\03.dgn  
 PROJECT: I:\Documents\10740\_001\Eng\_Docs\_Phase 1\FESC (Thomas)\162H15-shi-FSC-RampC-stage1-003.dgn



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
RAMP C & D - STAGE 1**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------



F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	572
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

D:\62H15-shi-FSC-RampC-stage1-003.dgn  
50103  
2012/11/30



**NOTE**


PR DRAINAGE STRUCTURES TO BE INSTALLED THAT CANNOT BE BROUGHT TO FINAL GRADE SHALL BE CAPPED WITH A STEEL PLATE UNTIL FINAL ADJUSTMENT CAN BE MADE. THE STEEL PLATE AND FINAL ADJUSTMENT SHALL BE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION, (SPECIAL).



**EROSION CONTROL LEGEND**

- |  |   |  |  |
|--|---|--|--|
|  | WORK ZONE AREA  |  | PERIMETER EROSION BARRIER                |
|  | TEMPORARY PAVEMENT  |  | TEMPORARY FENCE                          |
|  | STABILIZED CONSTRUCTION ENTRANCE                              |  | WASHOUT BASIN                            |
|  | TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2              |  | INLET AND PIPE PROTECTION                |
|  | TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET |  | INLET FILTER                             |
|  | ITEM PLACED IN PREVIOUS STAGE                                 |  | TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT |

**KEY MAP (ESC)**



MODEL: Default  
 FILE: \\na11c:\pub\ubenech-pw\benfry.com\benfry.com\esc\esc-Phase 1\FESC (Thomas)\D162H15-shi-ESC-Seil-stage-1-001.dgn  
 D:\62H15-shi-ESC-Seil-stage1-001.dgn  
 50103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**EROSION AND SEDIMENT CONTROL  
SEIL RD - STAGE 1**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	573
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

**NOTE**


PR DRAINAGE STRUCTURES TO BE INSTALLED THAT CANNOT BE BROUGHT TO FINAL GRADE SHALL BE CAPPED WITH A STEEL PLATE UNTIL FINAL ADJUSTMENT CAN BE MADE. THE STEEL PLATE AND FINAL ADJUSTMENT SHALL BE INCLUDED IN THE COST OF TRAFFIC CONTROL AND PROTECTION, (SPECIAL).



**EROSION CONTROL LEGEND**

- |   |  |
|---|--|
| WORK ZONE AREA  | PERIMETER EROSION BARRIER                |
| TEMPORARY PAVEMENT  | TEMPORARY FENCE                          |
| STABILIZED CONSTRUCTION ENTRANCE                              | WASHOUT BASIN                            |
| TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2              | INLET AND PIPE PROTECTION                |
| TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET | INLET FILTER                             |
| ITEM PLACED IN PREVIOUS STAGE                                 | TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT |

**KEY MAP (ESC)**



MODEL: Default  
 FILE: \\nautilus.pw.usbnet\pwr\com\benetech\pwr\01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC (Thomas)\D162H15-shi-ESC-Seil-stage-1-002.dgn  
 D:\62H15-shi-ESC-Seil-stage1-002.dgn  
 50103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
SEIL RD - STAGE 1**

SCALE: 1"=50'

SHEET OF SHEETS STA. Sta TO STA. ToSta


F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	574
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: h:\m\esc\_p\sub\esc-pw\benf\p\com\benf\esc-pw\01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC-[Thomas]\D162H15-shi-ESC-Seil-stage-1-003.dgn  
 D:\62H15-shi-ESC-Seil-stage1-003.dgn  
 50103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -













**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**




**EROSION AND SEDIMENT CONTROL  
WEST FRONTAGE ROAD - STAGE 1**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	575
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

**EROSION CONTROL LEGEND**

-  WORK ZONE AREA
-  TEMPORARY PAVEMENT
-  STABILIZED CONSTRUCTION ENTRANCE
-  TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
-  TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
-  ITEM PLACED IN PREVIOUS STAGE
-  PERIMETER EROSION BARRIER
-  TEMPORARY FENCE
-  WASHOUT BASIN
-  INLET AND PIPE PROTECTION
-  INLET FILTER
-  TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\nautilus.pw.usbornech.com\bernsch\pww\1\Documents\1\07005\10740\_001\Eng\_Docs\_Phase\_1\FESC-[Thomas]D162H15-shi-FSC-RockRun-stage1-000.dgn  
 D:\62H15-shi-FSC-RockRun-stage1-000.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


<b>EROSION AND SEDIMENT CONTROL</b>	
<b>ROCK RUN CROSSINGS DRIVE - STAGE 1</b>	
SCALE: 1"=50'	SHEET OF SHEETS
STA. Sta	TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	576
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\nautilus.psu.edu\share\pwr\benfry.com\benfry.com\esc\esc\Phase 1\FESC (Thomas)\D162H15-shi-ESC-RockRun-stage1-001.dgn  
 D:\62H15-shi-ESC-RockRun-stage1-001.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


<b>EROSION AND SEDIMENT CONTROL ROCK RUN CROSSINGS DRIVE - STAGE 1</b>	
SCALE: 1"=50'	SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	577
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: h:\mfg\p\subarea\esc\p\stage1\Documents\1107005\10740\_001\Eng\_Docs\_Phase\_1\ESC (Thomas)\D162H15-shi-ESC-RockRun-stage1-002.dgn  
 D:\62H15-shi-ESC-RockRun-stage1-002.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000 ' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


EROSION AND SEDIMENT CONTROL	
ROCK RUN CROSSINGS DRIVE - STAGE 1	
SCALE: 1"=50'	SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	578
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\nautilus.pw.us:home\erch-pw\ben\erch-pw\01\Documents\107005\107040\_001\Eng\_Docs\_Phase\_1\FESC (Thomas)\D162H15-shi-FSC-RockRun-stage1-003.dgn  
 D:\62H15-shi-FSC-RockRun-stage1-003.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
ROCK RUN CROSSINGS DRIVE - STAGE 1**

SCALE: 1"=50'  
SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	579
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				




- TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET PLACED IN PREVIOUS STAGE, TYP
- TEMPORARY DITCH CHECK, TYP
- TEMPORARY PAVEMENT PLACED IN PREVIOUS STAGE, TYP
- INLET FILTER PLACED IN PREVIOUS STAGE, TYP
- INLET AND PIPE PROTECTION, TYP

**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: \\nautilus.psu.edu\share\proj\ben\ben\com\ben\esc\p\01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC (Thomas)\D162H15-shi-ESC-55-stage1A-003.dgn  
 D:\162H15-shi-ESC-55-stage1A-003.dgn  
 50103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1A**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	580
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				






**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: \\nautilus.psu\ubereach-pw\ben\by.com\ben\esc-mp\01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC-[Thomas]\D162H15-shi-ESC-55-stage1A-004.dgn



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1A**

SCALE: 1"=50' SHEET OF SHEETS STA. Sta TO STA. ToSta


F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	581
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

D:\62H15-shi-ESC-55-stage1A-004.dgn  
50103  
2012/11/30



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: h:\m\esc\p\subareaesc\p\62h15\esc\esc-55-stage1A-005.dgn  
 MODEL: Default  
 FILE: h:\m\esc\p\subareaesc\p\62h15\esc\esc-55-stage1A-005.dgn



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1A**

SCALE: 1"=50' SHEET OF SHEETS STA. Sta TO STA. ToSta


F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	582
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

D:\62H15-shi-ESC-55-stage1A-005.dgn  
50 103  
2012/11/30



**EROSION CONTROL LEGEND**

- |  |   |  |  |
|--|---|--|--|
|  | WORK ZONE AREA  |  | PERIMETER EROSION BARRIER                |
|  | TEMPORARY PAVEMENT  |  | TEMPORARY FENCE                          |
|  | STABILIZED CONSTRUCTION ENTRANCE                              |  | WASHOUT BASIN                            |
|  | TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2              |  | INLET AND PIPE PROTECTION                |
|  | TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET |  | INLET FILTER                             |
|  | ITEM PLACED IN PREVIOUS STAGE                                 |  | TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT |



MODEL: Default  
 FILE: h:\m\esc\_p\subareaesc-pw-01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC\_T\Thomas\1062H15-shi-ESC-55-stage1A-006.dgn  
 MODEL: Default  
 FILE: h:\m\esc\_p\subareaesc-pw-01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC\_T\Thomas\1062H15-shi-ESC-55-stage1A-006.dgn



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1A**

SCALE: 1"=50'    SHEET    OF    SHEETS    STA. Sta    TO STA. ToSta

F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	583
CONTRACT NO. 62H15				
FAI 55, FAP 338    ILLINOIS    FED. AID PROJECT				


D:\62H15-shi-ESC-55-stage1A-006.dgn  
50103  
2012/11/30



INLET FILTER PLACED IN PREVIOUS STAGE, TYP

**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\na11c:\pub\uberech-pw\benfry.com\benfry.com\benfry.com\01\Documents\107005\107040\_001\Eng\_Docs\_Phase 1\FESC (Thomas)\D162H15-shi-ESC-55-stage1A-007.dgn



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1A**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------


F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	584
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

D:\62H15-shi-ESC-55-stage1A-007.dgn  
50103  
2012/11/30



**EROSION CONTROL LEGEND**

- WORK ZONE AREA
- TEMPORARY PAVEMENT
- STABILIZED CONSTRUCTION ENTRANCE
- TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
- TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
- ITEM PLACED IN PREVIOUS STAGE
- PERIMETER EROSION BARRIER
- TEMPORARY FENCE
- WASHOUT BASIN
- INLET AND PIPE PROTECTION
- INLET FILTER
- TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\na11c:\pub\subarea\esc\paw\ben\by.com\benesc\paw\01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC (Thomas)\D162H15-shi-ESC-55-stage1A-008.dgn



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1A**

SCALE: 1"=50' SHEET OF SHEETS STA. Sta TO STA. ToSta


F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	585
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

D:\62H15-shi-ESC-55-stage1A-008.dgn  
50103  
2012/11/30



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\na11c:\pub\ubenech\pub\benf\by\com\benecsch\pwp\01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC (Thomas)\D162H15-shi-ESC-55-stage1A-009.dgn  
 D:\62H15-shi-ESC-55-stage1A-009.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1A**


SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	586
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\na11c:\pub\ubenech-pw\benfry.com\benfry.com\esc\esc-1\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC-[Thomas]D162H15-shi-ESC-55-stage1A-010.dgn  
 D:\162H15-shi-ESC-55-stage1A-010.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
I-55 - STAGE 1A**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------


F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	587
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

- |   |  |
|---|--|
| WORK ZONE AREA  | PERIMETER EROSION BARRIER                |
| TEMPORARY PAVEMENT  | TEMPORARY FENCE                          |
| STABILIZED CONSTRUCTION ENTRANCE                              | WASHOUT BASIN                            |
| TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2              | INLET AND PIPE PROTECTION                |
| TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET | INLET FILTER                             |
| ITEM PLACED IN PREVIOUS STAGE                                 | TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT |

**KEY MAP (ESC)**



MODEL: Default  
 FILE: A:\MISC\pub\subareaesc\pwr\01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC (Thomas)\62H15-shi-ESC-il-59-RampD-stage1A-001.dgn  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
IL 59 - STAGE 1A**

SCALE: 1"=50'    SHEET    OF    SHEETS    STA. Sta    TO STA. ToSta


F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	588
CONTRACT NO. 62H15				
FAI 55, FAP 338    ILLINOIS    FED. AID PROJECT				





**EROSION CONTROL LEGEND**

- WORK ZONE AREA
- TEMPORARY PAVEMENT
- STABILIZED CONSTRUCTION ENTRANCE
- TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
- TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
- ITEM PLACED IN PREVIOUS STAGE
- PERIMETER EROSION BARRIER
- TEMPORARY FENCE
- WASHOUT BASIN
- INLET AND PIPE PROTECTION
- INLET FILTER
- TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: h:\a\esc\p\subareaesc\p\p\01\Documents\107005\107040\_00\Eng\_Docs\_Phase\_1\FESC (Thomas)\162H15-shi-ESC-IL59-RampD-stage1A-002.dgn  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
IL 59 - STAGE 1A**


SCALE: 1"=50' SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	589
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

- |  |   |  |  |
|--|---|--|--|
|  | WORK ZONE AREA  |  | PERIMETER EROSION BARRIER                |
|  | TEMPORARY PAVEMENT  |  | TEMPORARY FENCE                          |
|  | STABILIZED CONSTRUCTION ENTRANCE                              |  | WASHOUT BASIN                            |
|  | TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2              |  | INLET AND PIPE PROTECTION                |
|  | TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET |  | INLET FILTER                             |
|  | ITEM PLACED IN PREVIOUS STAGE                                 |  | TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT |



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
DRAWN - JHAITSMA	REVISOR -	
PLOT SCALE = 100,0000' / in.	CHECKED - VMICEK	REVISOR -
PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISOR -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**



**EROSION AND SEDIMENT CONTROL  
RAMP C & D - STAGE 1A**

SCALE: 1"=50' SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	590
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				


MODEL: Default  
 FILE: M:\MISC\p\subareaesc-ramp\by.com\benefit\com\benefit\p\01\Documents\107005\107040\_000\Eng\_Docs\_Phase\_B\ESC-[Thomas]D162H15-shi-ESC-IL59-RampD-stage1A-003.dgn

D:\62H15-shi-ESC-IL59-RampD-stage1A-003.dgn  
50103  
2012/11/30



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: 62H15-shi-ESC-il59-RampD-stage1A-004.dgn  
 PROJECT: 62H15-shi-ESC-il59-RampD-stage1A-004.dgn  
 USER: vinceM  
 DATE: 3/10/2022





USER NAME = vinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
RAMP C & D - STAGE 1A**


SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	591
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: h:\a\m\p\sub\ereach-pw\ben\p\com\ben\esc-mp\01\Documents\10700510740\_001\Eng\_Docx\_Phase\_1\FESC-[Thomas]D162H15-shi-FSC-Ramp-C-stage1A-001.dgn  
 D:\62H15-shi-FSC-Ramp-C-stage1A-001.dgn  
 50103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -













**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**




**EROSION AND SEDIMENT CONTROL  
RAMP C & D - STAGE 1A**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	592
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

### EROSION CONTROL LEGEND

-  WORK ZONE AREA
-  TEMPORARY PAVEMENT
-  STABILIZED CONSTRUCTION ENTRANCE
-  TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
-  TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
-  ITEM PLACED IN PREVIOUS STAGE
-  PERIMETER EROSION BARRIER
-  TEMPORARY FENCE
-  WASHOUT BASIN
-  INLET AND PIPE PROTECTION
-  INLET FILTER
-  TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: h:\mfg\p\subarea\esc-ramp\stage1a-002.dgn  
 PROJECT: 2018-075-R  
 USER: vinceM  
 DATE: 3/10/2022  
 TIME: 11:30



USER NAME = vinceM	DESIGNED - JCROSS	REVISED -
DRAWN - JHAITSMA	REVISED -	
PLOT SCALE = 100,0000' / in.	CHECKED - VMICEK	REVISED -
PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
RAMP C & D - STAGE 1A**

SCALE: 1"=50'      SHEET      OF      SHEETS      STA. Sta      TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	593
CONTRACT NO. 62H15				
FAI 55, FAP 338      ILLINOIS      FED. AID PROJECT				


D:\62H15-shi-ESC-RampC-stage1A-002.dgn  
50103  
2012/11/30



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: h:\mfg\p\subareaesc-rampc-stage1a-003.dgn  
 D:\62H15-shi-ESC-RampC-stage1A-003.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
RAMP C & D - STAGE 1A**


SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	594
CONTRACT NO. 62H15				
F. 51, FAP 338	ILLINOIS	FED. AID PROJECT		



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\na11c:\pub\ubereach-pw\benfry.com\benfry.com\benfry.com\01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC-[Thomas]\D162H15-shi-ESC-Seil-stage1A-001.dgn  
 D:\62H15-shi-ESC-Seil-stage1A-001.dgn  
 50 103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
SEIL RD - STAGE 1A**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------


F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	595
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				



**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: thomas\_group\subcontract\paw\_bentley.com\benesch-paw\01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC (Thomas)\D162H15-shi-ESC-Seil-stage1A-002.dgn  
 D:\62H15-shi-ESC-Seil-stage1A-002.dgn  
 50 103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -



**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
SEIL RD - STAGE 1A**

SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	596
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				






**EROSION CONTROL LEGEND**

	WORK ZONE AREA		PERIMETER EROSION BARRIER
	TEMPORARY PAVEMENT		TEMPORARY FENCE
	STABILIZED CONSTRUCTION ENTRANCE		WASHOUT BASIN
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2		INLET AND PIPE PROTECTION
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET		INLET FILTER
	ITEM PLACED IN PREVIOUS STAGE		TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT

**KEY MAP (ESC)**



MODEL: Default  
 FILE: thomas\_e\_group\subarea\esc\p\62115-shi-esc-seil-stage1a-003.dgn  
 MODEL: Default  
 FILE: thomas\_e\_group\subarea\esc\p\62115-shi-esc-seil-stage1a-003.dgn  
 MODEL: Default  
 FILE: thomas\_e\_group\subarea\esc\p\62115-shi-esc-seil-stage1a-003.dgn



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**













**EROSION AND SEDIMENT CONTROL  
WEST FRONTAGE ROAD - STAGE 1A**




SCALE: 1"=50'	SHEET	OF	SHEETS	STA. Sta	TO STA. ToSta
---------------	-------	----	--------	----------	---------------

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	597
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				

D:\62115-shi-esc-seil-stage1a-003.dgn  
50103  
2012/11/30

**EROSION CONTROL LEGEND**

-  WORK ZONE AREA
-  TEMPORARY PAVEMENT
-  STABILIZED CONSTRUCTION ENTRANCE
-  TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
-  TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
-  ITEM PLACED IN PREVIOUS STAGE
-  PERIMETER EROSION BARRIER
-  TEMPORARY FENCE
-  WASHOUT BASIN
-  INLET AND PIPE PROTECTION
-  INLET FILTER
-  TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: h:\mfg\p\subarea\esc\p\w\01\Documents\11\0205\10740\_001\Eng\_Docs\_Phase\_1\FESC\_T\Thomas\1162H15-shi-ESC-RockRun-stage1A-000.dgn  
 D:\162H15-shi-ESC-RockRun-stage1A-000.dgn  
 50103  
 2012/11/30





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
DRAWN - JHAITSMA	REVISOR -	
PLOT SCALE = 100,0000' / in.	CHECKED - VMICEK	REVISED -
PLOT DATE = 3/10/2022	DATE - 03/16/2022	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>EROSION AND SEDIMENT CONTROL ROCK RUN CROSSINGS DRIVE - STAGE 1A</b>			
SCALE: 1"=50'	SHEET	OF SHEETS	STA. Sta TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	598
CONTRACT NO. 62H15				
F. FAI 55, FAP 338	ILLINOIS	FED. AID PROJECT		



EROSION CONTROL LEGEND	
	WORK ZONE AREA
	TEMPORARY PAVEMENT
	STABILIZED CONSTRUCTION ENTRANCE
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
	ITEM PLACED IN PREVIOUS STAGE
	PERIMETER EROSION BARRIER
	TEMPORARY FENCE
	WASHOUT BASIN
	INLET AND PIPE PROTECTION
	INLET FILTER
	TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\nautilus.pw.usbnet\pwr\com\benesch\pwr\01\Documents\107005\10740\_00\Eng\_Docs\_Phase\_1\FESC-[Thomas]\D162H15-shi-FSC-RockRun-stage1A-001.dgn





USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**EROSION AND SEDIMENT CONTROL  
ROCK RUN CROSSINGS DRIVE - STAGE 1A**

SCALE: 1"=50'      SHEET      OF      SHEETS      STA. Sta      TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	599
CONTRACT NO. 62H15				
FAI 55, FAP 338      ILLINOIS      FED. AID PROJECT				



EROSION CONTROL LEGEND	
	WORK ZONE AREA
	TEMPORARY PAVEMENT
	STABILIZED CONSTRUCTION ENTRANCE
	TEMP EROSION CONTROL SEEDING AND MULCH, METHOD 2
	TEMP EROSION CONTROL SEEDING AND TEMP EROSION CONTROL BLANKET
	ITEM PLACED IN PREVIOUS STAGE
	PERIMETER EROSION BARRIER
	TEMPORARY FENCE
	WASHOUT BASIN
	INLET AND PIPE PROTECTION
	INLET FILTER
	TEMPORARY DITCH CHECK MINIMUM 12" HEIGHT



MODEL: Default  
 FILE: \\nautilus.pw.us\share\pwr\ben\pwr\com\ben\esc\pwr\01\Documents\11\0205\10740\_00\Eng\_Docs\_Phase\_1\FESC-[Thomas]\D162H15-shi-ESC-RockRun-stage1A-002.dgn  
 D:\62H15-shi-ESC-RockRun-stage1A-002.dgn  
 50103  
 2012/11/30



USER NAME = VinceM	DESIGNED - JCROSS	REVISED -
PLOT SCALE = 100,0000' / in.	DRAWN - JHAITSMA	REVISED -
PLOT DATE = 3/10/2022	CHECKED - VMICEK	REVISED -
	DATE - 03/16/2022	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>EROSION AND SEDIMENT CONTROL ROCK RUN CROSSINGS DRIVE - STAGE 1A</b>	
SCALE: 1"=50'	SHEET OF SHEETS STA. Sta TO STA. ToSta

F.A./P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2018-075-R	WILL	1510	600
CONTRACT NO. 62H15				
FAI 55, FAP 338 ILLINOIS FED. AID PROJECT				