

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	100% STATE
				BRIDGE 0014 RURAL	BRIDGE 0014 URBAN
58700300	CONCRETE SEALER	SQ FT	317228	194250	122978
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.33	0.67
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.95	0.05
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1

GENERAL NOTES

THE CONTRACTOR AND THE ENGINEER SHALL BE AWARE THAT NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE TOPOGRAPHY SHOWN IN THE PLANS WAS CREATED USING MICROFILM AND FIELD MEASUREMENTS. BOTH SHALL BE ASSUMED TO BE APPROXIMATE. THE CONTRACTOR SHALL VERIFY DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

NO OVERNIGHT CLOSURES WILL BE PERMITTED.

EXISTING PAVEMENT MARKING SHALL BE TEMPORARILY COVERED PRIOR TO APPLICATION OF THE DECK SURFACE TREATMENT, TO PREVENT THE MATERIAL FROM BEING APPLIED TO THE MARKINGS. THE TEMPORARY COVERING SHALL BE REMOVED AFTER APPLICATION OF THE DECK SURFACE TREATMENT AND PRIOR TO OPENING TO TRAFFIC. COST IS INCLUDED WITH THE DECK SURFACE TREATMENT SPECIFIED, INCLUDING RAISED REFLECTIVE PAVEMENT MARKERS AND REFLECTORS.

ALL TURF AREAS DISTURBED BY THE CONTRACTOR SHALL BE SEEDED WITH THE APPROPRIATE EROSION CONTROL AS DIRECTED BY THE ENGINEER AT THE EXPENSE OF THE CONTRACTOR.

COMMITMENTS

NONE

HIGHWAY STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 701201-04 LANE CLOSURE, 2L, 2W, DAY ONLY FOR SPEEDS >= 45 MPH
- 701421-04 LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS >= 45 MPH TO 55 MPH
- 701601-07 URBAN LANE CLOSURE NONTRAVERSABLE MEDIAN MULTILANE, 1W OR 2W WITH
- 701701-08 URBAN LANE CLOSURE, MULTILANE INTERSECTION
- 701901-01 TRAFFIC CONTROL DEVICES

\* VARIOUS ROUTES

FILE NAME =	USER NAME = muehlfeidec	DESIGNED - ACM	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES; HIGHWAY STANDARDS GENERAL NOTES; COMMITMENTS</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\muehlfeidec\d0288263\876749-shit-500-GN.dgn	DRAWN - ACM	REVISED -									
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -									
PLOT DATE = 3/8/2012	DATE -	REVISED -									
						SCALE: NONE	SHEET 1 OF 1 SHEETS	STA.	TO STA.		
						ILLINOIS FED. AID PROJECT					