

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE							HIGHWAY LIGHTING	NOISE WALL
				ROADWAY	BRIDGE	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL		
				0004 URBAN	0008 016-1705	0040 016-1720	0040 016-Z024	0040 016-1722	0040 016-1723	0040 016-1809		
44001980	CONCRETE BARRIER REMOVAL	FOOT	8421	8421								
44004250	PAVED SHOULDER REMOVAL	SO YD	5075	5075								
44200612	CLASS A PATCHES, TYPE III, 13 INCH	SQ YD	542	542								
44200614	CLASS A PATCHES, TYPE IV, 13 INCH	SO YD	660	660								
44201377	CLASS C PATCHES, TYPE II, 12 INCH	SO YD	515	515								
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	714	714								
442D1B21	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	605	605								
44213000	PATCHING REINFORCEMENT	SO YD	702	702								
44213200	SAW CUTS	FOOT	812	812								
44213204	TIE BARS 3/4"	EACH	172	172								
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SO YD	1400	1400								
48300510	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/2"	SO YD	1615	1615								
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1							
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1							
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1								
50102400	CONCRETE REMOVAL	CU YD	54		53	1						

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

A Rev. 6-2-14

FILE PATH: C:\Users\alibadeh\Documents\Projects\1315\Final Sheets\442D1B21\442D1B21-500.dgn



DIGW2B-442-500.dgn
 USER NAME: alibadeh
 PLOT SCALE: 2,000' / 1" / 1" / 1"
 PLOT DATE: 4/28/2014

DESIGNED - NSA
 DRAWN - NSA
 CHECKED - AFC
 DATE - 04/28/14

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 4 OF 24 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	147	8
CONTRACT NO. 60W28			ILLINOIS FED. AID PROJECT	