

90% FED,
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	LIRBAN TOTAL QUANTITY	CONSTRUCTION CODE							HIGHWAY LIGHTING	NOISE WALL
				ROADWAY	BRIDGE	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL		
				0004	0008	0040	0040	0040	0040	0040		
				016-1705	016-1720	016-2024	016-1722	016-1723	016-1809	0021	0040	
				URBAN						URBAN	NONE	
55101400	STORM SEWER REMOVAL 30"	FOOT	272		272							
56103900	DUCTILE IRON WATER MAIN, MECHANICAL JOINT 8"	FOOT	11		11							
56104200	DUCTILE IRON WATER MAIN, MECHANICAL JOINT 16"	FOOT	223		223							
56105000	WATER VALVES 8"	EACH	1		1							
56105310	WATER MAIN CONTROL VALVE-16 INCH	EACH	2		2							
56400600	FIRE HYDRANTS	EACH	1		1							
58700300	CONCRETE SEALER	SO FT	30,816		30,394				6422			
59000200	EPOXY CRACK INJECTION	FOOT	92				92					
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	73						73			
60107700	PIPE UNDERDRAINS 6"	FOOT	626		626							
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	90		90							
60200105	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	4		4							
60200205	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	13		13							
60200805	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 8 GRATE	EACH	9		9							

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

Rev. 6-2-14

Rev.

FILE PATH = C:\Users\alvarez\OneDrive\Documents\Projects\60W28-11-500.dgn



0160W28-11-500.dgn
 USER NAME = alvarez
 PLOT SCALE = 2.0000 / 1"
 PLOT DATE = 4/28/2014

DESIGNED - NSA
 DRAWN - NSA
 CHECKED - AFC
 DATE - 04/28/14

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 8 OF 24 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	12
CONTRACT NO. 60W28			ILLINOIS FED. AID PROJECT	