

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE																
				ROADWAY	BRIDGE	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	HIGHWAY LIGHTING	NOISE WALL								
				0004	0008	0040	0040	0040	0040	0040	0021	0040								
				016-1720	016-2024	016-1722	016-1723	016-1809	URBAN	NONE										
A 60600605	CONCRETE CURB, TYPE B	FOOT	7	7																
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 24	FOOT	118	118																
A 60602900	CONCRETE GUTTER, TYPE B	FOOT	179	179																
A 60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	8186	8186																
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	50	50																
63200310	GUARDRAIL REMOVAL	FOOT	51	51																
63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	3660	3660																
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	45	45																
63700805	CONCRETE BARRIER TRANSITION	FOOT	271	271																
63700900	CONCRETE BARRIER BASE	FOOT	4207	4207																
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	2367	2367																
64300240	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2	2																
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2																
66400305	CHAIN LINK FENCE, 6'	FOOT	520	520																
66402900	CHAIN LINK GATES, 6' X 6' SINGLE	EACH	1	1																
66407600	CHAIN LINK GATES, 6' X 12' DOUBLE	EACH	3	3																

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

A Rev. 6-2-14

FILE PATH: C:\Users\alicedahm\Documents\Projects\60602900\Sheets\60602900-ht-500.dgn



D:\60602900-ht-500.dgn
 USER NAME = alicedahm
 PLOT SCALE = 2,000' / 1" IN.
 PLOT DATE = 4/28/2014

DESIGNED - NSA
 DRAWN - NSA
 CHECKED - AFC
 DATE - 04/28/14

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 10 OF 24 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	14
CONTRACT NO. 60W28			ILLINOIS FED. AID PROJECT	