

90% FED.
10% STATE

CONSTRUCTION CODE

A

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE							HIGHWAY LIGHTING	NOISE WALL
				ROADWAY	BRIDGE	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL		
				0004	0008	0040	0040	0040	0040	0040		
				URBAN	016-1705	016-1720	016-Z024	016-1722	016-1723	016-1809	0021	0040
											URBAN	NONE
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	736								736	
* 81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	1020								1020	
* 81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	20								20	
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	10,644								10644	
* 81300320	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE 8" X 8" X 6" EACH	EACH	4								4	
* 81300410	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 10" X 8" X 4"	EACH	4								4	
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	1								1	
* 81300830	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 18" X 8"	EACH	1								1	
* 81300910	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 20" X 20" X 6"	EACH	6								6	
* 81301500	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 28" X 12" X 6"	EACH	15								15	
* 81400100	HANDHOLE	EACH	6								6	
* 81400200	HEAVY-DUTY HANDHOLE	EACH	6								6	
* 81603050	UNIT DUCT, 600V, 3-1C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	265								265	
* 81603070	UNIT DUCT, 600V, 2-1C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	550								550	
* 81603081	UNIT DUCT, 600V, 3-1C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	1890								1890	

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

A Rev. 6-2-14

FILE PATH: C:\Users\volizadahn\OneDrive\Prints\Final Sheets\016028-hy-500.dgn



016028-hy-500.dgn	DESIGNED - NSA	REVISED -
USER NAME - alizadahn	DRAWN - NSA	REVISED -
PLOT SCALE - 2.0000 / 1 in.	CHECKED - AFC	REVISED -
PLOT DATE - 4/28/2014	DATE - 04/28/14	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 14 OF 24 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	18
CONTRACT NO. 60W28			ILLINOIS FED. AID PROJECT	