

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE							HIGHWAY LIGHTING	NOISE WALL
				ROADWAY	BRIDGE	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL		
				0004	0008	0040	0040	0040	0040	0040		
				016-1705	016-1720	016-2024	016-1722	016-1723	016-1809	0021	0040	
				URBAN						URBAN	NONE	
*X5537700	STORM SEWERS TO BE CLEANED 10"	FOOT	107	107								
*X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	213	213								
*X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	74	74								
*X5538100	STORM SEWERS TO BE CLEANED 21"	FOOT	192	192								
*X5538200	STORM SEWERS TO BE CLEANED 24"	FOOT	436	436								
**A X5538400	STORM SEWERS TO BE CLEANED, 30"	FOOT	31	31								
X5610712	WATER MAIN REMOVAL, 12"	FOOT	52	52								
X5610716	WATER MAIN REMOVAL, 16"	FOOT	199	199								
A X6020270	MANHOLES TYPE B, 4'-DIA., TYPE I FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	1	1								
X6022505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE I FRAME, OPEN LID (CITY OF CHICAGO)	EACH	3	3								
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1								
A X6061305	CONCRETE MEDIAN SURFACE, SPECIAL	SQ FT	8081	8081								
X6370050	CONCRETE BARRIER WALL (SPECIAL)	FOOT	166	166								
A X6370159	CONCRETE BARRIER, SINGLE FACE, 32 INCH HEIGHT (SPECIAL)	FOOT	15	15								
X6430120	REMOVE IMPACT ATTENUATORS, NO SALVAGE	EACH	1	1								
X6640050	CHAIN LINK FENCE, 42" ATTACHED TO STRUCTURE (SPECIAL)	FOOT	1601	1601								
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	22	22								
A X6370015	CONCRETE BARRIER, SPECIAL, 32" HEIGHT	FOOT	50	50								
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1								

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM (100% STATE)

A Rev. 6-2-13

Rev.

FILE PATH: C:\Users\j11111111\Desktop\Projects\60W28\Sheet101628-INT-500.dgn



DESIGNED - NSA	REVISED -
DRAWN - NSA	REVISED -
CHECKED - AFC	REVISED -
DATE - 04/28/14	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 21 OF 24 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	210
CONTRACT NO. 60W28			ILLINOIS FED. AID PROJECT	