

EARTHWORK SCHEDULE

| FROM STATION | TO STATION | EARTH EXCAVATION (20200100) | | | | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS (20201200) | | | | EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (EARTH EXCAVATION * 0.85) | | | | EMBANKMENT | | | | EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) | | | | FURNISHED EXCAVATION (20400800) | | | |
|--|------------|--------------------------------|-------|-------|-------|---|-------|-------|-------|--|-------|-------|-------|------------|-------|-------|-------|--|-------|-------|-------|---------------------------------------|-------|-------|-------|
| | | CU YD | | | | CU YD | | | | CU YD | | | | CU YD | | | | CU YD | | | | CU YD | | | |
| | | STG 1 | STG 2 | STG 3 | STG 4 | STG 1 | STG 2 | STG 3 | STG 4 | STG 1 | STG 2 | STG 3 | STG 4 | STG 1 | STG 2 | STG 3 | STG 4 | STG 1 | STG 2 | STG 3 | STG 4 | STG 1 | STG 2 | STG 3 | STG 4 |
| RAMP NW (INCLUDING PR. RETAINING WALLS 016-1720, 016-1722, & 016-1723) | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1802+50.00 | 1802+75.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 1802+75.00 | 1803+00.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 1803+00.00 | 1803+50.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 1803+50.00 | 1804+00.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 1804+00.00 | 1804+50.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 1804+50.00 | 1805+00.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 1805+00.00 | 1805+50.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 1805+50.00 | 1806+00.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| 1806+00.00 | 1806+50.00 | 0 | 13 | 39 | 0 | 0 | 2 | 5 | 0 | 0 | 11 | 33 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 11 | 33 | 0 | | |
| 1806+50.00 | 1806+91.96 | 0 | 24 | 71 | 0 | 0 | 3 | 8 | 0 | 0 | 20 | 61 | 0 | 0 | 2 | 6 | 0 | 0 | 0 | 0 | 18 | 55 | 0 | | |
| 1806+91.96 | 1807+00.00 | 0 | 5 | 15 | 0 | 0 | 1 | 2 | 0 | 0 | 4 | 13 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 0 | 4 | 11 | 0 | | |
| 1807+00.00 | 1807+50.00 | 0 | 31 | 92 | 0 | 0 | 4 | 11 | 0 | 0 | 26 | 78 | 0 | 0 | 5 | 15 | 0 | 0 | 0 | 0 | 21 | 63 | 0 | | |
| 1807+50.00 | 1808+00.00 | 0 | 30 | 91 | 0 | 0 | 4 | 11 | 0 | 0 | 26 | 77 | 0 | 0 | 7 | 20 | 0 | 0 | 0 | 0 | 19 | 58 | 0 | | |
| 1808+00.00 | 1808+50.00 | 0 | 31 | 92 | 0 | 0 | 4 | 11 | 0 | 0 | 26 | 78 | 0 | 0 | 8 | 23 | 0 | 0 | 0 | 0 | 19 | 56 | 0 | | |
| 1808+50.00 | 1809+00.00 | 0 | 32 | 96 | 0 | 0 | 4 | 11 | 0 | 0 | 27 | 82 | 0 | 0 | 8 | 23 | 0 | 0 | 0 | 0 | 20 | 59 | 0 | | |
| 1809+00.00 | 1809+50.00 | 0 | 36 | 107 | 0 | 0 | 4 | 12 | 0 | 0 | 30 | 91 | 0 | 0 | 8 | 23 | 0 | 0 | 0 | 0 | 23 | 68 | 0 | | |
| 1809+50.00 | 1810+00.00 | 0 | 38 | 115 | 0 | 0 | 4 | 13 | 0 | 0 | 33 | 98 | 0 | 0 | 7 | 20 | 0 | 0 | 0 | 0 | 26 | 77 | 0 | | |
| 1810+00.00 | 1810+50.00 | 0 | 35 | 105 | 0 | 0 | 4 | 12 | 0 | 0 | 30 | 89 | 0 | 0 | 6 | 19 | 0 | 0 | 0 | 0 | 24 | 71 | 0 | | |
| 1810+50.00 | 1811+00.00 | 0 | 26 | 78 | 0 | 0 | 3 | 9 | 0 | 0 | 22 | 66 | 0 | 0 | 7 | 20 | 0 | 0 | 0 | 0 | 15 | 46 | 0 | | |
| 1811+00.00 | 1811+50.00 | 0 | 12 | 36 | 0 | 0 | 2 | 5 | 0 | 0 | 10 | 31 | 0 | 0 | 7 | 20 | 0 | 0 | 0 | 0 | 3 | 10 | 0 | | |
| 1811+50.00 | 1812+00.00 | 0 | 2 | 6 | 0 | 0 | 0 | 1 | 0 | 0 | 2 | 5 | 0 | 0 | 15 | 44 | 0 | 0 | 0 | 0 | -13 | -39 | 0 | | |
| 1812+00.00 | 1812+50.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 39 | 116 | 0 | 0 | 0 | 0 | -39 | -116 | 0 | | |
| 1812+50.00 | 1813+00.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 65 | 195 | 0 | 0 | 0 | 0 | -65 | -195 | 0 | | |
| 1813+00.00 | 1813+50.00 | 0 | 7 | 20 | 0 | 0 | 1 | 2 | 0 | 0 | 6 | 17 | 0 | 0 | 90 | 270 | 0 | 0 | 0 | 0 | -84 | -253 | 0 | | |
| 1813+50.00 | 1813+60.00 | 0 | 3 | 8 | 0 | 0 | 1 | 2 | 0 | 0 | 2 | 6 | 0 | 0 | 11 | 32 | 0 | 0 | 0 | 0 | -8 | -25 | 0 | | |
| 1813+60.00 | 1814+00.00 | 0 | 10 | 29 | 0 | 0 | 3 | 8 | 0 | 0 | 8 | 24 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 24 | 0 | | |
| 1814+00.00 | 1814+50.00 | 0 | 12 | 35 | 0 | 0 | 4 | 11 | 0 | 0 | 10 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 10 | 29 | 0 | | |
| 1814+50.00 | 1815+00.00 | 0 | 8 | 23 | 0 | 0 | 3 | 10 | 0 | 0 | 6 | 19 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 6 | 19 | 0 | | |
| 1815+00.00 | 1815+50.00 | 0 | 4 | 13 | 0 | 0 | 3 | 8 | 0 | 0 | 4 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 11 | 0 | | |
| 1815+50.00 | 1816+00.00 | 0 | 5 | 14 | 0 | 0 | 3 | 9 | 0 | 0 | 4 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 11 | 0 | | |
| 1816+00.00 | 1816+50.00 | 0 | 4 | 13 | 0 | 0 | 4 | 11 | 0 | 0 | 4 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 11 | 0 | | |
| 1816+50.00 | 1817+00.00 | 0 | 4 | 12 | 0 | 0 | 4 | 11 | 0 | 0 | 3 | 10 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 10 | 0 | | |
| 1817+00.00 | 1817+50.00 | 0 | 5 | 14 | 0 | 0 | 4 | 12 | 0 | 0 | 4 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 11 | 0 | | |
| 1817+50.00 | 1818+00.00 | 0 | 6 | 17 | 0 | 0 | 4 | 13 | 0 | 0 | 5 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 15 | 0 | | |
| 1818+00.00 | 1818+19.17 | 0 | 3 | 8 | 0 | 0 | 2 | 6 | 0 | 0 | 2 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 6 | 0 | | |
| 1818+19.17 | 1818+45.67 | 0 | 4 | 11 | 0 | 0 | 4 | 11 | 0 | 0 | 3 | 10 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 10 | 0 | | |
| 1818+45.67 | 1818+50.00 | 0 | 1 | 2 | 0 | 0 | 1 | 3 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 2 | 0 | | |
| 1818+50.00 | 1818+51.17 | 0 | 0 | 1 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | | |
| 1818+51.17 | 1818+53.67 | 0 | 1 | 2 | 0 | 0 | 1 | 2 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | | |
| SUBTOTAL | | 0 | 387 | 1160 | 0 | 0 | 77 | 230 | 0 | 0 | 329 | 986 | 0 | 0 | 282 | 846 | 0 | 0 | 0 | 0 | 47 | 140 | 0 | 1128 | |



• NOT A PAY ITEM.

•• FURNISHED EXCAVATION IS ASSUMED TO EQUAL EMBANKMENT DUE TO THE UNCERTAINTY IN THE PERCENTAGE OF EARTH EXCAVATION THAT IS CLASSIFIED AS SPECIAL, NON-SPECIAL, AND HAZARDOUS WASTE.

NOTE: REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS WAS ESTIMATED BY TOTALING 4" OF EXISTING TOPSOIL REMOVAL, 10% OF EARTH MOVED, AND 10% OF STRUCTURAL EXCAVATION (EARTH MOVED = EARTH EXCAVATION / 0.90)

C:\Users\p10101\OneDrive\Documents\60W28-Addendum\0160W28-Addendum-Schedule-03.dgn



DI60W28-Addendum-Schedule-03.dgn
 USER NAME: p101010
 PLOT SCALE: 1/80,000
 PLOT DATE: 5/26/2014

DESIGNED - KAM
 DRAWN - KAM
 CHECKED - KCF
 DATE - 04/28/14

REVISED - 5/27/2014
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 3 OF 6 SHEETS STA. TO STA.

| | | | | |
|---------------------------|-----------|--------|--------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 90/94/290 | 2013-010R | COOK | 747 | 35 |
| CONTRACT NO. 60W28 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |