PROPOSED PIPE UNDERDRAINS SCHEDULE

PIPE UNDERDRAIN	UPSTREAM			DOWNSTREAM			PIPE UNDERDRAINS 6" FOOT	PIPE UNDERDRAINS 6" (SPECIAL) FOOT
	STRUCTURE	STATION	OFFSET	STRUCTURE	STATION	OFFSET		
PU-04	-	1802+75.00	17.74' RT	S-11A	1806+69.73	14.54' RT	20	10
PU-05	-	1806+91.96	14.00' RT	S-11A	1806+69.73	14.54' RT	13	10
PU-08	-	1806+57.31	30.67' RT	S-13	1806+55.00	31.21' RT	123	10
PU-09	-	1807+96.03	27.30' RT	S-16	1809+60.69	26.75' RT	155	10
PU-10	-	1809+61.00	23.00' RT	S-17	1809+96.60	26.75' RT	26	10
PU-11	-	1811+13.35	11.00' LT	S-18	1810+18.26	13.15' LT	86	10
PU-12	-	1812+76.59	10.00' LT	S-19	1811+18.36	13.00' LT	147	10
PU-13	-	1813+07.00	12.00' LT	S-28	1812+81.60	13.00' LT	16	10
PU-14	-	1813+60.00	12.00' LT	S-28A	1813+10.00	13.00' LT	40	10
ROUNDED TOTAL							626	90

A

PROPOSED DRAINAGE STRUCTURE SCHEDULE (CITY OF CHICAGO)

STRUCTURE	NORTHING	EASTING	(CENTER OF STRUCTURE OR FACE OF CURB)	RIM (ELEV)	N. INVERT (ELEV)	W. INVERT (ELEV)	E. INVERT (ELEV)	S. INVERT (ELEV)	NE. INVERT (ELEV)	NW. INVERT (ELEV)	S. INVERT (ELEV)	NE. INVERT (ELEV)	NW. INVERT (ELEV)	SE. INVERT (ELEV)	SW. INVERT (ELEV)	CATCH BASINS, TYPE 4, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	MANHOLES, TYPE B, 4'-DIA., TYPE 1 FRAME, CLOSED LID (CITY OF CHICAGO)
																EACH	EACH
																X6022505	X6020270
GREEN STREET (SOUTH LIMITS)																	
S-C01	1897799.36	1170793.48	COS	594.05										582.08		1	
S-C01A	1897816.99	1170820.04	COS	594.28							582.15	581.85	581.74				1
GREEN STREET (NORTH LIMITS)																	
S-C03	1898218.03	1170779.08	FOC	592.78			587.36									1	
S-C04	1898215.97	1170817.23	FOC	593.06		587.64										1	
TOTALS																3	1

PROPOSED DRAINAGE PIPE SCHEDULE (CITY OF CHICAGO)

PIPE	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	UPSTREAM INVERT ELEVATION	DOWNSTREAM INVERT ELEVATION	COMBINED SEWER, (WATER MAIN REQUIREMENTS) 8 INCH CDOT FOOT	12 INCH CDOT FOOT	24 INCH CDOT FOOT	TRENCH BACKFILL CU YD
GREEN STREET (SOUTH LIMITS)								
P-C01	S-C01	BLIND CONNECTION	582.08	581.98	27			0.0
P-C01A	S-C01A	1897757.23 (NORTHING) 1170813.84 (EASTING)	582.15	581.85			60	0.0
P-C01B	1897823.70 (NORTHING) 1170798.84 (EASTING)	S-C01A	582.13	581.74		24		0.0
P-C01C	197819.33 (NORTHING) 1170834.60 (EASTING)	S-C01A	582.22	581.85		16		0.0
GREEN STREET (NORTH LIMITS)								
P-C02	1898209.91 (NORTHING) 1170798.87 (EASTING)	1898224.91 (NORTHING) 1170798.38 (EASTING)	582.91	582.83			15	21.8
P-C03	S-C03	BLIND CONNECTION	587.36	582.86	18			15.8
P-C04	S-C04	BLIND CONNECTION	587.64	582.88	17			15.0
ROUNDED TOTAL					62	40	75	52.6

A

AECOM
303 EAST WACKER DRIVE, SUITE 1400
CHICAGO, IL 60601-5276
PHONE: (312) 373-7700 FAX: (312) 373-8800

D60W28-sht-Schedule-Drain-07	DESIGNED - DMS/AFC	REVISED - ⚠ 5/27/2014	
USER NAME = schmanskid	DRAWN - DMS/AFC	REVISED -	
PLOT SCALE = 100.0000 ' / in.	CHECKED - EEY	REVISED -	
PLOT DATE = 5/27/2014	DATE - 4/28/2014	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DRAINAGE AND UTILITY SCHEDULES

SCALE: NTS | SHEET 7 OF 7 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	45
		CONTRACT NO. 60W28		
	ILLINOIS FED. AID PROJECT			

FILE PATH = n:\1288029\project\connective\local\Pw\EDMS\Documents\Alt America\Transportation\4826938_CivilianPhase II\320\CAD\D6_Roadway\Sheets\60W28_Construct\D60W28-sht-Schedule-Drain-07