SIGN DETAIL

1:60



SIGN NUMBER	TC-SGN-16
WIDTH x HGHT.	16'-6" x 3'-0"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Orange
LEGEND/BORDER	TYPE: Reflective
	COLOR: Black/Black

SYMBOL	ROT	X	Y	WID	HT
ARDOWN	0	78.4	8.7	30	20.6
ARDOWN	0	113.8	7.4	30	20.6

Panel Style: bottom_center.bsi
Dimensions are in inches.tenths
Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)				LENGTH	SERIES-SIZE
E	X	I	T		EM 2000
76.8	85.2	95.6	99.2	29.6	9.6
O	N	L	Y		E 2000
150.8	161.1	171.4	179.3	38.3	9.6

SIGN DETAIL



SIGN NUMBER	TC-SGN-17
WIDTH x HGHT.	18'-0" x 3'-0"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Orange
LEGEND/BORDER	TYPE: Reflective
	COLOR: Black/Black

SYMBOL	ROT	X	Y	WID	HT
ARDOWN	0	24	8.1	31.9	21.9

Panel Style: bottom_center.bsi
Dimensions are in inches.tenths
Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)				LENGTH	SERIES-SIZE
E	X	I	T		E 2000
80.7	91.3	104.2	108.4	36.7	12
O	N	L	Y		E 2000
129.4	142.3	155.1	165.1	47.9	12

AECOM
303 EAST WACKER DRIVE, SUITE 3400
CHICAGO, IL 60601-5276
PHONE: (312) 373-7700 FAX: (312) 373-6800

D16BW28-sht-Staging-Sign-Det-05.dgn	DESIGNED - AFC	REVISED - △1 05/27/2014	
USER NAME = gotelp2	DRAWN - NSA	REVISED -	
PLOT SCALE = 1.0000 ' / in.	CHECKED - KCF	REVISED -	
PLOT DATE = 5/24/2014	DATE - 04/28/14	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUGGESTED STAGES OF CONSTRUCTION AND TRAFFIC CONTROL
SIGN PANEL OVERLAY

SCALE: NTS | SHEET 1 OF 2 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	92F
		CONTRACT NO. 60W28		
		ILLINOIS FED. AID PROJECT		