

**REMOVAL AND PROPOSED SIGN SCHEDULE**

DESCRIPTION				LOCATION (STATION / OFFSET)		EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		SIGN PANEL TYPE 2	SIGN PANEL TYPE 3	WOOD SIGN SUPPORT	REMOVE SIGN PANEL ASSEMBLY - TYPE A	REMOVE SIGN PANEL ASSEMBLY - TYPE B	OVERHEAD SIGN STRUCTURE - SPAN, TYPE 1-A (4'-0" X 4'-6")	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)	REMOVE, STORE AND RE-ERECT SIGN PANEL (SPECIAL)	
LOCATION	SIGN NO.	LEGEND / DESCRIPTION	CODE	ACTION	BASELINE RAMP NW	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	(SQ FT)	(SQ FT)	(FOOT)	(EACH)	(EACH)	(FOOT)	(EACH)	(FOOT)	(EACH)	
RAMP NW	NW-01-WP	MERGE RIGHT	W4-3R	INSTALL NEW SIGN AND POST	1803+50			4.00	4.00	16		16.00							
	NW-02-TS(S)	SPEED LIMIT 35 MPH	R2-1	INSTALL NEW SIGN AND POST ON BARRIER WALL	1812+00			4.00	5.00	20								8.00	
	NW-03-TS(S)	SPEED LIMIT 35 MPH	R2-1	INSTALL NEW SIGN AND POST ON BARRIER WALL	1812+00			4.00	5.00	20								8.00	
	EX-01-OV	I-290 WEST EISENHOWER EXPY WEST SUBURBS DOWN ARROW		REMOVE EXISTING SIGN PANEL AND OVERHEAD SIGN STRUCTURE - SPAN	1818+33		16.00	10.50	-	-									
	EX-02-OV	CONGRESS PKWY/CHICAGO LOOP DOWN ARROW		REMOVE EXISTING SIGN PANEL AND OVERHEAD SIGN STRUCTURE - SPAN	1822+55		17.00	10.50	-	-									
	EX-01-SA	DOUBLE DOWN	W12-1	REMOVE EXISTING SIGN	1822+55	LT	4.00	4.00					1						
	EX-02-SA	CURVE RT	W1-2	REMOVE EXISTING SIGN	1823+88	LT	4.00	4.00						1					
	EX-02-SA	ADVISORY SPEED: 30 MPH	W13-1	REMOVE EXISTING SIGN	1823+88	LT	2.50	2.50							1				
	NW-03-OV	I-290 WEST EISENHOWER EXPY AURORA 45 DEGREE UP ARROWS	M1-1	INSTALL NEW SIGNS ON PROPOSED OVERHEAD SIGN STRUCTURE	1823+65.50				17.50	13.50		236.25				SEE OVERHEAD SIGN STRUCTURE FOR BILL OF MATERIALS FOR QUANTITY			
	NW-04-OV	CONGRESS EXPY EXIT ONLY		INSTALL NEW SIGNS ON PROPOSED OVERHEAD SIGN STRUCTURE	1823+65.50				16.50	7.00		115.50							
	NW-02-EXT	EXIT 51 I		INSTALL NEW SIGNS ON PROPOSED OVERHEAD SIGN STRUCTURE	1823+65.50				13.00	2.50		32.50							
	EX-03-SA	CHEVRON ALIGNMENT	W1-BR	REMOVE EXISTING SIGN	1827+18	LT	3.00	4.00							1				
	EX-04-SA	CHEVRON ALIGNMENT	W1-BR	REMOVE EXISTING SIGN	1828+22	LT	3.00	4.00							1				
	EX-01-CM	NOTICE, MOVE OVER - SLOW DOWN FOR STOPPED EMERGENCY OR MAINTENANCE VEHICLES, IT'S THE LAW			1833+88	LT			-	-									1
	ROUNDED TOTAL										56.0	384.5	16	1	3	-	1	16	1

NOTES:  
1. SEE OVERHEAD SIGN STRUCTURES GENERAL PLAN AND ELEVATION SHEET FOR OVER HEAD SIGN STRUCTURE QUANTITIES.

FILE PATH: J:\11080837\pernt\laesmonline\loc\DWG\DWG\Documents\Illinois\Transportation\60W28\Sign-Schedule-01.dwg



D:\60W28-ehi-Sign-Schedule-01  
 USER NAME: pmaerno  
 PLOT SCALE: 100.0000 \* / in.  
 PLOT DATE: 5/26/2014

DESIGNED - OPS  
 DRAWN - OPS/NSA  
 CHECKED - KCF  
 DATE - 04/28/14

REVISED - 5/27/2014  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SIGNING  
 SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	269
CONTRACT NO. 60W28				
ILLINOIS FED. AID PROJECT				