



STA RAMP NW	W		X		Y		PGL ELEV.	TOP OF WALL
	ELEV.	O/S	ELEV.	O/S	ELEV.	O/S		
1841+78.17	577.16	-19.64	579.14	-16.00	579.06	-12.00	578.82	582.64
1841+80.00	577.19	-19.64	579.09	-16.00	579.01	-12.00	578.77	582.59
1841+90.00	577.24	-19.64	578.83	-16.00	578.75	-12.00	578.51	582.33
1842+00.00	577.29	-19.64	578.61	-16.00	578.53	-12.00	578.29	582.11
1842+02.64	577.30	-19.63	578.55	-16.00	578.47	-12.00	578.23	582.05

FILE PATH: C:\Users\alvarez\Documents\60W28\Sheet\016-1705\WB-I-290.dgn



DIGW28-sht-Detail-89B.dgn  
 USER NAME: alvarez  
 PLOT SCALE: 40.0000 / in.  
 PLOT DATE: 5/27/2014

DESIGNED - NSA/OPS	REVISED - 5/27/2014
DRAWN - NSA/OPS	REVISED -
CHECKED - DBM	REVISED -
DATE - 04/28/14	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

ROADWAY DETAILS - CONCRETE BARRIER AT PIER 12 AND  
 TIE IN AT WB I-290  
 SCALE: N.T.S. SHEET 2 OF 2 SHEETS STA. TO STA.

F.A.J. RTE. 90/94/290	SECTION 2013-010R	COUNTY COOK	TOTAL SHEETS 747	SHEET NO. 644N
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60W28	

