

**TEMPORARY EROSION CONTROL SCHEDULE**

	MULCH, METHOD 2	MULCH, METHOD 4	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET FILTERS
STAGES	ACRE	ACRE	POUND	FOOT	EACH
STAGE 1	1.98	-	396	2592	33
STAGE 2	-	3.71	-	3135	64
STAGE 3A-3C	-	2.51	-	2487	20
STAGE 4	3.00	-	600	2004	8
ROUNDED TOTAL	5.00	6.25	996	10,218	125

**PERMANENT EROSION CONTROL SCHEDULE**

	TOPSOIL FURNISH AND PLACE, 4"	SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	EROSION CONTROL BLANKET	SODDING, SALT TOLERANT	SUPPLEMENTAL WATERING
PERMANENT CONDITION	SO YD	ACRE	POUND	POUND	SO YD	SO YD	UNIT
PERMANENT CONDITION	23706	4.77	1039	1039	23083	623	6.3
ROUNDED TOTAL	23706	5.00	1039	1039	23083	623	6.3

FILE PATH = p:\388035-p\m\escomon\me\local\AECOM\00\Documents\01\_Americas\Transportation\6269938\_Circle\Phase\_1\000\_CAD\005\_Roadway\Sheets\60W28\_Contract\0160W28-sht-Schedule-Eros-01



D160W28-sht-Schedule-Eros-01  
 USER NAME = ch1ue  
 PLOT SCALE = 100.0000' / in.  
 PLOT DATE = 4/28/2014

DESIGNED - AFC  
 DRAWN - AFC  
 CHECKED - DBM  
 DATE - 04/28/14

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**EROSION CONTROL SCHEDULES**

SCALE: NTS SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	198
CONTRACT NO. 60W28			ILLINOIS FED. AID PROJECT	