90% FED 10% STATE

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL	CONSTRUCTION CODE ROADWAY 0004 URBAN F.A.I. 270	BRIDGE 0010 URBAN S.N. 060-0350	BRIDGE 0010 URBAN S.N. 060-0351
*	81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	560	560		
*	81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	280		180	100
*	81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	80		40	40
*	81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	21600		10800	10800
*	81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	2		1	1
*	81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	8		4	4
*	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	10	10 △1		
*	81603112	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	14125	14125		
*	81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	12050		6025	6025
*	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	24100		12050	12050
*	82110008	LUMINAIRE, LED, ROADWAY, OUTPUT DESIGNATION H	EACH	146	70	39	37
*	83060450	LIGHT POLE, GALVANIZED STEEL, 45 FT. M.H., 15 FT. MAST ARM	EACH	59		30	29
*	83060550	LIGHT POLE, GALVANIZED STEEL, 50 FT. M.H., 15 FT. MAST ARM	EACH	71	70		1
*	83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	511	504		7

* SPECIALTY ITEM

△1 REVISED 6-22-2022

REV. - MS

MODEL: Default
FILE NAME: C:\ICS4PDF\12387145086_3\0876\90-sht-SOQ.dgn

HORNER & SHIFRIN
Teaming with: PARSONS

USER NAME = PWICS$	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 1.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 4/11/2022	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAI–270
SUMMARY OF QUANTITIES

SCALE: | SHEET 11 OF 15 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	60B-1	MADISON	875	14

CONTRACT NO. 76J90

ILLINOIS | FED. AID PROJECT