URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		FED 90% STATE 10% 0021					
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1039	1039					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	727	727					
20200100	EARTH EXCAVATION	CU YD	926	926					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE	CU YD	16193	16193					
	MATERIAL								
20400800	FURNISHED EXCAVATION	CU YD	5456	5456					
21001000	GEOTECHNICAL FABRIC FOR GROUND	SQ YD	4670	4670					
	STABILAZATION								
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	45948	45948					
25000210	SEEDING, CLASS 2A	ACRE	10	10					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	855	855					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	855	855					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	855	855					
25100115	MULCH, METHOD 2	ACRE	10	10					
25100630	EROSION CONTROL BLANKET	SQ YD	45948	45948					
28000305	TEMPORARY DITCH CHECKS	FOOT	1160	1160					
28000400	PERIMETER EROSION BARRIER	FOOT	5000	5000					

5

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		FED 90% STATE 10% 0021					
28000510	INLET FILTERS	EACH	12	12					
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	3892	3892					
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	15,194	15,194					
40603335	HOT-MIX ASPHALT SURFACE COURSE,	TON	1167	1167					
	MIX "D", N50								
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	10417	10417					
44004250	PAVED SHOULDER REMOVAL	SQ YD	14931	14931					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	46693	46693					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	7	7					
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1					
60260100	INLETS TO BE ADJUSTED	EACH	2	2					
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	5	5					
	(SPECIAL) TANGENT								
63200310	GUARDRAIL REMOVAL	FOOT	250	250					
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	85324	85324					
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	110	110					
14	* SPECIALTY ITEM								

Rev. 7-20-16

FILE NAME =	USER NAME = Bilgromka	DESIGNED - RWB	REVISED -
pw:\\ILDOT-EBONTEC.illinois.gov:PW\IDOT\Documents\IDOT Offices\District 1\Projects\D128515\CADData\Design\D128515GR-SHEET.dgn		DRAWN - RWB	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/10/2016	DATE - 4/13/2016	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 113 (COMET DRIVE TO KANKAKEE COUNTY LINE)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 1 OF 2 SHEETS | STA. | TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
299	2015-0131	WILL	156	3
		CONTRACT NO. 62A66		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT