

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1.	COVER SHEET
2.	INDEX OF SHEETS, STANDARDS, GENERAL NOTES & SIGNATURE
3.	SUMMARY OF QUANTITIES
4.	PATCHING SCHEDULE
5.	PROJECT LOCATION MAP
6.	PROJECT TYPICAL SECTIONS

STANDARDS

STANDARD NO.	DESCRIPTION
442001-04	CLASS A PATCHES
701101-05	OFF-RD OPERATIONS MULTILANE, 15' TO 24' FROM EDGE OF PAVEMENT
701106-02	OFF-RD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
701400-08	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701406-10	LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
701411-09	LANE CLOSURE, MULTILANE AT ENTRANCE OR EXIT RAMP FOR SPEEDS > 45 MPH
701446-07	TWO LANE CLOSURE, FREEWAY/EXPRESSWAY
701456-03	PARTIAL EXIT RAMP CLOSURE, FREEWAY/EXPRESSWAY
701901-05	TRAFFIC CONTROL DEVICES
701401-09	LANE CLOSURE, FREEWAY/EXPRESSWAY

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
DISTRICT 6**

EXAMINED <u>May 23rd</u> 20 <u>16</u> <i>John C. [Signature]</i> ENGINEER OF OPERATIONS
EXAMINED <u>May 19</u> 20 <u>16</u> <i>Ron [Signature]</i> ENGINEER OF PROJECT IMPLEMENTATION
EXAMINED <u>May 19</u> 20 <u>16</u> <i>Julius P. [Signature]</i> ENGINEER OF PROGRAM DEVELOPMENT

MIXTURE REQUIREMENTS		
THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT		
LOCATION:	SHOULDER REPAIR	STRUCTURE REPAIR
MIXTURE USE(S):	LOWER LIFT	TOP LIFT
AC/PG:	PG 64-22	PG 64-22
DESIGN AIR VOIDS:	4.0% @ N50	4.0% @ N50
MIXTURE COMPOSITION:	IL 19.0	IL 9.5
FRICTION AGGREGATE:	N/A	MIX "C"

Rev. 7-20-16

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0-01623-6004	0-01623-6004
				100% STATE	100% STATE
				MONTGOMERY	SANGAMON
				ROADWAY	ROADWAY
				0005	0005
				RURAL	RURAL
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	304	200	104
44200612	CLASS A PATCHES, TYPE III, 13 INCH	SQ YD	36	16	20
44200614	CLASS A PATCHES, TYPE IV, 13 INCH	SQ YD	386.7	106.7	280
44213000	PATCHING REINFORCEMENT	SQ YD	726.7	322.7	404
44213200	SAW CUTS	FOOT	3,394	1,828	1,566
44213204	TIE BARS 3/4"	EACH	135	36	99
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	18	10	8
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	0.5	0.5
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0	0.5	0.5
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1.0		1.0
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1.0	0.5	0.5
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30.0	15.0	15.0
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2.0	1.0	1.0
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.5	0.5
X4820110	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	SQ YD	100.0	50.0	50.0
X7010410	SPEED DISPLAY TRAILER	CAL MO	1.0	0.5	0.5

⚠
⚠
⚠
⚠
⚠

Rev. 7-20-14

FILE NAME *	USER NAME * sharp1d	DESIGNED -	REVISED -
S:\CONTRACTMAINT\CAD\72J26 - 1-55 - CLASS	A PATCHING - MONTGOMERY-SANGAMON CD\PLANS	DESIGNED BY -	REVISED BY -
		DATE -	DATE -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	D6 PATCHING 2017-4	MONT/SANG	6	3
CONTRACT NO. 72J26			ILLINOIS FED. AID PROJECT	

SCALE: SHEET OF SHEETS STA. TO STA.