

SUMMARY OF QUANTITIES

CCDE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION CODE	
				80% FED LOCAL	20% VILLAGE
				ROADWAY 0004 URBAN	NON-PARTICIPATING URBAN
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,560	4,560	
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	13,806	13,806	
72000100	SIGN PANEL - TYPE 1	SQ FT	109	109	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	9	9	
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	4	4	
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	33	33	
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	3	3	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	150	150	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12,054	12,054	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,362	1,362	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,144	1,144	
78000850	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	136	136	
* SP 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	
81028190	UNDERGROUND CONDUIT, GALVANIZED STEEL, 1 1/2" DIA.	FOOT	140	140	

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION CODE	
				80% FED LOCAL	20% VILLAGE
				ROADWAY 0004 URBAN	NON-PARTICIPATING URBAN
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	315	315	
* SP 81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	2	2	
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	80	80	
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2,035	2,035	
* SP 81603100	UNIT DUCT, 600V, 4-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	3,500	3,500	
81702160	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO.2	FOOT	771	771	
* 82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1	1	
* SP 83001200	LIGHT POLE, ALUMINUM, 35 FT. M.H., 6 FT. DAVIT ARM	EACH	19	19	
* SP 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	152	152	
SP Z0004530	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SQ YD	96	96	
SP Z0004538	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 10"	SQ YD	106	106	
SP Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
SP Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	312	312	
* SP Z0033058	POST MOUNTED FLASHING BEACON INSTALLATION (SPECIAL)	EACH	2	2	
SP Z0062456	TEMPORARY PAVEMENT	SQ YD	1,293	1,293	
# SP Z0076800	TRAINEES	HOUR	500	500	

* INDICATES SPECIALTY ITEM # CONSTRUCTION TYPE CODE 0042
 SP INDICATES ITEMS COVERED BY SPECIAL PROVISIONS

* INDICATES SPECIALTY ITEM # CONSTRUCTION TYPE CODE 0042
 SP INDICATES ITEMS COVERED BY SPECIAL PROVISIONS

COPYRIGHT © 2016 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGNER
 LICENSE NO. - 184-000121 - EXPIRES 4/30/2017
 2334343
 1/21/2016
 I:\Mekano\PL\DV\40988-127\1\CA00\Sheets-Ph2\40988SHT_500.dgn

BAXTER & WOODMAN	DESIGNED - CAC	REVISED - MWH 7-21-16
	DRAWN - CJC	REVISED -
	CHECKED - ADJ	REVISED -
	DATE - 04-29-16	FILE - 140988SHT_500.dgn

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE STA. TO STA.

F.A.P. RTE. 503	SECTION 15-00061-00-WR	COUNTY WILL	TOTAL SHEETS 88	SHEET NO. 7
CONTRACT NO. 61C98			FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT M-40031531	