

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN				TOTAL QUANTITIES	UNIT	TOTAL QUANTITIES	URBAN							
				I000-2A	IL 83 AT IL 132	LAKE VILLA 100%	INTER-CONNECT IL 132 AT DEEP LAKE				I000-2A	IL 83 AT IL 132	LAKE VILLA 100%	INTER-CONNECT IL 132 AT DEEP LAKE				
* M8100100	CONDUIT IN TRENCH, 100MM DIA., GALVANIZED STEEL	METER	1.50		1.50				M4428042	CLASS D PATCHES, TYPE I, 305MM	SQ M	30	30					
* M8101090	CONDUIT PUSHED, 100MM DIA., GALVANIZED STEEL	METER	197		197				M4428242	CLASS D PATCHES, TYPE II, 305MM	SQ M	306	306					
* M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	448		290		158		M4428342	CLASS D PATCHES, TYPE III, 305MM	SQ M	540	540					
* M8731210	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	METER	301		301				M4428442	CLASS D PATCHES, TYPE IV, 305MM	SQ M	612	612					
* M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	600		600				MX033796	DRIVING AND FILLING SHELLS	METER	872	872					
* M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	800		800				MX033796	BRIDGE DECK LATEX CONCRETE OVERLAY (65MM)	SQ M	2043	2043					
* M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	180		180				MX033796	HOT MIX ASPHALT SURFACE REMOVAL, 30MM	SQ M	1545	1545					
* M8731300	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	METER	708		708				MX033797	HOT-MIX ASPHALT SIDEWALK	SQ M	1545	1545					
* M8731800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	METER	30		30				MZ006012	BRIDGE DECK HYDRO-SCARIFICATION (15MM)	SQ M	1624	1624					
* M8750510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 4.85 METER	EACH	2		2				M6024065	INLETS, TYPE A, 600MM DIAMETER WITH TYPE 24 FRAME AND GRATE	EACH	1	1					
* M8770065	STEEL MAST ARM ASSEMBLY AND POLE, 11.58 METER	EACH	2		2				* M8780420	CONCRETE FOUNDATION, TYPE E 1060MM DIAMETER	METER	12.80		12.80				
* M8780100	CONCRETE FOUNDATION, TYPE A	METER	7.20		7.20				M5120250	FURNISHING SOLDIER PILES (HP SECTIONS)	METER	31.20	31.20					
* M8780150	CONCRETE FOUNDATION, TYPE C	METER	1.20		1.20				MX620237	CATCH BASINS, TYPE C, 600MM DIAMETER, WITH TYPE 8 GRATE	EACH	6	6					
* M8780400	CONCRETE FOUNDATION, TYPE E 750MM DIAMETER	METER	9.20		9.20				* M8770105	STEEL MAST ASSEMBLY AND POLE, 17.07 METER	EACH	1		1				
* M8860100	DETECTOR LOOP, TYPE I	METER	220		220				* M8770115	STEEL MAST ASSEMBLY AND POLE, 18.28 METER	EACH	1		1				
MX030063	STORM SEWERS (WATER MAIN REQUIREMENTS) 300mm	METER	105.50			105.50												
MX030199	TEMPORARY PAVEMENT	SQ M	1565	1565														
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	24.87	9.20			15.67											
MX032179	SILICONE JOINT SEALER, 25MM	METER	108.30	108.30														
* MX032922	ELECTRIC CABLE IN CONDUIT, GROUNDING NO. 6 1C	METER	202		202													
MX033276	TEMPORARY SOIL RETENTION SYSTEM	SQ M	27	27														
* MX033445	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU M	8.20	8.20														
MX033710	STEEL CASING PIPE, AUGERED AND JACKED, 600mm	METER	16.50	16.50														
MX606050	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-5.60	METER	44	44														
* MX873030	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	METER	103			103												
MZ001050	AGGREGATE SUBGRADE 300mm	SQ M	8107	8107														
MZ016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ M	20	20														
MZ016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ M	20	20														
Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL II	EACH	1				1											
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1													
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	12	12														
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	33	33														
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1													
* X8620020	UNINTERRUPTABLE POWER SUPPLY	EACH	1		1													
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1														
Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5														