



SECTION COUNTY RTE. SHEETS NO. 866 4N-1 LAKE 165 12 STA. TO STA.

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

CONTRACT NO. 60931

## LEGEND

- 1. EXISTING HOT-MIX ASPHALT SURFACING, 114mm
- 2. EXISTING HOT-MIX ASPHALT BASE COURSE, 260mm
- 3. EXISTING PCC BASE COURSE, 260mm
- 4. EXISTING CURB AND GUTTER, TYPE B-15.30
- 5. EXISTING SIDEWALK
- 6. EXISTING AGGREGATE BASE COURSE, TYPE B
- 7. PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, 50mm
- 8. PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 50mm
- 9. PROPOSED HMA BASE COURSE, 270mm
- 10. PROPOSED AGGREGATE SUBGRADE, 300mm
- 11. PROPOSED COMBINATION CONCRETE CURB AND GUTTER TYPE B-15.60
- 12. PROPOSED PCC SIDEWALK, 125mm
- 13. PROPOSED HOT-MIX ASPHALT SIDEWALK, 150mm

## NOTE:

"THE CONTRACTOR SHALL MILL FIRST PRIOR TO PATCHING".

ADDITIONAL SUB-BASE GRANULAR MATERIAL UNDER PROPOSED CURB AND GUTTER SHALL NOT BE PAID FOR SEPARATELY BUT WILL BE CONSIDERED AS INCLUDED IN THE COST PER SQUARE METER OF SUB-BASE GRANULAR MATERIAL, TYPE B. 100mm

ANY SAW CUTTING REQUIRED TO REMOVE AN ITEM ADJACENT TO AN ITEM TO BE SAVE WILL BE CONSIDERED AS PART OF THE REMOVAL ITEM AND WILL NOT BE PAID FOR SEPARATELY.

PLACEMENT OF TIE BARS FOR COMBINATION CONCRETE CURB & GUTTER SHALL NOT BE PAID FOR SEPARATELY BUT WILL BE CONSIDERED AS INCLUDED IN THE COST PER LINEAR METER OF COMBINATION CONCRETE CURB & GUTTER, TYPE B-15.60

DENOTES REMOVAL ITEM SEE PLAN SHEETS FOR EXACT LOCATIONS.

## NOTE:

"FOR SECTIONS WITH PROFILE CORRECTION ADD HMA BINDER COURSE, IL-19.0, N70".

## PIPE UNDERDRAIN LOCATIONS:

IL 83 STA. 2+825 TO STA 2+850, LT STA. 2+900 TO STA. 2+925, RT. STA. 2+975 TO STA. 3+000, LT. STA. 3+050 TO STA. 3+075, LT.

IL 132 STA. 0+800 TO STA. 0+825, RT. STA. 1+125 TO STA. 1+150, LT

REVISIONS				
NAME	DATE	ILLINOIS DEPAR	TMENT OF TRANSPORTATION	
		IL RTE 83 (MILWAKEE AVE) AT IL RTE 132 (GRAND AVE)		
		PROPOSED TYPICAL SECTION		
		SCALE:	DRAWN BY	
		DATE: 3/12/2010	CHECKED BY	

c:\pw\_work\PWIDOT\GALBANNB\dOI08064\PI04498-design2.dgm