

## NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

ı	TILE NAME =	USER NAME = galbannb	DESIGNED -	REVISED -	R. MIRS 09-15-97			ARTERIAL ROAD		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET SHEETS NO.
· c	:\pw_work\PWIDOT\GALBANNB\d0175346\Dis	Std.dgn	DRAWN -	REVISED -	- R. MIRS 12-11-97			INFORMATION SIGN		866	4N-1	LAKE	165 131
		PLOT SCALE = 51.3436 '/ IN.	CHECKED -	REVISED -	T. RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION						CONTRACT	NO. 60931
- 1		PLOT DATE = 3/12/2010	DATE -	REVISED -	- C. JUCIUS 01-31-07		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA.	TO STA.	FED. ROAD DIST.	NO. 1   ILLINOIS   FED. AI	D PROJECT	