

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	2010-052 DTR	WILL	210	15
STA.		TO STA.		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

STATION	OFFSET		TREE REMOVAL			
			EXISTING ROW		PROPOSED ROW	
			LEFT FEET	RIGHT FEET	20100110 6 TO 15 UNITS	20100210 OVER 15 UNITS
<b>84TH AVENUE</b>						
701+55	34				15	
701+55	34				15	
701+55	34				15	
701+55	34				15	
701+71	35				7	
701+71	35				7	
701+71	37				12	
701+71	37				12	
702+58		43			15	
<b>HILLSIDE ROAD</b>						
747+84	31		7			
748+02	30		9			
748+13	29		11			
748+30	29		10			
748+40	32		6			
748+40	32		6			
748+88	26		9			
748+90	26		8			
748+90	28		9			
<b>80TH AVENUE</b>						
NONE						
<b>HUNTER WOODS DRIVE/FRANKFORT SQUARE</b>						
NONE						
<b>HARLEM AVENUE</b>						
NONE						
<b>TOTALS</b>						
			1300	458	701	153
<b>GROWTH FACTOR</b>			1.5	1.5	1.5	1.5
<b>TOTALS</b>						
			1950	687	1052	230

NOTE:  
THE ORIGINAL TREE SURVEY FOR SECTION BETWEEN STA. 424+60 AND STA. 591+10 WAS PERFORMED IN 2002. A GROWTH FACTOR HAS BEEN APPLIED TO THE TOTAL QUANTITY TO ACCOUNT FOR THE INCREASED TREE SIZES. PAYMENT FOR TREE REMOVAL SHALL BE BASED ON THE ACTUAL MEASUREMENT OF THE TREE AT THE TIME OF REMOVAL, AS DEFINED BY ARTICLE 201.10 OF THE STANDARD SPECIFICATIONS.

STATION	LEFT FEET	RIGHT FEET	TREE REMOVAL, ACRES (ACRES)
20100500			
ROUTE 30			
439+00		86	0.1
<b>93RD AVENUE</b>			
548+00		85	0.1
<b>TOTAL</b>			
			0.2
<b>ROUNDED TOTAL</b>			
			0.25

STATION	LEFT FEET	RIGHT FEET	METAL POST - TYPE A (FOOT)
72900100			
ROUTE 30			
440+15		60	30
442+52		57	30
498+34		54	30
<b>TOTAL</b>			
			90

STATION	LEFT FEET	RIGHT FEET	SELECTIVE CLEARING (UNIT)
Z0064800			
ROUTE 30			
439+00		85	7
499+00		55	5
515+00		55	6
520+00		68	4
524+00		61	4
<b>93RD AVENUE</b>			
548+00		85	17
<b>HILLSIDE ROAD</b>			
748+00	40		10
<b>TOTAL</b>			
			53

STATION	LEFT FEET	RIGHT FEET	SIGN PANEL - TYPE 2 (SQ FT)
72000200			
ROUTE 30			
440+15		60	18
442+52		57	18
498+34		54	18
<b>TOTAL</b>			
			54

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		U.S. ROUTE 30 SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE 5/5/2010 DRAWN BY DJK CHECKED BY JRV